

BHARAT HEAVY ELECTRICALS LIMITED
RAMACHANDRAPURAM :: HYDERABAD-502032
(TOWNSHIP ADMINISTRATION)

Tender Notice No.
HY/TA/OT-04/2015-16

Schedule - A Price bid

Date: 04.09.2015, Item. No. 02

Name of work: Providing chain link mesh fencing to Type-III and Type IV Blocks in NH-I,NH-III NH-IV and TC Area in Township

Sl. No	Description	Total quantity	Unit	Rate	Amount (in Rs.)
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means over areas (exceeding 30 cm in depth. 1.5 m in width as well as 10 Sqm on plan) including disposal of excavated earth, within a lead of 50 m and lift up to 1.5 m disposed earth to be levelled and neatly dressed for all kind of soils etc. compete all as directed by Engineer-in-charge	151.00	One Cum	129.35	19531.85
2	Conveyance of excavated earth including loading,unloading and disposal at places with in a distance of 2 kms etc. compete all as directed by Engineer-in-charge.	113.25	One Cum	93.94	10638.71
3	Reinforced cement concrete work in walls 1:2:4 (1cement 1 coarse sand 2 and 4 grade stone aggregate 20mm nominal size) (any thickness) including attached pilasters buttresses plinth and string course fillets columns pillars piers abutments posts and struts etc. (for casting poles as specified by Engineer In-charge)	53.50	One Cum	3486.40	186522.40
4	Reinforcement Cold twisted bars for RCC work including straightening, cutting bending placing in position and binding all complete. (Steel will be free issue from BHEL store)	9216.00	kg	7.37	67921.92
5	Centering and shuttering including strutting propping etc. and removal of form work for :Columns piers, abutments, pillars, posts and struts.	2278.00	One Sq.M	365.60	832836.80

Sl. No	Description	Total quantity	Unit	Rate	Amount (in Rs.)
6	Encasing Boundary poles with cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 12.5 mm nominal size) including centring and shuttering but excluding cost of reinforcement etc. complete all as directed by Engineer-in-charge.	107.00	One Cum	3083.39	329922.73
7	Erection RCC poles/M.S angles posts in position by conveying the same to the places as directed.	2839.00	Each	32.99	93658.61
8	Filling available excavated earth (excluding rock) in trenches, plinth sides of founding each deposited layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, lead upto 50m and lift up to 1.5m,.	37.75	One Cum	83.80	3163.45
9	Labour charges for fixing of chain link Mesh to the existing poles with G.I binding wire,applying sufficient pull, by engaging required skilled manpower including cost of G.I binding wire and cost of transportation from BHEL stores to the required places all as directed by Engineer-in-charge. (Chain link Mesh will be issued free of cost from BHEL stores).	18002.50	One Sqm	32.00	576080.00
10	Steel work welded in built up sections/framed work including cutting,hoisting,fixing in position and applying a priming coat of approved steel primer using structural steel etc as required in gratings,frames,guard ladder,railings,brackets,gates and simillar works including locking arrangemnet by providing Aldrop MS powder coated 300 mm long.	18875.00	Kg	27.10	511512.50
10a	MSAldrop powder coated 300 mm long.	151.00	Each	134.00	20234.00

Sl. No	Description	Total quantity	Unit	Rate	Amount (in Rs.)
11	Surface dressing of the ground including removing vegetation and inequalities not exceeding 15cm deep and disposal of rubbish, lead up to 50 m and lift up to 1.5m for all kinds of soil all as directed by Engineer-in-charge.	36135.00	One Sq.M	9.35	337862.25
Total Rupees Twenty nine lakhs eighty nine thousand eighty hundred eight five and paise twenty two only)					2989885.22
Cement & Steel will be free issue from BHEL Stores					
Tender %	In words		Figures		
Excess					
Less					
Estimate					

Notes:

1	A penalty of 0.5% of the gross value of work will be levied for every week's delay of work subject to a maximum penalty of 10% of the gross value of work.
2	The tender % age quoted by the contractor shall be inclusive of all taxes and duties other than service tax as applicable from time to time.
3	Service tax if paid by the contractor with respect to this work will be reimbursed by BHEL on production of documentary evidence for having paid the service tax by the contractor.
4	All the bills of the contractors will be cleared subject to the production of clearance certificate by the contractors in respect of compliance of all statutory requirement, issued by IR section of HR department BHEL.
5	The agency shall submit the I.R. clearance certificate for the above work and arrange to get the final bill sent to Finance within one month from the actual date of completion of work.
6	The maintenance period of the work is 12 months . The security deposit will be released after satisfactory completion of the work and after getting I.R clearance and payment of final bill.