

BHARAT HEAVY ELECTRICALS LIMITED
RAMACHANDRAPURAM :: HYDERABAD-502032
(TOWNSHIP ADMINISTRATION)

Schedule - A Price bid

Tender Notice No.
HY/TA/OT-05/2015-16
Date: 09.09.2015, Item. No. 02
Name of work: Periodical External Painting and other associated Civil works to Type-III & IV quarters in NH-I area in Township

SL.No	Description of Item	Qty	Unit	Rate	Amount
1	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50mtr lead.	714.00	Sqm	15.00	10,710.00
2	20mm cement plaster of mix, 1:4(1 cement 4 coarse sand)	714.00	Sqm	137.28	98,016.62
3	Finishing walls with Acrylic smooth exterior paint of required shade, old work (two or more coats applied @ 1.67ltr/10sqm) on excising cement paint surface) including necessary preparation surface complete all as directed by Engineer.	68718.00	Sqm	48.30	3,319,079.40
4	Applying one coat of water thinnable cement primer of approved brand and manufacture on wall surface including necessary preparation surface complete all as directed by Engineer.	20615.40	Sqm	25.50	525,692.70
5	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade,one or more coats on old work including necessary preparation surface complete all as directed by Engineer.	29310.00	Sqm	39.30	1,151,883.00
6	Brick work FPS brick of class designation 75 in superstructure above plinth level up to floor V level in all shapes and sizes in cement mortar 1:6(1cement :6 coarse sand)	5.00	Sqm	3,513.18	17,565.91
7	Arresting the growth of trees along the walls of the buildings in Township by applying gylcil with ammonia of required quantity till the tree is dried and removing the dried tree along with roots (which are not able to be removed by the painters with hand) etc complete all as directed by Engineer.	80.00	One Sqm	121.71	9,736.80
8	Providing and applying Cement base wall care putty of 2mm thickness over plastered surface to prepare the surface even and smooth complete.	510.00	One Sqm	135.89	69,303.90
9	Demolishing RCC work manually/ by mechanical means including stacking of steel bars and disposal of unserviceable material within 50mtr lead as per direction of engineer in charge	8.00	Cum	978.95	7,831.60
10	Extra for cutting reinforcement bars manually by mechanical means in RCC or RB work (payment shall be made on the cross sectional area of RCC or RB work) as per direction of engineer in charge	165.00	Sqm	325.15	53,649.75
11	Providing guttas in triangular shape of base 150 mm and height 150 mm with cement mortar 1:4, including fine finishing, cost of all materials etc complete all as directed by Engineer-in-charge.	920.00	Rmt	4.67	4,299.85
12	18mm thick plain cement mortar band in cement mortar 1:4(1 cement 4 fine sand,) Flush Band	920.00	Rmt	2.46	2,261.94

SL.No	Description of Item	Qty	Unit	Rate	Amount
13	Reinforced cement concrete work in walls (any thickness) including attached pilasters buttresses plinth and string course fillets columns pillars piers abutments posts and struts etc. up to floor five level excluding cost of cantering shuttering finishing and reinforcement,1:2:4(1cement 2 coarse sand 4 grade stone aggregate 20mm nominal size)	3.00	Cum	3,486.40	10,459.20
14	White washing with lime to give an even shade :Old work (one or more coats) including scraping complete all as directed by Engineer.	20700.00	Sqm	4.35	90,045.00
Total (Rupees fifty three lakhs seventy thousand five hundred thirty five and Paise sixty six only)					5,370,535.66

Cement & Steel will be free issue from BHEL Stores

Tender %	In words	Figures
Excess		
Less		
Estimate		

Notes:

1	A penalty of 0.5% of the gross value of work will be levied for every week's delay of work subject to a maximum penalty of 10% of the gross value of work.
2	The tender % age quoted by the contractor shall be inclusive of all taxes and duties other than service tax as applicable from time to time.
3	Service tax if paid by the contractor with respect to this work will be reimbursed by BHEL on production of documentary evidence for having paid the service tax by the contractor.
4	All the bills of the contractors will be cleared subject to the production of clearance certificate by the contractors in respect of compliance of all statutory requirement, issued by IR section of HR department BHEL.
5	The agency shall submit the I.R. clearance certificate for the above work and arrange to get the final bill sent to Finance within one month from the actual date of completion of work.
6	The maintenance period of the work is 12 months . The security deposit will be released after satisfactory completion of the work and after getting I.R clearance and payment of final bill.