

BHARAT HEAVY ELECTRICALS LIMITED

RAMACHANDRAPURAM :: HYDERABAD-502032

(TOWNSHIP ADMINISTRATION)

Price Bid - Part - B - Item No.01

Tender Notice No:
HY/TA/OT-13/2014-15
Date: 27.01.2014, Item No. 01

Name of work: Renovation works of Corridor in General Hospital					
Sl. No	Description of item	Qty	Unit	Rate	Amount
1	Dismantling stone slab flooring laid in cement mortar including stacking of serveceable material and disposal of unserveceable material within 50mtr lead	1500.00	Sqm	40.50	60,750.00
2	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50mtr lead	1800.00	Sqm	8.20	14,760.00
3	Plastering in cement mortar 1:6, 20 mm thick including curing, cost of all materials, etc complete all as directed by Engineer-in-charge.	1800.00	Sqm	65.83	118,494.00
4	Providing and laying of polished granite stone flooring over a cement base of 1:6 , 20mm thick including edge moulding and neat laying as directed by Engineer in charge.	1500.00	Sq.M	1613.76	2,420,640.00
5	Providing and laying polished vitrified floor/ wall tiles in different size (thickness to be specified by the manufacture) with water absorption's less than 0.08% and conforming to IS 15622 of approved make in all colours and shade, laid on 20mm thick cement mortar 1:4(1cement 4 coarse sand) including grouting the joints with white cement and matching pigment etc. complete Size of tile 600x600 mm	1800.00	sqm	966.93	1,740,474.00
6	Providing Altek lappam two coats ove a base of primer on new / old plastered surfaces as per the directions of Engineer In charge.	2200.00	Sq.M	47.20	103,840.00
7	Applying two or more coats of Acrylic paint of approved shade and brand including scraping, cost of all materials and over an under coat of suitable shade with ordinary paint/primer of approved brand and manufacture etc., complete all as directed by Engineer-in-charge.	2200.00	Sqm	50.40	110,880.00
				Rs.	4,569,838.00

Signature of the Contractor

Issuing Authority

Tender %	In words	Figures
Excess		
Less		
Estimate		
Notes		
1	A penalty of 0.5% of the gross value of work will be levied for every week's delay of work subject to a maximum penalty of 10% of the gross value of work.	
2	The tender % age quoted by the contractor shall be inclusive of all taxes and duties other than service tax as applicable from time to time.	
3	Service tax if paid by the contractor with respect to this work will be reimbursed by BHEL on production of documentary evidence for having paid the service tax by the contractor.	
4	All the bills of the contractors will be cleared subject to the production of clearance certificate by the contractors in respect of compliance of all statutory requirement, issued by IR section of HR department BHEL.	
5	The agency shall submit the I.R. clearance certificate for the above work and arrange to get the final bill sent to Finance within one month from the actual date of completion of work.	
6	The maintenance period of the work is 12 months . The security deposit will be released after satisfactory completion of the work and after getting I.R clearance and payment of final bill.	
7	Cement will be free issued from Departmental Stores.	