

PSGSG 14-15 /003	SPECIFICATIONS FOR "FALSE CEILING AND PARTIONING MATERIAL & INSTALLATION"	Drg.No.	-
		Date	26.05.14
		Rev	01
		Product	UHV Lab
3.0	Fabrication of frame work (including structural steel sections etc), erection of frame work, applying metal primer and synthetic enamel paint, cutting, lead and lift and fixing of shera boards, sand papering to get smooth surface and final plastic emulsion painting.		
4.0	The dimensions of the room are length of 26metres, width of 9.5 metres and height of 11.0 metres approximately.		
5.0	The partition area is as per the enclosed drawing (Annexure-A) to a height of 11 metres and length of 26 metres on both sides of the room. The PPS (Positive Pressure Systems should be flushed while doing partitioning on both sides.		
6.0	The False ceiling area is as per the enclosed drawing (Annexure-A) for length of 26 metres and width of 9.5 metres.		
7.0	The supplier may visit UHV laboratory in BHEL R&D for further intrinsic details and if any further clarifications required contact Lab personnel before submitting the offer.		
Page 2/2	PSGSG 14-15 /003	Signature	