


	TITLE :	SPEC. NO. PE-TS- 999-165-N002
	STANDARD TECHNICAL SPECIFICATION	VOLUME : II B
	SELF - CLEANING FILTERS	SECTION : D
		REV. NO. 0 DATE : 02.12.2009
		SHEET 2 OF 10

wood pieces etc. The performance of the filter shall be continuous with minimum number of flushing / backwashing operations.

3.02.02 The self-cleaning filter shall be designed such that the pressure drop across the filter (i.e., between inlet and outlet connections) under clean conditions and partially (50%) choked conditions shall not be more than those specified in Data Sheet -A.

3.02.03 Unless otherwise specified in Data Sheet -A, debris discharge / wash water flow rate during flushing/back washing operation shall be limited to 10% of the total flow rate and flushing / backwashing operation shall be completed within a period of maximum three (3) minutes. The pressure drop across the debris filter during flushing/backwashing operation shall not be morethan the pressure drop under partially (50%) choked condition.

3.02.04 The coarse particles and floating matter accumulating at the filter section/screen are flushed out of the system by the debris flushing / backwash unit such that the pressure drop across the filter after flushing / backwashing, shall not be more than the pressure drop under clean conditions.

3.03.00 **Operational Requirement**

The self-cleaning filter and other accessories shall be designed for the following flushing/backwashing operation modes :

3.03.01 Complete automatic flushing/backwashing operation effected by the following :-

- ◆ differential pressure measuring system at a pre-determined differential pressure across the filter
- ◆ adjustable timer (0-24 hours)
- ◆ push button (for manual initiation of sequential flushing / backwashing)


3.03.02 Manual operation in the event of failure of control system.

3.04.00 **Filter Housing / Body**

3.04.01 The self-cleaning filter housing/body shall be designed and manufactured as per the applicable codes for pressure vessels. However in no case thickness of housing/ body shall not be less than connecting pipe thickness as specified in Data Sheet-A. It shall house the filter section / screen assembly and shall have flanged inlet, outlet, flushing / debris discharge openings and pressure measuring tappings etc.

3.04.02 In design of filter housing / body due attention shall be given for easy removal and replacement of filter section / screen assembly.

3.04.03 The filter shall be provided with inspection hole with bolted cover.

	TITLE :	SPEC. NO. PE-TS- 999-165-N002
	STANDARD TECHNICAL SPECIFICATION	VOLUME : II B
	SELF - CLEANING FILTERS	SECTION : D
		REV. NO. 0 DATE : 02.12.2009
		SHEET 3 OF 10

3.04.04 The filter body / housing shall be provided with vent and drain connections with isolating valves. It shall be possible to drain unfiltered and filtered water.

3.04.05 If specified in Data Sheet-A, filter body/housing shall be epoxy painted.

3.05.00 **Filter Section / Screen assembly.**

3.05.01 The filter section/screen shall be designed for the maximum differential pressure across the filter and shall be securely positioned by a supporting cage and shall be securely mounted in the housing or body.

3.05.02 The perforation/mesh size of the filter section shall not be more than that specified in Data Sheet-A.

3.05.03 The arrangement of the filter section shall be such that there shall be no forced accumulation of debris.

3.06.00 **Differential Pressure Measuring System**

3.06.01 The self-cleaning filter shall be provided with a measuring system for differential pressure across the filter section/screen, to check debris accumulation and to initiate flushing / backwashing operation. This shall consist of a separate differential pressure transmitter for normal automatic flushing operation and separate DP Switch as a backup in the event of DPT failure, a differential pressure gauge for manual observation with adequate no. of tappings with isolating valves and equalizing valves.

3.06.02 The contacts for differential pressure transmitter, differential pressure switch and for differential pressure gauge shall be independent so that in the event of failure of one, the other is available .


3.06.03 The differential pressure measuring system shall also be equipped with built in flushing arrangement consisting of flushing pump, valves and associated piping, to prevent blockage of the system with any debris. Unless otherwise specified in Section C, water required for flushing the differential pressure measuring system shall be taken from downstream side of the strainer/ screen.

3.07.00 **Flushing / Backwash Unit :**

3.07.01 The self-cleaning filter shall be provided with suitable flushing/backwash unit (to be installed at ground floor) and debris discharge/backwash outlet valve with associated actuator to flush out the accumulated debris / sludge.

3.07.02 The flushing pump shall be provided with mechanical seals to the extent possible. If gland packing is provided it should be of good quality to prevent leakage of water from pump glands.

3.07.3 The flushing backwash unit shall be either fixed type with actuator operated

	TITLE :	SPEC. NO. PE-TS- 999-165-N002
	STANDARD TECHNICAL SPECIFICATION	VOLUME : II B
	SELF - CLEANING FILTERS	SECTION : D
		REV. NO. 0 DATE : 02.12.2009
		SHEET 4 OF 10

flushing valves or electric motor driven (through reduction gear) backwash rotor. In case of backwash rotor, it shall be fitted with removable shoes for smooth and close running contact with the filter section/screen and to prevent the unfiltered water from bypassing to waste.

3.07.04 If any water is to be injected for backwashing the filter section/screen, water shall be taken from down-stream side of the filter section/ screen with necessary pump, valves and piping for water injection supplied by the bidder.

3.07.05 View glass to be provided in debris outlet pipe to monitor the flushing of debris.

3.08.00 **Valves**

The flushing valves (if any,) the debris discharge/backwash outlet valve, isolation, vent and drain valves shall conform to appropriate codes / standards. The debris discharge/backwash outlet valve shall be larger than the debris discharge/back wash outlet pipe.

3.09.00 **Instrumentation and Control System**

3.09.01 Complete instrumentation and control system for automatic flushing / backwashing operation, protection, interlocking, indication/annunciation of high differential pressure and other malfunctions etc. shall be provided. This shall consist of adequate operational hardware, local control panel and interconnecting control and power cabling between the control panel and the self-cleaning filter and its associated electrical devices.

3.09.02 The control panel shall house all necessary instruments, indicating/ annunciation lamps, alarms, differential pressure indicator, timer, function selector switches, relays, protection and interlocking systems, start/stop push buttons, counter to register number of flushing operations etc., and shall be complete with internal wiring. In addition to the above, the control panel shall meet the requirements of the enclosed specification.


3.09.03 All instrumentation shall be of reputed make and shall meet the requirement of the enclosed specification.

3..10.00 **Other Accessories.**

3.10.01 Counter flanges, flat faced slip on type, complete with gaskets, bolts and nuts etc., shall be supplied for the filter inlet, outlet connections and all other terminal points. Fabrication, dimensions and drilling of the flanges shall conform to the codes/standards specified in Data Sheet-A.

3.10.02 Self-cleaning filter shall be provided with suitable lifting arrangement for handling during erection and maintenance.

3.10.03 Necessary supporting arrangement (wherever applicable) complete with foundation plates, bolts, nuts etc., shall be provided.

	TITLE :	SPEC. NO. PE-TS- 999-165-N002
	STANDARD TECHNICAL SPECIFICATION	VOLUME : II B
	SELF - CLEANING FILTERS	SECTION : D
		REV. NO. 0 DATE : 02.12.2009
		SHEET 5 OF 10

3.11.00 **Material of Construction**

Material of self-cleaning filter and other accessories shall be corrosion resistant and consistent with the fluid handled. However material specification for various components shall be equal or superior to those specified in Data Sheet-A.

4.00.00 **PAINTING**

4.01.00 The surface preparation of the filter housing / body and other parts shall be done as per the standard mentioned in Data Sheet-A and shall include the following :

- a) Removal of oil, grease, dirt and swarf etc.
- b) Removal of rust and scale etc.
- c) Sand blasting/shot blasting.

4.02.00 All internal surfaces of the filter which are subject to immersion or water spray and which are not made of stainless steel or other corrosion resistant materials after surface preparation, shall be coated with adequate coats (minimum 200 to 250 microns thick) of epoxy paint of approved make and quality over a coat of zinc chromite primer, unless otherwise specified in Data sheet-A.

4.03.00 The external surfaces of the filter and other accessories after surface preparation, shall be coated with adequate coats (minimum 175 to 200 microns thick) of synthetic enamel paint of approved make and quality over two coats of red oxide primer, unless otherwise specified in Data Sheet-A.

5.00.00 **SHOP INSPECTION AND TESTS**


5.01.00 **General :**

5.01.01 Manufacturer shall conduct all tests and stage inspections as per the approved quality plan to ensure that the self-cleaning filter and other accessories shall conform to the requirements of this specification and of the applicable codes/standards.


5.01.02 All materials used for manufacture/fabrication of the filter shall be of tested quality. Relevant test certificates for chemical analysis, mechanical tests and heat treatment shall be made available before the final shop inspection. In case the relevant test certificates are not available, the manufacturer shall arrange to carry out the necessary tests as per approved quality plan and applicable codes at his cost, for which samples shall be identified by BHEL's representative.

5.01.03 All shop tests shall be conducted in the presence of BHEL's representative and test certificates / reports for the same shall be furnished to BHEL for approval.

5.01.04 Qualification of welding procedures and welders shall be as per ASME B&PV

	TITLE :	SPEC. NO. PE-TS- 999-165-N002
	STANDARD TECHNICAL SPECIFICATION	VOLUME : II B
	SELF - CLEANING FILTERS	SECTION : D
		REV. NO. 0 DATE : 02.12.2009
		SHEET 6 OF 10

- Code, Section-IX / applicable codes.
- 5.02.00 **Filter Housing / Body**
- 5.02.01 Chemical analysis, mechanical tests shall be carried out on housing/body material.
- 5.02.02 All butt welded joints shall be subjected to radiographic / ultrasonic testing as per applicable codes. However all welded joints shall be subjected to 100% magnetic particle / penetrant testing to ensure freedom from defects.
- 5.03.00 **Rubber Lining (as applicable)**
- Rubber lining shall be subjected to surface crack test, 100% spark and hardness tests and shall be checked for layer thickness, defects etc.
- 5.04.00 **Filter Section/Screen assembly**
- Supporting cage and filter section/screen materials shall be tested for chemical properties. Checks shall be carried out for perforation/mesh size, defects etc.
- 5.05.00 **Flushing / Backwash Unit**
- 5.05.01 Material of various components of the flushing/Backwash Unit shall be tested for chemical and mechanical properties.
- 5.05.02 Hollow shaft of backwash rotor shall be ultrasonically tested as per ASTM-A 388 for internal flaws. Penetrant test shall be carried out for surface flaws.
- 5.06.00 **Valves**
- Inspection and testing of valves including leakage test shall be carried out as per the requirements of the applicable standards. Correlating test certificates for materials of the valve components shall be furnished.
- 5.07.00 **Flanges**
- 5.07.01 In case of fabricated flanges, all the welds shall be subjected to 100% radiography as per ASME B&PV code, section VIII, Division-1.
- 5.07.02 In case of forged flanges, ultrasonic testing shall be carried out as per ASTM-E 388.
- 5.07.03 If the thickness of the plate used for flanged is 40mm or more the same shall be checked ultrasonically as per ASTM-A 435 to demonstrate the absence of lamination and lack of fusion etc.
- 5.07.04 Chemical and mechanical test certificates shall furnish for flange materials.
- 5.07.05 Flanges shall be checked for edge preparation, fit up and satisfactory working with

	TITLE :	SPEC. NO. PE-TS- 999-165-N002
	STANDARD TECHNICAL SPECIFICATION	VOLUME : II B
	SELF - CLEANING FILTERS	SECTION : D
		REV. NO. 0 DATE : 02.12.2009
		SHEET 7 OF 10

5.08.00 matching parts.
All materials for various nozzles, seals, pipes, gaskets, nuts bolts etc., shall be of tested quality and correlating test certificates for chemical and mechanical properties shall be furnished.

5.09.00 **Dimensional Checks**

Dimensional checks of various components of the filter shall be carried out as per the drawings approved by BHEL.

5.10.00 **Hydrostatic Test**

Hydrostatic test shall be conducted on the filter housing/body at a pressure of 2 times the design pressure. The duration of the test shall be minimum 30 minutes.

5.11.00 **Leakage Test**

Leakage test shall be conducted at the design pressure to demonstrate that the filter assembly is leak tight and no water seepage shall take place at various nozzle and valve connections.

5.12.00 **Functional Tests**

The self-cleaning filter assembly complete with valves, actuators and other accessories shall be subjected to functional tests and the following shall be checked :-

5.12.01 Smooth and free operation of all movable parts.

5.12.02 Interlocks and sequential operation.

5.12.03 Satisfactory operation of actuator torque switches, limit switches etc.

6.00.00 **TESTING AT SITE**

After completion of installation at site, the self cleaning filter with complete accessories, will be tested to check that the filter performance meets the requirements of its specification, Rectification of all defects shall have to be done by the supplier at no extra cost to the Owner / Purchaser. However the Owner / Purchaser reserves the right to reject the equipment / parts not meeting the requirement if the deficiency still persists.

7.00.00 **PERFORMANCE GUARANTEE**

7.00.00 **PERFORMANCE GUARANTEE & Bid evaluation criteria**

The Self cleaning strainer shall be guaranteed to meet the performance requirements specified in Section-D , Data Sheet A and Guarantee schedule and also for trouble free operation after commissioning. Schedule of performance guarantees (enclosed in

	TITLE :	SPEC. NO. PE-TS- 999-165-N002
	STANDARD TECHNICAL SPECIFICATION	VOLUME : II B
	SELF - CLEANING FILTERS	SECTION : D
	REV. NO. 0	DATE : 02.12.2009
	SHEET 8 OF 10	

Volume III) duly filled and signed shall be furnished with the bid.

The Performance guarantees of equipments shall stand valid till the satisfactory completion of performance testing & its acceptance by BHEL/ Customer. If the guarantee period specified in the Commercial Specification is higher, same shall prevail.

7.01.00 Performance Guarantee Parameters shall be as under :

- Pressure drop in Self cleaning strainer in clean condition viz. after backwashing.

7.02.01 Bidder to note that bids shall be evaluated on account of pressure drop across Self cleaning strainer (in clean condition) & liquidated damages on account of not meeting the same shall be in accordance with following :

A) Bid Evaluation Criteria and Liquidated Damages:

The bids received shall be evaluated for Pressure drop across Self cleaning strainer:

- The permissible limit of pressure drop across Self cleaning strainer in clean condition shall be 0.6 MWC.
- If the pressure drops quoted are higher than above limit, the bids shall be technically loaded @ Rate as mentioned in Data Sheet-A for respective projects per 1 MWC pressure drop (viz. per unit).
- However no advantage shall be given for pressure drops quoted less than above permissible limit.
- The maximum acceptable limit for pressure drop across self cleaning strainer (with technical loadings) shall be 1.0 MWC

The bids will be technically rejected for pressure drops quoted higher than above maximum limit.

- The guaranteed pressure drops shall be demonstrated at site by vendors and if found higher shall be subject to LD @ twice the bid evaluation factor as above.


8.00.00 QUALITY ASSURANCE & QUALITY PLAN

8.01.00 The self - cleaning filter and other accessories to be supplied shall have assured quality and workmanship.

8.02.00 Typical quality plans (Q.P. No. PEM-MSE-SQP-07) are enclosed herewith this specification for bidder's guidance. The bidder shall comply with these minimum requirements and shall furnishing own quality plan based on materials and components of the filter being offered.

9.00.00 NAME PLATE AND TAG NUMBERS

9.01.00 The filter shall be provided with a permanently attached brass or stainless steel plate indicating the following details:-

	TITLE :	SPEC. NO. PE-TS- 999-165-N002
	STANDARD TECHNICAL SPECIFICATION	VOLUME : II B
	SELF - CLEANING FILTERS	SECTION : D
		REV. NO. 0 DATE : 02.12.2009
		SHEET 9 OF 10

- a) Design flow
- b) Design and test pressures
- c) Design temperature
- d) Filter section/screen mesh size
- e) Empty and operating weights
- f) Revolving speed of backwash rotor

9.02.00 Each valve shall be provided with a name plate indicating the following :-

- a) Service
- b) Design and test pressures
- c) Maximum flow and flow direction
- d) Size
- e) Engineer's Tag Number

Tag numbers will be indicated on the drawing submitted for approval during contract stage.

9.03.00 Each motor / actuator shall be provided with a name plate indicating the following details :

- a) Supply conditions.
- b) KW Rating
- c) Make

10.00.00 **DRAWINGS, DATA & INFORMATION TO BE SUBMITTED WITH THE BID**

The bidder shall furnish the following drawings, data and information alongwith the bid without which the offer will be deemed incomplete.

10.01.00 Data sheet-B with all particulars / data duly filled in.

10.02.00 General arrangement / installation drawings of the self-cleaning filter with all accessories, incorporating the principal dimensions and weights of equipment offered, size and location of various nozzle connections, supporting arrangement (if applicable) and scope of supply etc.


10.03.00 Cross-sectional / detailed drawings of filter housing / body, filter section / screen assemblies, flushing / backwashing unit, differential pressure measuring system, actuators, motors, control panel etc., indicating bill of quantities and materials of construction.

10.04.00 Flow and control logic diagrams for complete filter during normal and flushing / backwashing operations.

10.05.00 Performance evaluation procedure at site.

	TITLE :	SPEC. NO. PE-TS- 999-165-N002
बी एल 5 एम	STANDARD TECHNICAL SPECIFICATION	VOLUME : II B
	SELF - CLEANING FILTERS	SECTION : D
		REV. NO. 0 DATE : 02.12.2009
		SHEET 10 OF 10

- 10.06.00 Control panel layout and list of instruments provided on control panel.
- 10.07.00 List of annunciations, protections and interlocks provided.
- 10.08.00 Write-up on operation, control, monitoring, interlocks and protection of filter.
- 10.09.00 Manufacturer's descriptive and illustrative literature on the equipments / components being offered.
- 10.10.00 A detailed experience list about the successful installations of similar equipment of equal or higher inlet / outlet sizes and flow capacities for similar application.
- 10.11.00 A comprehensive write-up on the testing facilities, tests to be conducted inspection methods and QA system adopted by the manufacturer.
- 10.12.00 Quality plan for the self-cleaning filter and for all its accessories.
- 11.00.00 **DRAWINGS, DATA & INFORMATION TO BE SUBMITTED AFTER THE AWARD OF CONTRACT :**
- The drawings, data and other documents as required in Data Sheet-C shall be furnished after the award of contract.

	TITLE :	SPECIFICATION NO. PE-TS-317/326-165-N002	
	DATA SHEET - C	VOLUME : II - B	
	SELF - CLEANING FILTER	SECTION : D	
	(Backwash Type)	REV. NO. 02	DATE : 02.12.2009
		SHEET 1 OF 2	

1.00.00 **DRAWINGS, DATA AND INFORMATION TO BE SUBMITTED AFTER THE AWARD OF CONTRACT :**

After the award of contract, the following drawings, data and information is to be submitted for review / approval of BHEL as per the distribution schedule given in Section -C.

1.01.00 Within 3 (three) weeks of the data of LOI, the following shall be submitted :

1.01.01 Data Sheet -B duly revised conforming to accepted bid.

1.01.02 Final versions of the following drawings to enable BHEL to finalise the layout and to design foundations and structures.

a) General arrangement / Installation drawings of the self-cleaning filter with all accessories, indicating the principal dimensions and weights of equipment offered, size and location of various nozzle connections, withdrawal space and scope of supply etc.

b) Foundation arrangement drawings (wherever applicable) showing load data on supports, size and location of another bolts etc.

1.02.00 **With in the stipulated time period as per vendor's drawing/document list, the following shall be submitted :**

1.02.01 Cross-sectional/detailed drawings of filter housing/body, filter screen/section assembly, flushing / backwash unit, differential pressure measuring system, actuators, motors, control panel etc. indicating bill of quantities and materials of construction.

10.02.02 Flow and control logic diagrams for complete filter during normal and flushing operation and system write-up covering all modes of operation.

1.02.03 Final version of performance evaluation procedures at site.


1.02.04 Detailed schedule of valves indicating tag numbers, type, make, size, pressure & temperature ratings, materials etc.

1.02.05 Detailed schedule of power & control cable.

1.02.06 Detailed schedule of piping and fittings indicating sizes, materials, maximum working pressure & temperatures etc.

1.02.07 Control panel layout and list of instruments provided on control panel and internal wiring diagrams.

1.02.08 List of annunciations, protections and interlocks provided.

	TITLE :	SPECIFICATION NO. PE-TS-317/326-165-N002	
	DATA SHEET - C	VOLUME : II - B	
	SELF - CLEANING FILTER	SECTION : D	
	(Backwash Type)	REV. NO. 02	DATE : 02.12.2009
		SHEET 2 OF 2	

- 1.02.09 Detailed drawings of flanges.
- 1.02.10 Quality Plan
- 1.02.11 Material test certificates.
- 1.02.12 Shop tests reports and certificates.
- 1.02.13 Write-up and instruction manuals for erection, operation and maintenance.
- 1.02.14 Storage instructions.
- 1.02.15 Vendor to send 3 sets of final documents (O&M Manual, GA drg, P&ID) direct to site under intimation to PEM.

DMS (BHEL-PEM)
 6078516-2014/07/19



TITLE :
DATA SHEET – A2 FOR
SELF CLEANING STRAINERS (SCS)

SPECIFICATION NO. SPEC. NO. PE-TS-405-165-N003

VOLUME : II B
SECTION : D

REV. NO. 00 DATE : 15.07.2014

Page 1 of 7

S. No.	DESCRIPTION	UNITS	3x660MW NTPC NORTH KARANPURA STPP	
1.0	GENERAL			
1.1	Type of Strainers/ Filters	-	Self Cleaning Strainers	
1.2	No. of Strainers/ Filters required	Nos.	Total 6 Sets for 3 units viz. i.e.(1 Working + 1 Standby at ACW pumps discharge) per unit	Total 2 Sets for 3 units viz. i.e.(1 Working + 1 Standby at AHS cooling water pumps discharge).
1.3	Inlet connection	mm Nb	800	350
1.3	Outlet connection	mm Nb	800	350
1.4	Filter type/ duty	-	On line / continuous	
1.5	Location	-	ACW Pump discharge Header (Outdoor)	AHS Pump discharge Header (Outdoor)
1.6	Liquid handled	-	Clarified Water as per analysis attached in Project information in section-B	
2.0	DESIGN DATA			
2.1	Operating pressure	Bar (g)	3.5 to 4.5	
2.2	Design pressure	Kg/cm ²)	7.5	
2.3	Design temperature	Deg. C	60	
2.4	Flow rate through filter		3014 3617	693 832
	a) Normal			
	b) Maximum			



TITLE :
**DATA SHEET – A2 FOR
 SELF CLEANING STRAINERS (SCS)**

SPECIFICATION NO. SPEC. NO. **PE-TS-405-165-N003**

VOLUME : **II B**
 SECTION : **D**

REV. NO. **00** DATE : **15.07.2014**

Page 2 of 7

3x660MW NTPC NORTH KARANPURA STPP

S. No.	DESCRIPTION	UNITS	
2.5	Design differential pressure for filter section/ screen	Bar (g)	1.5 (Min.)
2.6	Type of suspended matter likely to enter the filter	-	Typical debris encountered in closed circuit CW system with Cooling Tower
2.7	Differential pressure measuring system set pressure <ul style="list-style-type: none"> • For initiating flushing/ backwashing • For alarm/ annunciation 	mbar mbar	110 160
2.8	Filter section/ screen perforation size	mm	2 mm (Max)
2.9	Free flow area in the screen basket	-	At least 120 % of pipe inlet area
3.0	GUARANTEED PERFORMANCE REQUIREMENT		
3.1	Pressure drop across the filter (i.e. between inlet and outlet connection) at normal flow	-	



TITLE :
**DATA SHEET – A2 FOR
 SELF CLEANING STRAINERS (SCS)**

SPECIFICATION NO. SPEC. NO. **PE-TS-405-165-N003**
 VOLUME : **II B**
 SECTION : **D**
 REV. NO. **00** DATE : **15.07.2014**
 Page 3 of 7

S. No.	DESCRIPTION	UNITS	3x660MW NTPC NORTH KARANPURA STPP
	a) Clean condition	mbar	Refer Section – C of specification
	b) Partially (50%) choked condition	mbar	Not to exceed 110
3.2	Debris discharge flow during flushing period	Cub m/ Hr.	Not to exceed 2.5% of total flow rate
4.0	MATERIALS OF CONSTRUCTION		
4.1	Filter body/ housing	-	IS:210 Gr. FG 260 or ASTM –A-515 Gr. 75/IS:2062 with epoxy painted inside
4.2	Filter screen/ section	-	SS-316
4.3	Shaft	-	SS-316
4.4	Supporting cage	-	SS-316
4.5	Differential measuring system	-	SS-316
4.6	Flushing/ backwashing unit	-	SS-316
4.7	Backwash rotor shoes	-	Neoprene
4.8	Any other internal hardware /pipes etc.	-	SS-316 or eq.



TITLE :
**DATA SHEET – A2 FOR
 SELF CLEANING STRAINERS (SCS)**

SPECIFICATION NO. SPEC. NO. **PE-TS-405-165-N003**
 VOLUME : II B
 SECTION : D
 REV. NO. 00 DATE : 15.07.2014
 Page 4 of 7

S. No.	DESCRIPTION	UNITS	3x660MW NTPC NORTH KARANPURA STPP
--------	-------------	-------	-----------------------------------

4.9	Valves	-	
4.9.1	Gate valves (65Nb and above)/Check Valves (all sizes)		
	a) Body & Bonnet	-	ASTM A 216 Gr. WCB/ASTM A105
	b) Disc for Check Valve	-	ASTM A 216 Gr. WCB/ASTM A105
	c) Trim	-	ASTM A 182 Gr. F6 or equivalent
4.9.2	Globe Valves 50 Nb & Below		
	Body, Bonnet & trim		ASTM A-105
	Stem		13% Chrome steel ASTM-A-182-Gr. F6a
4.9.3	C) Ball valves		
	i) Body		SA 351 CF8M
	ii) Ball		SA 351 CF8M
	iii) Stem		SS 316
4.10	Piping	-	By Bidder
	Material a) upto 150 Nb		<ul style="list-style-type: none"> Carbon steel ERW, IS:1239 (Heavy Grade)
	a) 200 Nb and above		<ul style="list-style-type: none"> carbon steel (IS:2062), Rolled & Welded confirming to IS:3589



TITLE :
**DATA SHEET – A2 FOR
 SELF CLEANING STRAINERS (SCS)**

SPECIFICATION NO. SPEC. NO. PE-TS-405-165-N003

VOLUME : II B
SECTION : D

REV. NO. 00 DATE : 15.07.2014

Page 5 of 7

S. No.	DESCRIPTION	UNITS	3x660MW NTPC NORTH KARANPURA STPP	
5.0	COUNTER FLANGES		In Bidder's Scope	
5.1	Material			
	Flanges		IS 2062, Gr. B, epoxy painted	
5.2	Drilling Standard	-	BS 4504 or equivalent	
6.0	Connecting pipe size (OD & Thk)	mm	813 X 8	355.6 X 6
7.0	PAINTING			
7.1	External Surface	-		
	a) Surface preparation	-	Power tool cleaning/Shot blasting/ abrasive blasting	
	b) Primer		Two coats of Zinc chrome primer (Alkyd base) by brush/spray to IS 104 OR Two coats of Red oxide Zinc Phosphate based primer (alkyd base) to IS 12744 with min. DFT per coat of 25 microns	
	Intermediate		One coat of Synthetic enamel (long oil alkyd) to IS 2932 with min. DFT of 30 microns	
	c) Final paint		Two coats of Synthetic enamel (long oil alkyd) to IS 2932 with min. DFT of 35 microns to achieve total min DFT of 150 microns.	
7.2	Internal Surface			
	a) Surface preparation		SA 2.5 of Swedish Specification SIS 05.5900.197	
	b) Primer		One coat of epoxy resin based primer	
	c) Final paint		Applicable no. Of coats of coal tar epoxy paint to achieve total DFT of 200 to 250 microns	
8.0	SHOP TEST			



TITLE :
**DATA SHEET – A2 FOR
 SELF CLEANING STRAINERS (SCS)**

SPECIFICATION NO. SPEC. NO. PE-TS-405-165-N003
VOLUME : II B
SECTION : D
REV. NO. 00 DATE : 15.07.2014
Page 6 of 7

S. No.	DESCRIPTION	UNITS	3x660MW NTPC NORTH KARANPURA STPP
8.1	Hydrostatic test		
	a) Test Pressure	bar (g)	1.5 times design pressure
	b) Test duration	min.	30
8.2	Leakage test		
	a) Test Pressure	bar (g)	Design Pressure
	b) Test duration	min.	30

Bidder to note that electrical power supply shall be provided by purchaser based on electrical load list of bidder furnished at tender stage and any changes or additional requirement of electrical load by bidder during contract stage shall be provided by BHEL(purchaser) with cost repercussions to the bidder

9.0	Adequate provision for future installation of cathodic protection required		YES
10.0	Flow straightener for streamlining the ACW flow in SCS		If required as per bidder's design – the same to be incorporated by bidder in its constructional feature.
11.0	Performance Guarantee & Bid Evaluation		
11.1	Performance Parameters to be Guaranteed		
	❖ Pressure drop SCS		As per Guarantee schedule of bidder
11.2	Bid evaluation Criteria & Liquidated damages		As per clause no. 8.00.00 of section C1
11.3	Bid evaluation rate		@ Rs 2.0 Lacs per 0.1 MWC pr. Drop across each SCS
11.4	Liquidated damages		Twice the bid evaluation rate



TITLE :
**DATA SHEET – A2 FOR
SELF CLEANING STRAINERS (SCS)**

SPECIFICATION NO. SPEC. NO. PE-TS-405-165-N003

**VOLUME : II B
SECTION : D**

REV. NO. 00 DATE : 15.07.2014

Page 7 of 7

3x660MW NTPC NORTH KARANPURA STPP

S. No.	DESCRIPTION	UNITS	
12.0	Whether automatic flushing/ back- washing operation effected by the following : i. Differential pressure ii. Adjustable timer iii. Push button		YES YES YES YES
13.0	Whether provision for manual flushing / backwashing operation is made in the event of control system failure.		YES
14.0	Whether built in flushing arrangement complete with flushing pump, valves, and associated piping, is provided.		YES (if required)
15.0	Mandatory Spare to be supplied under this specification		NIL

ANNEX TO DATASHEET-A

PIPE SIZE TABLE (REFER CL. N. 6.2, SECTION C1, Vol.IIB)

PIPE SIZES

NB	O.D.(MM) MAX.	THK.(MM) MIN
15	21.8	3.2
25	34.2	4.0
50	60.8	4.5
100	115.0	5.4
150	166.5	5.4
200	219.1	6.0
250	273.0	6.0
300	323.9	6.0
350	355.6	6.0

PIPE SIZES

NB	O.D.(MM) MAX.	THK.(MM) MIN
400	406.4	6.0
450	457	6.0
500	508	6.0
600	610	6.0
700	711	7.0
800	813	8.0
900	914	8.0
1000	1016	9.0
1200	1219	10.0
1400	1422	12.5
1500	1524	14.2



Manufacturer's Name & Address

STANDARD QUALITY PLAN

BHEL Doc No.: PE-QP-999-165-N005

P.O. No.

Item :

Vendor Q.P. NO.

PROJECT:

Self Cleaning Strainer

PACKAGE : SELF CLEANING STRAINER

CUSTOMER:

Date :

PURCHASER:

Page 01 of 12

CONSULTANT:

SL. NO.

DESCRIPTION

PAGE NOS.

1

SELF CLEANING STRAINER

2-4

2

BALL VALVES

5

3

BUTTERFLY VALVES

6

4

PRESSURE GAUGE, DP GAUGE, DP SWITCH
DP TRANSMITTER

7

5

GEAR MOTOR DRIVE & WORM PLANETARY GEAR BOX

8

6

ACTUATORS

9

7

STARTER PANEL

10

8

FASTENERS

11

9

ALL COMPONENT / EQUIPMENT

12

ANNEXURES

DRY RUN TEST PROCEDURE

2

HYDRO TEST PROCEDURE

2

HYDRO STATIC LEAK TIGHTNESS TESTING PROCEDURE

2

PACKING PROCEDURE

1

Note: Items not included in quality plan to be inspected as per Approved datasheet/drawings.

LEGEND

* Records identified with "STAR" shall be essentially included by contractor in QA Documentation.

** M : Manufacturer/ Sub-contractor

C : CONTRACTOR O: OWNER

Indicate : "P" - Perform, "W" - Witness and "V" - Verification

Manufacturer / Sub-Contractor

Contractor

Signature

Name & Sign. Of approving authority & Seal



Manufacturer's Name & Address

STANDARD QUALITY PLAN

BHEL Doc No.: PE-QP-999-165-N005

Item :

Vendor Q.P. NO.

PROJECT:

Self Cleaning Strainer

PACKAGE : SELF CLEANING STRAINER

CUSTOMER:

P.O. No.

Date :

PURCHASER:

Page 02 of 12

CONSULTANT:

Sl. No.	Component / Operation	Characteristics Checked	Class	Type of Check	Quantum of Check	Reference Documents	Acceptance Norms	Format of Record	Agency			Remarks		
									M	C	O			
1	2	3	4	5	6	7	8	9	**	10		11		
1.0.0	SELF CLEANING STRAINER													
1.1.0	Raw Material													
[a]	Housing Shell, Nozzle flanges & Main flanges/Counter Flange	Chemical properties	Major	Chemical Analysis	One sample/cast / heat / batch	Approved drg/Data sheet	Approved drg/Data sheet	Mill Test Certificate / lab test report / raw material flow sheet	*	P	V	V	All raw material identification as per manufacturer TC/Lab report by BHEL	
		Physical properties	Major	Physical test	One sample/cast / heat / batch	Approved drg/Data sheet	Approved drg/Data sheet	Mill Test Certificate / lab test report / raw material flow sheet	*	P	V	V		
		Surface Defects	Minor	Visual	100%	Approved drg/Data sheet	Approved drg/Data sheet	Mill Test Certificate /Inspection Report	-	P	V	V		
		Sub Surface Defects	Major	Ultrasonic Test	100%	ASME A 435/A609	ASME A 435/A609	Inspection report	*	P	V	V	Plates > 20mm Thk only	
[b]	Nozzle Pipes	Chemical properties	Major	Chemical Analysis	One sample/cast / heat / batch	Approved drg/Data sheet	Approved drg/Data sheet	Mill Test Certificate / lab test report / raw material flow sheet	*	P	V	V		
		Physical properties	Major	Physical test	One sample/cast / heat / batch	Approved drg/Data sheet	Approved drg/Data sheet	Mill Test Certificate / lab test report / raw material flow sheet	*	P	V	V		
		Surface defects	Minor	Visual	100%	Approved drg/Data sheet	Approved drg/Data sheet	Mill Test Certificate /Inspection Report	-	P	V	V		
		Leak tightness	Major	Hydrostatic test	100%	Approved drg/Data sheet	Approved drg/Data sheet	Mill Test Certificate /Inspection Report	-	P	V	V		
[c]	Screen basket, Nozzle flanges	Chemical properties	Major	Chemical Analysis	One sample/cast / heat / batch	Approved drg/Data sheet	Approved drg/Data sheet	Mill Test Certificate / lab test report / raw material flow sheet	*	P	V	V		
		Physical properties	Major	Physical test	One sample/cast / heat / batch	Approved drg/Data sheet	Approved drg/Data sheet	Mill Test Certificate / lab test report / raw material flow sheet	*	P	V	V		
		Surface Defects	Minor	Visual	100%	Approved drg/Data sheet	Approved drg/Data sheet	Mill Test Certificate /Inspection Report	-	P	V	V		
		Sub-surface defects	Major	Ultrasonic test	100%	ASME A 745	ASME A 745	Inspection report	*	P	V	V	Plates > 20mm Thk only (UT full volume)	
		Corrosion Resistance	Major	IGCI	One/Heat	ASTM A 262	Practice E of ASTM A 262	Test Report	*	P	V	V		
LEGEND														
* Records identified with "STAR" shall be essentially included by contractor in QA Documentation.														
** M : Manufacturer/ Sub-contractor														
C : CONTRACTOR O: OWNER														
Indicate : "P" - Perform, "W" - Witness and "V" - Verification														
Manufacturer / Sub-Contractor Signature									Contractor Signature			Name & Sign. Of approving authority & Seal		



Manufacturer's Name & Address

STANDARD QUALITY PLAN

BHEL Doc No.: PE-QP-999-165-N005

Item :

Vendor Q.P. NO.

PROJECT:

Self Cleaning Strainer

PACKAGE : SELF CLEANING STRAINER

CUSTOMER:

P.O. No.

Date :

PURCHASER:

Page 03 of 12

CONSULTANT:

Sl. No.	Component / Operation	Characteristics Checked	Class	Type of Check	Quantum of Check	Reference Documents	Acceptance Norms	Format of Record	Agency			Remarks		
									M	C	O			
1	2	3	4	5	6	7	8	9	**	10		11		
[d]	Nozzle Pipes	Chemical properties	Major	Chemical Analysis	One sample/cast / heat / batch	Approved drg/Data sheet	Approved drg/Data sheet	Mill Test Certificate / lab test report / raw material flow sheet	*	P	V	V		
		Physical properties	Major	Physical test	One sample/cast / heat / batch	Approved drg/Data sheet	Approved drg/Data sheet	Mill Test Certificate / lab test report / raw material flow sheet	*	P	V	V		
		Surface defects	Minor	Visual	100%	Approved drg/Data sheet	Approved drg/Data sheet	Mill Test Certificate/ Inspection Report	-	P	V	V		
		Leak tightness	Major	Hydrostatic test	100%	Approved drg/Data sheet	Approved drg/Data sheet	Mill Test Certificate/ Inspection Report	-	P	V	V		
1.2.0	Inprocess Quality Control													
1.2.1	Welding procedure specification	Correctness	Critical	Scrutiny	100%	ASME Sec. IX	ASME Sec. IX	QW 482 of ASME Sec.IX	-	P	V	V	Welders already qualified by BHEL/ LRQA / NTPC in the past shall be employed for this job.	
1.2.2	Welding procedure qualification	Weld soundness	Critical	Physical test	100%	ASME Sec. IX	ASME Sec. IX	QW 483 of ASME Sec.IX	--	P	V	V	Welding procedure already approved by BHEL/ LRQA / NTPC shall be followed.	
1.2.3	Welder performance qualification	Weld soundness	Critical	Physical test	100%	ASME Sec. IX	ASME Sec. IX	QW 484 of ASME Sec.IX	--	P	V	V	Welders already qualified by BHEL/ LRQA / NTPC shall be employed for this job.	
1.2.4	Fit-up of butt weld	Alignment, and dimensions	Major	Template, visual	100%	Manufacturing Drawing	ASME Sec.VIII Div. I	Log book	--	P	V	-	BHEL to witness >20mm thick butt joint.	
1.2.5	Fit-up of shell flange and nozzle assembly to shell	Orientation, alignment and dimensions	Major	Template, visual	100%	Manufacturing Drawing	ASME Sec.VIII Div. I	Log book	--	P	-	-		
1.2.6	Weld quality for Pressure Parts													
	[a] Root run	Surface defects	Major	Penetrant test / Visual	100%	ASME Sec.VIII Div. I / sec V	ASME Sec.VIII Div. I Appendix 8	Operation Process Sheet		P	-	-		
1.2.7	[a] Completed butt welds	1.Surface defects	Major	Penetrant test	100%	ASME Sec.VIII Div. I / sec V	ASME Sec.VIII Div. I Appendix 8	Inspection report	*	P	V	V		
		2.Sub-surface defects	Critical	Radiography test	10% of total weld length+ 100% T Joints.	ASME Sec.VIII Div. I / sec V	ASME Sec.VIII Div. I Appendix 4 / UW 52	Radiographs and inspection report	*	P	V	V	RT films will be reviewed by BHEL	
	[b] Completed fillet welds	Surface defects	Major	Penetrant test	100%	ASME Sec.VIII Div. I / sec V	ASME Sec.VIII Div. I Appendix 8	Inspection report	*	P	V	V		
LEGEND														
* Records identified with "STAR" shall be essentially included by contractor in QA Documentation.														
** M : Manufacturer/ Sub-contractor														
C : CONTRACTOR O: OWNER														
Indicate : "P" - Perform, "W" - Witness and "V" - Verification														
Manufacturer / Sub-Contractor Signature										Contractor			Name & Sign, Of approving authority & Seal	



Manufacturer's Name & Address

STANDARD QUALITY PLAN

BHEL Doc No.: PE-QP-999-165-N005

Item :

Vendor Q.P. NO.

PROJECT:

P.O. No.

Self Cleaning Strainer

PACKAGE : SELF CLEANING STRAINER

CUSTOMER:

Date :

PURCHASER:

Page 04 of 12

CONSULTANT:

Sl. No.	Component / Operation	Characteristics Checked	Class	Type of Check	Quantum of Check	Reference Documents	Acceptance Norms	Format of Record	Agency			Remarks		
									M	C	O			
1	2	3	4	5	6	7	8	9	**	10		11		
1.2.8	Pickling and Passivation	Protection Layer	Major	Visual	100%	IS : 10117	IS : 10117	Log Book	--	P	-	-		
1.2.9	Fabricated Shell (Prior to sand blasting)	1.Dimensions, Orientation	Major	Measurement by visual	100%	Manufacturing Drawing	Manufacturing Drawing	Inspection report	*	P	V	V		
		2. Hydro test	Critical	Hydrostatic Pr. @ 1.5 times of design pr.(positive) [Duration 30 minutes]	100%	ASME Sec.VIII Div.1	ASME Sec.VIII Div.1	Inspection report	*	P	V	V		
1.3.0	Final tests (completed equipments) - After assembly	1.Dimensions, orientation, workmanship & finish	Major	Measurement by visual	100%	G.A.drawing	G.A.drawing	Inspection report	*	P	V	V		
		2. Leak tightness for assembly	Critical	Leak test @ design pr.(positive) [Duration 30 minutes]	100%	ASME Sec.VIII Div.1	No leakage	Inspection report	*	P	W	V		
		3.Dry function test for Debris filter	Critical	Operational test	100%	Approved Procedure	Approved Procedure	Inspection report	*	P	W	V		
1.4.0	Rubber Lining (Shell)													
1.4.1	Rubber Formulation	Tensile, elongation & hardness	Major	Physical test	One per lot	Manufacturer's procedure	BS 6374/Equivalent	Manufacturers Test certificate	*	P	V	V		
		Polymer Identification	Major	Flame test	One per lot	For Semi Ebonite /Ebonite Polymer catches fire and on removal from fire continues to burn	For Semi Ebonite /Ebonite Polymer catches fire and on removal from fire continues to burn	Inspection report		P	V	V		
		% Change in weight after 24 hours of immersion in sea water at 70°	Major	Immersion test (bleeding test)	One per lot	ASTM D 471	+ / - 1%	Inspection report		P	V	V		
1.4.2	Surface preparation of items to be lined	Free from rust, scale, dust & grease	Major	Visual	100%	SA 2.5	SA 2.5	Manufacturers Internal Inspection report		P	-	-		
1.4.3	Vulcanising	Temperature, Pressure & Time	Major	Process monitoring	100%	Manufacturer's procedure	Manufacturer Procedure	Process Procedure		P	-	-		
1.4.4	Vulcanised Rubber Lined items	[a] Chip test	Major	Chip test	One per lot	Approved Drawing & BS 6374/Equivalent	BS 6374/Equivalent	Inspection report	*	P	V	V		
		[b] Adhesion, Visual defects, Thickness & Hardness	Major	Measurement, Visual Inspection	100% visual, Thickness/ hardness at random	Approved Drawing & BS 6374/Equivalent	BS 6374/Equivalent	Inspection report	*	P	V	V		
		[c] Spark test for Pin Holes at 5 kv/mm	Major	Spark test for Pin Holes	100%	Approved Drawing & BS 6374/Equivalent	BS 6374/Equivalent	Inspection report	*	P	V	V		
LEGEND														
* Records identified with "STAR" shall be essentially included by contractor in QA Documentation.														
** M : Manufacturer/ Sub-contractor														
C : CONTRACTOR O: OWNER														
Indicate : "P" - Perform, "W" - Witness and "V" - Verification														
Manufacturer / Sub-Contractor Signature										Contractor			Name & Sign, Of approving authority & Seal	



Manufacturer's Name & Address

STANDARD QUALITY PLAN

BHEL Doc No.: PE-QP-999-165-N005

Item :

Vendor Q.P. NO.

PROJECT:

Ball Valves

PACKAGE : SELF CLEANING STRAINER

CUSTOMER:

P.O. No.

Date :

PURCHASER:

Page 05 of 12

CONSULTANT:

Sl. No.	Component / Operation	Characteristics Checked	Class	Type of Check	Quantum of Check	Reference Documents	Acceptance Norms	Format of Record	Agency			Remarks	
									M	C	O		
1	2	3	4	5	6	7	8	9	**	10		11	
2.0.0	Ball valves												
2.1.0	Materials												
	Body and Tail end pieces	Chemical properties	Major	Chemical properties	One Sample/Cast / heat	Approved drg/Data sheet	Approved drg/Data sheet	Manufacturer's T.C.	*	P	V	V	
		Physical properties	Major	Physical properties	One Sample/Cast / heat / batch	Approved drg/Data sheet	Approved drg/Data sheet	Manufacturer's T.C.	*	P	V	V	
2.1.1	Ball	Chemical properties	Major	Chemical properties	One Sample/Cast / heat	Approved drg/Data sheet	Approved drg/Data sheet	Manufacturer's T.C.	*	P	V	V	
		Physical properties	Major	Physical properties	One Sample/Cast / heat / batch	Approved drg/Data sheet	Approved drg/Data sheet	Manufacturer's T.C.	*	P	V	V	
2.1.2	Stem	Chemical properties	Major	Chemical properties	One Sample/Cast / heat	Approved drg/Data sheet	Approved drg/Data sheet	Manufacturer's T.C.	*	P	V	V	
		Physical properties	Major	Physical properties	One Sample/Cast / heat / batch	Approved drg/Data sheet	Approved drg/Data sheet	Manufacturer's T.C.	*	P	V	V	
2.2.0	In-process inspection												
2.2.1	Ball	Hardness	Major	Hardness Testing	Random	Approved Drg. / Data Sheet	Approved Drg. / Data Sheet	Manufacturers TC	*	P	V	V	
2.3.0	Assembly	a) Dimensions	Major	Measurement	100%	Approved drg/Data sheet	Approved drg/Data sheet	Manufacturer's T.C.	*	P	V	V	
		b) Opening / Closing	Major	Operation	100%	—	As per approved data sheet	—		P	--	V	
2.4.0	Testing												
	[a] Body	Leakage	Critical	Hydraulic test	100%	EN 12266-1&2	EN 12266-1&2 / Appd. Data sheet	Manufacturer's T.C.	*	P	V	V	
	[b] Seat test	Leakage	Critical	Hydraulic test	100%	EN 12266-1&2	EN 12266-1&2 / Appd. Data sheet	Manufacturer's T.C.	*	P	V	V	
	[c] Seat	Leakage	Critical	Air test	100%	EN 12266-1&2	EN 12266-1&2 / Appd. Data sheet	Manufacturer's T.C.	*	P	V	V	
LEGEND													
* Records identified with "STAR" shall be essentially included by contractor in QA Documentation.													
** M : Manufacturer/ Sub-contractor													
C : CONTRACTOR O: OWNER													
Indicate : "P" - Perform, "W" - Witness and "V" - Verification													
Manufacturer / Sub-Contractor Signature										Contractor		Name & Sign. Of approving authority & Seal	



Manufacturer's Name & Address

Manufacturing Quality Plan

BHEL Doc No.: PE-QP-999-165-N005

P.O. No.

Item : Pressure Gauge, DP Gauge, DP switch&DP Transmitter

Vendor Q.P. NO.

PACKAGE : SELF CLEANING STRAINER

PROJECT:

CUSTOMER:

Date :

Page 07 of 12

PURCHASER:

CONSULTANT:

Sl No.	Component / Operation	Characteristics Checked	Class	Type of Check	Quantum of Check	Reference Documents	Acceptance Norms	Format of Record	Agency			Remarks			
									M	C	O				
1	2	3	4	5	6	7	8	9	**	10		11			
4.0.0	In process quality control	Make, Range and Model	Critical	Visual	100%	Approved Sheet	Data	Approved Data Sheet	Manufacturer test certificate	*	P	V	V		
		Calibration	Critical	Calibration test	100%	Approved Sheet	Data	Approved Data Sheet	Manufacturer test certificate	*	V	V	V		
		Degree of protection	Critical	-	Type test certificate		Approved Sheet	Data	Approved Data Sheet	Manufacturer test certificate	*	V	V	V	
<p>LEGEND</p> <p>* Records identified with "STAR" shall be essentially included by contractor in QA Documentation.</p> <p>** M : Manufacturer/ Sub-contractor C : CONTRACTOR O: OWNER</p> <p>Indicate : "P" - Perform, "W" - Witness and "V" - Verification</p>															
Manufacturer / Sub-Contractor		Contractor												Name & Sign. Of approving authority & Seal	
Signature															

DMS (BHEL-PEM)
6078516-2014/07/19



Manufacturer's Name & Address

Manufacturing Quality Plan

BHEL Doc No.: PE-QP-999-165-N005

Item : Geared Motor drive & Worm planetary Gear box

Vendor Q.P. NO.

PROJECT:

PACKAGE : SELF CLEANING STRAINER

CUSTOMER:

Date :

PURCHASER:

Page 08 of 12

CONSULTANT:

P.O. No.

Sl. No.	Component / Operation	Characteristics Checked	Class	Type of Check	Quantum of Check	Reference Documents	Acceptance Norms	Format of Record	Agency			Remarks	
									M	C	O		
1	2	3	4	5	6	7	8	9	**	10		11	
5.0.0	GEARED MOTOR DRIVE	Running Test	Critical	Functional Test	100%	Approved Data Sheet	Approved Data Sheet	Manufacturer's compliance certificate	*	P	V	V	
		No load	Critical	Functional test	100%	Approved Data Sheet	Approved Data Sheet		*	P	V	V	
		Noise test	Critical	Functional test	100%	Approved Data Sheet	Approved Data Sheet		*	P	V	V	
		Oil leakage test	Critical	Functional test	100%	Approved Data Sheet	Approved Data Sheet		*	P	V	V	
		Visual	Critical	-	100%	Approved Data Sheet	Approved Data Sheet		*	P	V	V	
		Name plate verification	Critical	-	100%	Approved Data Sheet	Approved Data Sheet		*	P	V	V	
5.1.0	Complete Unit of planetary gear	No Leak Test	Critical	Functional test	One Sample/lot	Approved Data Sheet	Supplier Catalogue	Manufacturer's compliance certificate	*	P	V	V	
		Noise Level	Minor	Functional test	One Sample/lot	Approved Data Sheet	Approved Data Sheet			P	V	V	
		Visual Name plate Verification	Minor	-	100%	Approved Data Sheet	Approved Data Sheet			P	V	V	
			LEGEND										
			* Records identified with "STAR" shall be essentially included by contractor in QA Documentation.										
			** M : Manufacturer/ Sub-contractor										
Manufacturer / Sub-Contractor			Contractor			C : CONTRACTOR			O: OWNER				
Signature						Indicate : "P" - Perform, "W" - Witness and "V" - Verification						Name & Sign. Of approving authority & Seal	



Manufacturer's Name & Address

Manufacturing Quality Plan

BHEL Doc No.: PE-QP-999-165-N005

Item : Actuators

Vendor Q.P. NO.

PROJECT:

P.O. No.

PACKAGE : SELF CLEANING STRAINER

CUSTOMER:

Date :

PURCHASER:

Page 09 of 12

CONSULTANT:

Sl. No.	Component / Operation	Characteristics Checked	Class	Type of Check	Quantum of Check	Reference Documents	Acceptance Norms	Format of Record	Agency			Remarks		
									M	C	O			
1	2	3	4	5	6	7	8	9	10			11		
6.0.0	Actuators	Functional test	Major	Electrical test	100%	Supplier catalogue/Appd data sheet	Supplier catalogue/Appd data sheet	Test certificate	*	P	V	V		
		Make, Range, Model	Major	Visual	100%	Supplier catalogue/Appd data sheet	Supplier catalogue/Appd data sheet	Inspection Report	-	P	-	-		
		Assembly check alongwith valves	Major	Visual	100%	Supplier catalogue/Appd data sheet	Supplier catalogue/Appd data sheet	Inspection Report	-	P	-	-		
		Functional Check along with settings / Auxillary Caontacts	Major	Visual	100%	Supplier catalogue	Supplier catalogue/Appd data sheet	Inspection Report	-	P	-	-	Review of TC's	
LEGEND														
* Records identified with "STAR" shall be essentially included by contractor in QA Documentation.														
** M : Manufacturer/ Sub-contractor														
C : CONTRACTOR O: OWNER														
Indicate : "P" - Perform, "W" - Witness and "V" - Verification														
Manufacturer / Sub-Contractor Signature			Contractor									Name & Sign. Of approving authority & Seal		

DMS (BHEL PEQA)
6078516-2014/0019



Manufacturer's Name & Address

Manufacturing Quality Plan

BHEL Doc No.: PE-QP-999-165-N005

Item : Starter Panel

Vendor Q.P. NO.

PROJECT:

P.O. No.

PACKAGE : SELF CLEANING STRAINER

CUSTOMER:

Date :

Page 10 of 12

PURCHASER:

CONSULTANT:

Sl. No.	Component / Operation	Characteristics Checked	Class	Type of Check	Quantum of Check	Reference Documents	Acceptance Norms	Format of Record	Agency			Remarks		
									M	C	O			
1	2	3	4	5	6	7	8	9	**	10		11		
7.0.0	Starter panel													
7.1.0	Incoming Material													
7.1.1	Fabricated & Painted Panel	Dimension	Major	Measurement	100%	Approved Drgs.	Approved Drgs.	Inspection report	-	P	--	--	7 Tank treatment before painting	
		Panel G.A.	Major	Measurement	100%	Approved Drgs.	Approved Drgs.	Inspection report	-	P	--	--		
		Paint colour	Major	Visual	100%	Approved Drgs.	Approved Drgs.	Inspection report	-	P	--	--		
		Paint thickness	Major	Measurement	100%	Approved Drgs.	Approved Drgs.	Inspection report	-	P	--	--		
		Paint Shade, Adhesion	Major	Visual	Sample	Approved Drgs.	Approved Drgs.	Inspection report	-	P	--	--		
7.1.2	Wire	Size / Colour / Rating / Surface Defects	Major	Visual Dimension /	Sample	IS 694	Specification drawings /	Inspection report	-	P	--	--	ISI Marked wire	
7.1.3	Panel Mounting	Make, Functional, Type & Rating	Major	Visual / Electrical	100%	Approved BOM	Approved BOM	---		P	V	V	For bolt list refer starter panel document Part-II	
7.2.0	In Process Inspection													
7.2.1	Name Plate, Component Mounting, Etc.	Workmanship, Finish, Correctness	Major	Visual	100%	Approved Drgs.	Approved drawings	Inspection report	-	P	--	--		
7.2.2	Electrical Wiring of Panels	Continuity, Colour of wires, Bunching and Grouping	Major	Visual	100%	Mounting Drawing	Approved drawings	Inspection report	-	P	--	--		
7.2.3	Ferruling of Cables	Start & End	Major	Visual	100%	Manufacturer's drawing	Manufacturer's drawing	Inspection report	-	P	--	--		
7.3.0	Final Inspection													
7.3.1	Workmanship, Finish & Paint shade / Thickness	Visual	Major	Visual	100%	G.A Drawing	Approved drgs.	Inspection report	*	P	W	V		
7.3.2	Overall Dimension, G.A of starter panel	Measurement	Major	Visual	100%	G.A Drawing	Approved drgs.	Test Certificate	-	P	W	V		
7.3.3	Component Identification	Visual	Major	Visual	100%	G.A Drawing	Approved drgs.	Inspection report	-	P	W	V		
7.3.4	IR - HV - IR	Electrical	Critical	Electrical	100%	Mfg.Procedure	Mfg. Pcedure	Inspection report	-	P	W	V		
7.3.5	Functional & Continuity	Functional	Major	Functional	100%	Appd Drawing	Appd Drawing	Inspection report	*	P	W	V		
			LEGEND											
			* Records identified with "STAR" shall be essentially included by contractor in QA Documentation.											
			** M : Manufacturer/ Sub-contractor											
Manufacturer / Sub-Contractor			Contractor			C : CONTRACTOR			O: OWNER					
Signature			Indicate : "P" - Perform, "W" - Witness and "V" - Verification											
										Name & Sign. Of approving authority & Seal				



Manufacturer's Name & Address

Manufacturing Quality Plan

BHEL Doc No.: PE-QP-999-165-N005

Item : Fasteners

Vendor Q.P. NO.

PROJECT:

P.O. No.

PACKAGE : SELF CLEANING STRAINER

CUSTOMER:

Date :

Page 11 of 12

PURCHASER:

CONSULTANT:

Sl. No.	Component / Operation	Characteristics Checked	Class	Type of Check	Quantum of Check	Reference Documents	Acceptance Norms	Format of Record	Agency			Remarks	
									M	C	O		
1	2	3	4	5	6	7	8	9	**	10		11	
8.1.0	Internal Fasteners - SS												
8.1.1	Stainless Steel Fasteners	Chemical properties	Major	Chemical analysis	1 Per heat/HT Batch	Approved Drawing	Approved Drawing	Test certificate/Compliance certificate	--	P	V	V	
		Physical properties	Major	Physical test	1 per heat	Approved Drawing	Approved Drawing	Test certificate/Compliance certificate	--	P	V	V	
		Visual and Workmanship finish	Major	Visual	Sample	Approved Drawing	Approved Drawing	Inspection report	--	P	V	V	
		Dimensions	Major	Measurement	Sample	Approved Drawing	Approved Drawing	Inspection report	--	P	V	V	
8.2.0	Carbon steel fasteners	Visual	Major	Visual	Sample	Approved Drawing	Approved Drawing	Manufacturer's certificate / Lab Report	--	P	V	V	
		Dimensions	Major	Measurement	Sample	Approved Drawing	Approved Drawing	Manufacturer's certificate / Lab Report	--	P	V	V	
		Physical properties	--	Physical test	1 sample per heat	IS : 1367	IS : 1367	Manufacturer's certificate / Lab Report	--	P	V	V	
				a) Tensile									
				b) Yield									
				c) Elongation									
				d) Proof load									
LEGEND													
* Records identified with "STAR" shall be essentially included by contractor in QA Documentation.													
** M : Manufacturer/ Sub-contractor													
C : CONTRACTOR O: OWNER													
Indicate : "P" - Perform, "W" - Witness and "V" - Verification													
Manufacturer / Sub-Contractor Signature										Contractor		Name & Sign, Of approving authority & Seal	



Manufacturer's Name & Address

P.O. No.

Manufacturing Quality Plan

Item : All components / Equipments

Vendor Q.P. NO.

PACKAGE : SELF CLEANING STRAINER

Date :

Page 12 of 12

BHEL Doc No.: PE-QP-999-165-N005

PROJECT:

CUSTOMER:

PURCHASER:

CONSULTANT:

Sl. No.	Component / Operation	Characteristics Checked	Class	Type of Check	Quantum of Check	Reference Documents	Acceptance Norms	Format of Record	Agency			Remarks		
									M	C	O			
1									**	10		11		
9.0.0	All Components / Equipments	Painting Dry film thickness	Major and	Measurement	Random	Painting schedule	Painting schedule	Inspection report	P	V	V			
		Packing	Major	Measurement	100%	Packing Procedure	Packing Procedure	Inspection report	P	-	-			
			LEGEND											
			* Records identified with "STAR" shall be essentially included by contractor in QA Documentation.											
			** M : Manufacturer/ Sub-contractor											
			C : CONTRACTOR O: OWNER											
Manufacturer / Sub-Contractor Signature			Contractor			Indicate : "P" - Perform, "W" - Witness and "V" - Verification							Name & Sign. Of approving authority & Seal	

DMS (BHEL-PEM)
6078316-2014/07/19



**TITLE : TECHNICAL SPECIFICATION
FOR
SELF CLEANING STRAINERS (SCS)**

SPEC. NO. PE-TS-405-165-N003

VOLUME : IIB

SECTION : D

REV. NO. 0

DATE :15.07.2014

SHEET 1of 1

**SECTION D2
STANDARD TECHNICAL SPECIFICATION
FOR
ELECTRICAL SYSTEMS**

TITLE :
GENERAL TECHNICAL REQUIREMENTS

FOR

LV MOTORS

SPECIFICATION NO. PE-SS-999-506-E101
VOLUME NO. : II-B
SECTION : D
REV NO. : 00 DATE : 28.01.10
SHEET : 1 OF 1

GENERAL TECHNICAL REQUIREMENTS

FOR

LV MOTORS

SPECIFICATION NO.: PE-SS-999-506-E101 Rev 00

	TITLE :	SPECIFICATION NO.
	GENERAL TECHNICAL REQUIREMENTS	PE-SS-999-506-E101
	FOR	VOLUME NO. : II-B
	LV MOTORS	SECTION : D
		REV NO. : 00 DATE : 28.01.10
		SHEET : 1 OF 4

1.0 INTENT OF SPECIFICATION

The specification covers the design, materials, constructional features, manufacture, inspection and testing at manufacturer's work, and packing of Low voltage (LV) squirrel cage induction motors along with all accessories for driving auxiliaries in thermal power station.

Motors having a voltage rating of below 1000V are referred to as low voltage (LV) motors.

2.0 CODES AND STANDARDS

Motors shall fully comply with latest edition, including all amendments and revision, of following codes and standards:

IS:325	Three phase Induction motors
IS : 900	Code of practice for installation and maintenance of induction motors
IS: 996	Single phase small AC and universal motors
IS: 4722	Rotating Electrical machines
IS: 4691	Degree of Protection provided by enclosures for rotating electrical machines
IS: 4728	Terminal marking and direction of rotation rotating electrical machines
IS: 1231	Dimensions of three phase foot mounted induction motors
IS: 8789	Values of performance characteristics for three phase induction motors
IS: 13555	Guide for selection and application of 3-phase A.C. induction motors for different types of driven equipment
IS: 2148	Flame proof enclosures for electrical appliance
IS: 5571	Guide for selection of electrical equipment for hazardous areas
IS: 12824	Type of duty and classes of rating assigned
IS: 12802	Temperature rise measurement of rotating electrical machines
IS: 12065	Permissible limits of noise level for rotating electrical machines
IS: 12075	Mechanical vibration of rotating electrical machines

In case of imported motors, motors as per IEC-34 shall also be acceptable.

3.0 DESIGN REQUIREMENTS

3.1 Motors and accessories shall be designed to operate satisfactorily under conditions specified in data sheet-A and Project Information, including voltage & frequency variation of supply system as defined in Data sheet-A

3.2 Motors shall be continuously rated at the design ambient temperature specified in Data Sheet-A and other site conditions specified under Project Information
Motor ratings shall have at least a 15% margin over the continuous maximum demand of the driven equipment, under entire operating range including voltage & frequency variation specified above.

3.3 Starting Requirements

3.3.1 Motor characteristics such as speed, starting torque, break away torque and starting time shall be properly co-ordinated with the requirements of driven equipment. The accelerating torque at any speed with the minimum starting voltage shall be at least 10% higher than that of the driven equipment.

3.3.2 Motors shall be capable of starting and accelerating the load with direct on line starting without exceeding acceptable winding temperature.

TITLE : GENERAL TECHNICAL REQUIREMENTS FOR LV MOTORS	SPECIFICATION NO. PE-SS-999-506-E101
	VOLUME NO. : II-B
	SECTION : D
	REV NO. : 00 DATE : 28.01.10
	SHEET : 2 OF 4

The limiting value of voltage at rated frequency under which a motor will successfully start and accelerate to rated speed with load shall be taken to be a constant value as per Data Sheet - A during the starting period of motors.

3.3.3 The following frequency of starts shall apply

- i) Two starts in succession with the motor being initially at a temperature not exceeding the rated load temperature.
- ii) Three equally spread starts in an hour the motor being initially at a temperature not exceeding the rated load operating temperature. (not to be repeated in the second successive hour)
- iii) Motors for coal conveyor and coal crusher application shall be suitable for three consecutive hot starts followed by one hour interval with maximum twenty starts per day and shall be suitable for minimum 20,000 starts during the life time of the motor

3.4 **Running Requirements**

3.4.1 Motors shall run satisfactorily at a supply voltage of 75% of rated voltage for 5 minutes with full load without injurious heating to the motor.

3.4.2 Motor shall not stall due to voltage dip in the system causing momentary drop in voltage upto 70% of the rated voltage for duration of 2 secs.

3.5 **Stress During bus Transfer**

3.5.1 Motors shall withstand the voltage, heavy inrush transient current, mechanical and torque stress developed due to the application of 150% of the rated voltage for at least 1 sec. caused due to vector difference between the motor residual voltage and the incoming supply voltage during occasional auto bus transfer.

3.5.2 Motor and driven equipment shafts shall be adequately sized to satisfactorily withstand transient torque under above condition.

3.6 Maximum noise level measured at distance of 1.0 metres from the outline of motor shall not exceed the values specified in IS 12065.

3.7 The max. vibration velocity or double amplitude of motors vibration as measured at motor bearings shall be within the limits specified in IS: 12075.

4.0 **CONSTRUCTIONAL FEATURES**

4.1 Indoor motors shall conform to degree of protection IP: 54 as per IS: 4691. Outdoor or semi-indoor motors shall conform to degree of protection IP: 55 as per IS: 4691 and shall be of weather-proof construction. Outdoor motors shall be installed under a suitable canopy

4.2 Motors upto 160KW shall have Totally Enclosed Fan Cooled (TEFC) enclosures, the method of cooling conforming to IC-0141 or IC-0151 of IS: 6362.

Motors rated above 160 KW shall be Closed Air Circuit Air (CACA) cooled

4.3 Motors shall be designed with cooling fans suitable for both directions of rotation.

	TITLE :	SPECIFICATION NO.
	GENERAL TECHNICAL REQUIREMENTS	PE-SS-999-506-E101
	FOR	VOLUME NO. : II-B
	LV MOTORS	SECTION : D
		REV NO. : 00 DATE : 28.01.10
		SHEET : 3 OF 4

- 4.4. Motors shall not be provided with any electric or pneumatic operated external fan for cooling the motors.
- 4.5. Frames shall be designed to avoid collection of moisture and all enclosures shall be provided with facility for drainage at the lowest point.
- 4.6. In case Class 'F' insulation is provided for LV motors, temperature rise shall be limited to the limits applicable to Class 'B' insulation.
In case of continuous operation at extreme voltage limits the temperature limits specified in table-1 of IS:325 shall not exceed by more than 10°C.
- 4.7 Terminals and Terminal Boxes**
- 4.7.1 Terminals, terminal leads, terminal boxes, windings tails and associated equipment shall be suitable for connection to a supply system having a short circuit level, specified in the Data Sheet-A.

Unless otherwise stated in Data Sheet-A, motors of rating 110 kW and above will be controlled by circuit breaker and below 110 kW by switch fuse-contactor. The terminal box of motors shall be designed for the fault current mentioned in data sheet "A".
- 4.7.2 Unless otherwise specified or approved, phase terminal boxes of horizontal motors shall be positioned on the left hand side of the motor when viewed from the non-driving end.
- 4.7.3 Connections shall be such that when the supply leads R, Y & B are connected to motor terminals A B & C or U, V & W respectively, motor shall rotate in an anticlockwise direction when viewed from the non-driving end. Where such motors require clockwise rotation, the supply leads R, Y, B will be connected to motor terminals A, C, B or V W & V respectively.
- 4.7.4 Permanently attached diagram and instruction plate made preferably of stainless steel shall be mounted inside terminal box cover giving the connection diagram for the desired direction of rotation and reverse rotation.
- 4.7.5 Motor terminals and terminal leads shall be fully insulated with no bar live parts. Adequate space shall be available inside the terminal box so that no difficulty is encountered for terminating the cable specified in Data Sheet-A.
- 4.7.6 Degree of protection for terminal boxes shall be IP 55 as per IS 4691.
- 4.7.7 Separate terminal boxes shall be provided for space heaters.. If this is not possible in case of LV motors, the space heater terminals shall be adequately segregated from the main terminals in the main terminal box. Detachable gland plates with double compression brass glands shall be provided in terminal boxes.
- 4.7.8. Phase terminal boxes shall be suitable for 360 degree of rotation in steps of 90 degree for LV motors.
- 4.7.9 Cable glands and cable lugs as per cable sizes specified in Data Sheet-A shall be included. Cable lugs shall be of tinned Copper, crimping type.
- 4.8 Two separate earthing terminals suitable for connecting G.I. or MS strip grounding conductor of size given in Data Sheet-A shall be provided on opposite sides of motor frame. Each terminal box shall have a grounding terminal.

4.9 General

TITLE : GENERAL TECHNICAL REQUIREMENTS FOR LV MOTORS	SPECIFICATION NO. PE-SS-999-506-E101
	VOLUME NO. : II-B
	SECTION : D
	REV NO. : 00 DATE : 28.01.10
	SHEET : 4 OF 4

- 4.9.1 Motors provided for similar drives shall be interchangeable.
- 4.9.2 Suitable foundation bolts are to be supplied alongwith the motors.
- 4.9.3 Motors shall be provided with eye bolts, or other means to facilitate safe lifting if the weight is 20Kgs. and above.
- 4.9.4 Necessary fitments and accessories shall be provided on motors in accordance with the latest Indian Electricity rules 1956.
- 4.9.5 All motors rated above 30 kW shall be provided with space heaters to maintain the motor internal air temperature above the dew point. Unless otherwise specified, space heaters shall be suitable for a supply of 240V AC, single phase, 50 Hz.
- 4.9.6 Name plate with all particulars as per IS: 325 shall be provided
- 4.9.7 Unless otherwise specified, the colour of finish shall be grey to Shade No. 631 and 632 as per IS:5 for motors installed indoor and outdoor respectively. The paint shall be epoxy based and shall be suitable for withstanding specified site conditions.
- 5.0 INSPECTION AND TESTING**
- 5.1 All materials, components and equipments covered under this specification shall be procured, manufactured, as per the BHEL standard quality plan No. PED-506-00-Q-006/0 and PED-506-00-Q-007/2 enclosed with this specification and which shall be complied.
- 5.2 LV motors of type-tested design shall be provided. Valid type test reports not more than 5 year shall be furnished. In the absence of these, type tests shall have to be conducted by manufacturer without any commercial implication to purchaser.
- 5.3 All motors shall be subjected to routine tests as per IS: 325 and as per BHEL standard quality plan.
- 5.4 Motors shall also be subjected to additional tests, if any, as mentioned in Data Sheet A.
- 6.0 DRAWINGS TO BE SUBMITTED AFTER AWARD OF CONTRACT**
- a) OGA drawing showing the position of terminal boxes, earthing connections etc.
- b) Arrangement drawing of terminal boxes.
- c) Characteristic curves:
(To be given for motor above 55 kW unless otherwise specified in Data Sheet).
- i) Current vs. time at rated voltage and minimum starting voltage.
- ii) Speed vs. time at rated voltage and minimum starting voltage.
- iii) Torque vs. speed at rated voltage and minimum voltage.
For the motors with solid coupling the above curves i), ii), iii) to be furnished for the motors coupled with driven equipment. In case motor is coupled with mechanical equipment by fluid coupling, the above curves shall be furnished with and without coupling.
- iv) Thermal withstand curve under hot and cold conditions at rated voltage and max. permissible voltage.



MOTOR

TESTS/CHECKS TEMS/COMPONENTS	Visual	Dimensional	Make/Type/Rating /General Physical Inspection	Mech/Chem. Properties	NDT /DP/MPI/UT	Metallography	Electrical Characteristics	Welding/Brazing(WPS/PQR)	Heat Treatment
Plates for stator frame, end shield, spider etc.	Y	Y	Y	Y	Y				Y
Shaft	Y	Y	Y	Y	Y	Y			Y
Magnetic Material	Y	Y	Y	Y			Y		
Rotor Copper/Aluminium	Y	Y	Y	Y			Y		Y
Stator copper	Y	Y	Y	Y			Y		Y
SC Ring	Y	Y	Y	Y	Y		Y	Y	Y
Insulating Material	Y		Y	Y			Y		
Tubes, for Cooler	Y	Y	Y	Y	Y				Y
Sleeve Bearing	Y	Y	Y	Y	Y				Y
Stator/Rotor, Exciter Coils	Y	Y	Y				Y	Y	
Castings, stator frame, terminal box and bearing housing etc.	Y	Y	Y	Y	Y			Y	
Fabrication & machining of stator, rotor, terminal box	Y	Y			Y			Y	Y
Wound stator	Y	Y					Y	Y	
Wound Exciter	Y	Y					Y	Y	
Rotor complete	Y	Y					Y		
Exciter, Stator, Rotor, Terminal Box assembly	Y	Y					Y		
Accessories, RTD, BTD,CT, Space heater, antifriction bearing, gaskets etc.	Y	Y	Y						
Complete Motor	Y	Y	Y						

Note: 1. This is an indicative list of tests/checks. The manufacture is to furnish a detailed Quality Plan indicating the practices & Procedure followed along with relevant supporting documents during QP finalization. However, No QP for LT motor upto 50KW.
 2. Additional routine tests for Flame proof motors shall be applicable as per relevant standard
 3. Makes of major bought out items for HT motors will be subject to NTPC approval.
 Y1 = for HT Motor / Machines only.



MOTOR

TESTS/CHECKS	Magnetic Characteristics	Hydraulic/Leak/Pressure Test	Thermal Characteristics	Run out	Dynamic Balancing	Routine & Acceptance tests as per IS-325/IS-4722 /IS- 9283/IS 2148/IEC60034/IEC 60079-I	vibration	Over speed	Tan delta, shaft voltage & polarization index test	Paint shade, thickness & adhesion
ITEMS/COMPONENTS										
Plates for stator frame, end shield, spider etc.										
Shaft										
Magnetic Material	Y		Y							
Rotor Copper/Aluminium										
Stator copper			Y							
SC Ring										
Insulating Material			Y							
Tubes for Cooler		Y								
Sleeve Bearing		Y								
Stator/Rotor, Exciter Coils										
Castings, stator frame, terminal box and bearing housing etc.										
Fabrication & machining of stator, rotor, terminal box										
Wound stator										
Wound Exciter										
Rotor complete				Y	Y					
Exciter, Stator, Rotor, Terminal Box assembly										
Accessories, RTD, BTD, CT, , Space heater, antifriction bearing, gaskets etc.										
Complete Motor						Y	Y	Y	Y1	Y

Note: 1. This is an indicative list of tests/checks. The manufacture is to furnish a detailed Quality Plan indicating the practices & Procedure followed along with relevant supporting documents during QP finalization. However, No QP for LT motor upto 50KW.
 2. Additional routine tests for Flame proof motors shall be applicable as per relevant standard
 3. Makes of major bought out items for HT motors will be subject to NTPC approval.
 Y1 = for HT Motor / Machines only.

		QUALITY PLAN		CUSTOMER :			PROJECT			SPECIFICATION :		
		SHEET 1 OF 2		BIDDER/ VENDOR :			TITLE			NUMBER :		
				SYSTEM			QUALITY PLAN NUMBER PED-506-00-Q-006, REV-01			SPECIFICATION TITLE		
							ITEM AC ELECT. MOTORS BELOW 55KW (LV)			SECTION		VOLUME III
SL. NO.	COMPONENT/OPERATION	CHARACTERISTICS CHECK	CAT.	TYPE/METHOD OF CHECK	EXTENT OF CHECK	REFERENCE DOCUMENT	ACCEPTANCE NORM	FORMAT OF RECORD	AGENCY			REMARKS
									P	W	V	
1	2	3	4	5	6	7	8	9	10			11
1.0	ASSEMBLY	1.WORKMANSHIP	MA	VISUAL	100%	MANUF'S SPEC	MANUF'S SPEC	-DO-	2	-	-	
		2.DIMENSIONS	MA	-DO-	-DO-	MFG. DRG./MFG. SPEC.	MFG. DRG./MFG. SPEC.	-DO-	2	-	-	
		3.CORRECTNESS COMPLETENESS TERMINATIONS/ MARKING/COLOUR CODE	MA	VISUAL	100%	MFG.SPEC./RELEVANT IS	MFG.SPEC. RELEVANT IS	-DO-	2	-	-	
2.0	PAINTING	1.SHADE	MA	VISUAL	SAMPLE	MANUFR'S SPEC/BHEL SPEC./RELEVANT STANDARD	BHEL SPEC. SAME AS COL.7	LOG BOOK	2	-	-	
3.0	TESTS	1.ROUTINE TEST INCLUDING SPECIAL TEST AS PER BHEL SPEC.	MA	-DO-	100%	IS-325/BHEL SPEC./DATA SHEET	SAME AS COL.7	TEST REPORT	2	1	-	NOTE -1 & NOTE-3
		2.OVERALL DIMENSIONS & ORIENTATION	MA	MEASUREMENT & VISUAL	100%	APPROVED DRG/DATA SHEET	APPROVED DRG/DATA SHEET & RELEVANT IS	INSPN. REPORT	2	1	-	NOTE -1 & NOTE-3
BHEL			PARTICULARS			BIDDER/VENDOR						
			NAME									
			SIGNATURE									



QUALITY PLAN

SHEET 2 OF 2

CUSTOMER :

PROJECT

SPECIFICATION :

BIDDER/ :

TITLE

NUMBER :

VENDOR

QUALITY PLAN
NUMBER PED-506-00-Q-006, REV-01

SPECIFICATION :

SYSTEM

ITEM AC ELECT. MOTORS BELOW 55KW (LV)

TITLE :

SECTION

VOLUME III

SL. NO.	COMPONENT/OPERATION	CHARACTERISTICS CHECK	CAT.	TYPE/METHOD OF CHECK	EXTENT OF CHECK	REFERENCE DOCUMENT	ACCEPTANCE NORM	FORMAT OF RECORD	AGENCY			REMARKS
									P	W	V	
1	2	3	4	5	6	7	8	9	10			11
		3.NAMEPLATE DETAILS	MA	VISUAL	100%	IS-325 & DATA SHEET	IS-325 & DATA SHEET	INSPN. REPORT	2	1	-	
<p>NOTES:</p> <p>1 ROUTINE TESTS ON 100% MOTORS SHALL BE DONE BY THE VENDOR. HOWEVER, BHEL SHALL WITNESS ROUTINE TESTS ON RANDOM SAMPLES. THE SAMPLING PLAN SHALL BE MUTUALLY AGREED UPON</p> <p>2 WHERE EVER CUSTOMER IS INVOLVED IN INSPECTION, (1) SHALL MEAN BHEL AND CUSTOMERS BOTH TOGETHER.</p> <p>3 FOR EXHAUST/VENTILATION FAN MOTORS OF RATING UPTO 1.5KW , ONLY ROUTINE TEST CERTIFICATES SHALL BE FURNISHED FOR SCRUTINY.</p> <p><u>Legends for Inspection agency</u></p> <p>1. BHEL/CUSTOMER 2. VENDOR (MOTOR MANUFACTURER) 3. SUB-VENDOR (RAW MATERIAL/COMPONENTS SUPPLIER)</p> <p>P. PERFORM W. WITNESS V. VERIFY</p>												
BHEL			PARTICULARS			BIDDER/VENDOR						
			NAME									
			SIGNATURE									
			DATE						BIDDER'S/VENDORS COMPANY SEAL			

		QUALITY PLAN			CUSTOMER :		PROJECT TITLE		SPECIFICATION : NUMBER :			
		SHEET 1 OF 9			BIDDER/ VENDOR :		QUALITY PLAN NUMBER PED-506-00-Q-007, REV-03		SPECIFICATION : TITLE			
		SYSTEM			ITEM: AC ELECT. MOTORS 55 KW & ABOVE (LV & MV)		SECTION		VOLUME III			
SL. NO.	COMPONENT/OPERATION	CHARACTERISTIC CHECK	CAT.	TYPE/ METHOD OF CHECK	EXTENT OF CHECK	REFERENCE DOCUMENT	ACCEPTANCE NORM	FORMAT OF RECORD	AGENCY			REMARKS
1	2	3	4	5	6	7	8	9	P	W	V	11
1.0	RAW MATERIAL & BOUGHT OUT CONTROL											
1.1	SHEET STEEL, PLATES, SECTION, EYEBOLTS	1.SURFACE CONDITION	MA	VISUAL	100%	-	FREE FROM BLINKS, CRACKS, WAVINESS ETC	LOG BOOK	3	-	-	
		2.DIMENSIONS	MA	MEASUREMENT	SAMPLE	MANFR'S DRG./SPEC	MANFR'S DRG./SPEC	-DO-	3	-	-	
		3.PROOF LOAD TEST (EYE BOLT)	MA	MECH. TEST	-DO-	-DO-	-DO-	INSPEC. REPORT	3	-	2	
1.2	HARDWARES	1.SURFACE CONDITION	MA	VISUAL	100%		FREE FROM CRACKS, UN-EVENNESS ETC.	-DO-	3	-	-	
		2.PROPERTY CLASS	MA	VISUAL	SAMPLES	MANFR'S DRG./SPEC BOOK	RELEVENT IS/SPEC.	SUPPLIERS TC & LOG	3	-	2	PROPERTY CLASS MARKING SHALL BE CHECKED BY THE VENDOR
1.3	CASTING	1.SURFACE CONDITION	MA	VISUAL	100%		FREE FROM CRACKS, BLOW HOLES ETC.	LOG BOOK	3	-	2	
		2.CHEM. & PHY. PROP.	MA	CHEM & MECH TEST	1/HEAT NO.	MANFR'S DRG./SPEC	RELEVENT IS/	SUPPLIER'S TC	3	-	2	HEAT NO. SHALL BE VERIFIED
		3.DIMENSIONS	MA	MEASUREMENT	100%	MANUFR'S M DRG.	ANUFR'S DRG.	LOG BOOK	3	-	2	
1.4	PAINT & VARNISH	1.MAKE, SHADE, SHELF LIFE & TYPE	MA	VISUAL	100% CONTINUOUS	MANFR'S DRG./SPEC	MANFR'S DRG./SPEC	LOG BOOK	3	-	2	
BHEL			PARTICULARS		BIDDER/VENDOR							
			NAME									
			SIGNATURE									
			DATE				BIDDER'S/VENDORS COMPANY SEAL					



QUALITY PLAN

SHEET 2 OF 9

CUSTOMER :	PROJECT TITLE	SPECIFICATION : NUMBER :
BIDDER/ VENDOR :	QUALITY PLAN NUMBER PED-506-00-Q-007, REV-03	SPECIFICATION : TITLE
SYSTEM	ITEM: AC ELECT. MOTORS 55 KW & ABOVE (LV & MV)	SECTION VOLUME III

SL. NO.	COMPONENT/OPERATION	CHARACTERISTIC CHECK	CAT.	TYPE/ METHOD OF CHECK	EXTENT OF CHECK	REFERENCE DOCUMENT	ACCEPTANCE NORM	FORMAT OF RECORD	AGENCY			REMARKS
									P	W	V	
1	2	3	4	5	6	7	8	9	10			11
1.5	SHAFT (FORGED OR ROLLED)	1. SURFACE COND. 2. CHEM. & PHYSICAL PROPERTIES 3. DIMENSIONS 4. INTERNAL FLAWS	MA MA MA CR	VISUAL CHEM. & PHYSICAL TESTS MEASUREMENT UT	100% 1/HEAT NO. OR HEAT TREATMENT BATCH NO 100%	- MFG. DRG. SPEC. -DO- ASTM-A388	FREE FROM VISUAL DEFECTS RELEVANT IS MANUFR'S DRG. MANUFR'S SPEC. BHEL SPEC.	-DO- SUPPLIER'S TC LOG BOOK -DO-	3 3 3 3	- - - 2	- 2 2 1	VENDOR'S APPROVAL IDENTIFICATION SHALL BE MAINTAINED FOR DIA OF 55 MM & ABOVE
1.6	SPACE HEATERS, CONNECTORS, TERMINAL BLOCKS, CABLES, CABLE LUGS, CARBON BRUSH TEMP. DETECTORS, RTD, BTD'S	1. MAKE & RATING 2. PHYSICAL COND. 3. DIMENSIONS (WHEREVER APPLICABLE) 4. PERFORMANCE/ CALIBRATION	MA MA MA MA	VISUAL -DO- MEASUREMENT TEST	-DO- -DO- SAMPLE 100%	MANUFR'S DRG. SPEC. - MANUFR'S DRG./ SPEC. -DO-	MANUFR'S DRG. SPEC. NO PHYS. DAMAGE, NO ELECTRICAL DISCONTINUITY MANUFR'S DRG. / SPEC. -DO-	-DO- -DO- -DO- INSP. REPORT	3 3 3 3	- - - -	2 2 2 2	
BHEL			PARTICULARS		BIDDER/VENDOR							
			NAME									
			SIGNATURE									
			DATE									
										BIDDER'S/VENDORS COMPANY SEAL		



QUALITY PLAN

SHEET 3 OF 9

CUSTOMER :

PROJECT

SPECIFICATION :

BIDDER/
VENDOR

TITLE
QUALITY PLAN
NUMBER PED-506-00-Q-007, REV-03

NUMBER :

SPECIFICATION :
TITLE

SYSTEM

ITEM: AC ELECT. MOTORS 55 KW & ABOVE (LV & MV)

SECTION

VOLUME III

SL. NO.	COMPONENT/OPERATION	CHARACTERISTIC CHECK	CAT.	TYPE/METHOD OF CHECK	EXTENT OF CHECK	REFERENCE DOCUMENT	ACCEPTANCE NORM	FORMAT OF RECORD	AGENCY			REMARKS
									P	W	V	
1	2	3	4	5	6	7	8	9	10			11
1.7	OTHER INSULATING MATERIALS LIKE SLEEVES, BINDINGS CORDS, PAPERS, PRESS BOARDS ETC.	1. SURFACE COND. ETC. 2. OTHER CHARACTERISTICS	MA MA	VISUAL TEST	100% SAMPLE	- MANUF'S SPEC.	NO VISUAL DEFECTS MANUF'S SPEC.	INSPT. REPORT LOG BOOK AND OR SUPPLIER'S TC	3 3	- -	2 2	
1.8	SHEET STAMPING (PUNCHED)	1. SURFACE COND. 2. DIMENSIONS INCLUDING BURS HEIGHT 3. ACCEPTANCE TESTS	MA MA MA	VISUAL MEASUREMENT ELECT. & MECH TESTS	100% SAMPLE -DO-	- MANUF'S DRG. . MANUF'S SPEC./ RELEVANT IS	NO VISUAL DEFECTS (FREE FROM BURS) MANUF'S DRG. RELEVANT IS	LOG BOOK -DO- SUPPLIER'S TC	3 3 3	- -	- 2 2	
1.9	CONDUCTORS	1. SURFACE FINISH 2. ELECT. PROP, & MECH. PROP	MA MA	VISUAL ELECT. & MECH. TEST	100% SAMPLES	- RELEVANT IS/ BS OR OTHER STANDARDS	FREE FROM VISUAL DEFECTS RELEVANT IS/ BS OR OTHER STANDARDS	LOG BOOK SUPPLIERS TC & VENDOR'S INSPN. REPORTS	3* 3	- -	2* 2	* MOTOR MANUFACTURER TO CONDUCT VISUAL CHECK FOR SURFACE FINISH ON RANDOM BASIS (10% SAMPLE) AT HIS WORKS AND MAINTAIN RECORD FOR VERIFICATION BY BHEL/CUSTOMER.
BHEL			PARTICULARS			BIDDER/VENDOR						
			NAME									
			SIGNATURE									
			DATE			BIDDER'S/VENDORS COMPANY SEAL						



QUALITY PLAN

SHEET 4 OF 9

CUSTOMER :

BIDDER/ VENDOR :

SYSTEM :

PROJECT TITLE

QUALITY PLAN NUMBER PED-506-00-Q-007, REV-03

ITEM: AC ELECT. MOTORS 55 KW & ABOVE (LV & MV)

SPECIFICATION :

NUMBER :

SPECIFICATION : TITLE

SECTION VOLUME III

SL. NO.	COMPONENT/OPERATION	CHARACTERISTIC CHECK	CAT.	TYPE/METHOD OF CHECK	EXTENT OF CHECK	REFERENCE DOCUMENT	ACCEPTANCE NORM	FORMAT OF RECORD	AGENCY			REMARKS
									P	W	V	
1	2	3	4	5	6	7	8	9	10			11
1.10	BEARINGS	3.DIMENSIONS	MA	MEASUREMENT	-DO-	-DO-	-DO-	Log Book	3	-	2	
		1.MAKE & TYPE	MA	VISUAL	100%	MANFR'S DRG./ APPROVED DATASHEET	MANFR'S DRG./ APPROVED DATASHEET	-DO-	3	-	2	
		2.DIMENSIONS	MA	MEASUREMENT	SAMPLE	BHEL DATA SHEET	BHEL DATA SHEET BEARING MANUF'S CATALOGUES	-DO-	3	-	2	
		3.SURFACE FINISH	MA	VISUAL	100%	-	FREE FROM VISUAL DEFECTS	-DO-	3	-	2	
1.11	SLIP RING (WHEREVER APPLICABLE)	1.SURFACE COND.	MA	VISUAL	100%	-	-DO-	-DO-	3	-	-	
		2.DIMENSIONS	MA	MEASUREMENT	SAMPLE	MANUF'S DRG	MANUF'S DRG	-DO-	3	-	-	
		3.TEMP.WITH-STAND CAPACITY	MA	ELECT.TEST	-DO-	MANUF'S SPEC./ BHEL SPEC.	MANUF'S SPEC./ BHEL SPEC.	-DO-	3	-	2	
		4.HV/IR	MA	-DO-	100%	-DO-	-DO-	-DO-	3	-	2	
1.12	OIL SEALS & GASKETS	1.MATERIAL OF GASKET	MA	VISUAL	100%	MANUF'S DRG/SPECS	MANUF'S DRG./ SPECS.	-DO-	3	-	-	
		2.SURFACE COND.	MA	VISUAL	100%	-	FREE FROM VISUAL DEFECTS	-DO-	3	-	-	
		3.DIMENSIONS	MA	MEASUREMENT	SAMPLE	MANUF'S DRG	MANUF'S DRG	-DO-	3	-	-	
BHEL			PARTICULARS			BIDDER/VENDOR						
			NAME									
			SIGNATURE									
			DATE						BIDDER'S/VENDORS COMPANY SEAL			



QUALITY PLAN

SHEET 5 OF 9

CUSTOMER :

PROJECT

SPECIFICATION :

BIDDER/ VENDOR :

QUALITY PLAN
NUMBER PED-506-00-Q-007, REV-03

SPECIFICATION :
TITLE

SYSTEM

ITEM: AC ELECT. MOTORS 55 KW & ABOVE (LV & MV)

SECTION VOLUME III

SL. NO.	COMPONENT/OPERATION	CHARACTERISTIC CHECK	CAT.	TYPE/METHOD OF CHECK	EXTENT OF CHECK	REFERENCE DOCUMENT	ACCEPTANCE NORM	FORMAT OF RECORD	AGENCY			REMARKS
									P	W	V	
1	2	3	4	5	6	7	8	9	10			11
2.0	IN PROCESS											
2.1	STATOR FRAME WELDING (IN CASE OF FABRICATED STATOR)	1.WORKMANSHIP & CLEANNESS	MA	VISUAL	100%	-DO-	GOOD FINISH	LOG BOOK	3/2	2	-	
		2.DIMENSIONS	MA	MEASUREMENT	-DO-	MANUF'S DRG	MANUF'S DRG	-DO-	2	-	-	
2.2	MACHINING	1.FINISH	MA	VISUAL	100%	-DO-	GOOD FINISH	LOG BOOK	2	-	-	
		2.DIMENSIONS	MA	MEASUREMENT	-DO-	MANUF'S DRG	MANUF'S DRG	-DO-	2	-	-	
		3.SHAFT SURFACE FLOWS	MA	PT	-DO-	RELEVANT SPEC./ ASTM-E165	MANUF'R'S SPEC./ BHEL SPEC./	-DO-	2	-	1	
2.3	PAINING	1.SURFACE PREPARATION	MA	VISUAL	100%	MANFR'S SPEC/BHEL SPEC./ RELEVANT STAND	BHEL SPEC. SAME AS COL.7	LOG BOOK	2	-	-	
		2.PAINT THICKNESS (BOTH PRIMER & FINISH COAT)	MA	MEASUREMENT BY ELCOMETER	SAMPLE	-DO-	-DO-	-DO-	2	-	-	
		3.SHADE	MA	VISUAL	-DO-	-DO-	-DO-	Log Book	2	-	-	
		4.ADHESION	MA	CROSS CUTTING & TAPE TEST	-DO-	-DO-	-DO-	Log Book	2	-	-	
BHEL			PARTICULARS			BIDDER/VENDOR						
			NAME									
			SIGNATURE									
			DATE						BIDDER'S/VENDORS COMPANY SEAL			



QUALITY PLAN

SHEET 6 OF 9

CUSTOMER :

PROJECT
TITLE

SPECIFICATION :
NUMBER :

BIDDER/
VENDOR

QUALITY PLAN
NUMBER PED-506-00-Q-007, REV-03

SPECIFICATION :
TITLE

SYSTEM

ITEM: AC ELECT. MOTORS 55 KW & ABOVE (LV & MV)

SECTION

VOLUME III

SL. NO.	COMPONENT/OPERATION	CHARACTERISTIC CHECK	CAT.	TYPE/METHOD OF CHECK	EXTENT OF CHECK	REFERENCE DOCUMENT	ACCEPTANCE NORM	FORMAT OF RECORD	AGENCY			REMARKS	
									P	W	V		
1	2	3	4	5	6	7	8	9	10			11	
2.4	SHEET STACKING	1.COMPLETENESS	MA	MEASUREMENT	SAMPLE	MANUFR'S SPEC.	MANUFR'S SPEC.	Log Book	2	-	-	(FOR MOTORS OF 2MW AND ABOVE) * ON 10% RANDOM SAMPLE	
		2.COMPRESSION & TIGHTENING	MA	MEASUREMENT	100%	-DO-	-DO-	Log Book	2	-	-		
		3.CORE LOSS & HOTSPOT	MA	ELECT.TEST	-DO-	-DO-	-DO-	Log Book	2	1*	1		
2.5	WINDING	1.COMPLETENESS	CR	VISUAL	100%	MANUFR'S SPEC./BHEL SPEC. SPEC. SPEC.	MANUFR'S /BHEL	Log Book	2	-	-		
		2.CLEANLINESS	CR	-DO-	-DO-	-DO-	-DO-	Log Book	2	-	-		
		3.IR-HV-IR	CR	ELECT. TEST	-DO-	-DO-	-DO-	Log Book	2	-	1		
		4.RESISTANCE	CR	-DO-	-DO-	-DO-	-DO-	Log Book	2	-	1		
		5.INTERTURN INSULATION	CR	-DO-	-DO-	-DO-	-DO-	Log Book	2	-	-		
2.6	IMPREGNATION	6.SURGE WITH STAND AND TAN. DELTA TEST	CR	-DO-	-DO-	-DO-	-DO-	Log Book	2	-	1		FOR MV MOTOR
		1.VISCOSCITY	MA	PHY. TEST	AT STARTING	-DO-	-DO-	Log Book	2	-	-		
		2.TEMP. PRESSURE VACCUM	MA	PROCESS CHECK	CONTINUOUS	-DO-	-DO-	Log Book	2	-	-		
		3.NO. OF DIPS	MA	-DO-	-DO-	-DO-	-DO-	Log Book	2	-	1	THREE DIPS TO BE GIVEN	
BHEL			PARTICULARS			BIDDER/VENDOR							
			NAME										
			SIGNATURE										
			DATE						BIDDER'S/VENDORS COMPANY SEAL				



QUALITY PLAN

SHEET 7 OF 9

CUSTOMER :

PROJECT

SPECIFICATION :

BIDDER/
VENDOR

QUALITY PLAN
NUMBER PED-506-00-Q-007, REV-03

NUMBER :

SPECIFICATION :
TITLE

SYSTEM

ITEM: AC ELECT. MOTORS 55 KW & ABOVE (LV & MV)

SECTION

VOLUME III

SL. NO.	COMPONENT/OPERATION	CHARACTERISTIC CHECK	CAT.	TYPE/METHOD OF CHECK	EXTENT OF CHECK	REFERENCE DOCUMENT	ACCEPTANCE NORM	FORMAT OF RECORD	AGENCY			REMARKS
									P	W	V	
1	2	3	4	5	6	7	8	9	10			11
2.7	COMPLETE STATOR ASSEMBLY	4.DURATION 1.COMPACTNESS & CLEANLINESS	MA MA	-DO- VISUAL	-DO- 100%	-DO- -DO-	-DO- -DO-	Log Book Log Book	2 2	- -	1 -	
2.8	BRAZING/COMPRESSION JOINT	1.COMPLETENESS 2.SOUNDNESS	CR CR	-DO- MALLETT TEST & UT	-DO- -DO-	-DO- -DO-	-DO- -DO-	Log Book Log Book	2 2	- -	- 1	
2.9	COMPLETE ROTOR ASSEMBLY	3.HV 1.RESIDUAL UNBALANCE	MA CR	ELECT. TEST DYN. BALANCE	-DO- -DO-	-DO- MFG SPEC./ ISO 1940	-DO- MFG. DWG.	Log Book Log Book	2 2	- -	1 1	VERIFICATION FOR MV MOTOR ONLY
2.10	ASSEMBLY	2.SOUNDNESS OF DIE CASTING 1.ALIGNMENT 2.WORKMANSHIP 3.AXIAL PLAY 4.DIMENSIONS 5.CORRECTNESS, COMPLETENESS TERMINATIONS/ MARKING/ COLOUR CODE 6. RTD, BTD & SPACE HEATER MOUNTING.	CR MA MA MA MA MA MA	ELECT. (GROWLER TEST) MEAS. VISUAL MEAS. -DO- VISUAL	-DO- -DO- -DO- -DO- 100%	-DO- -DO- -DO- MFG.DRG./ MFG SPEC. MFG SPEC. RELEVANT IS	-DO- -DO- -DO- MFG. DRG/ RELEVANT IS	Log Book Log Book Log Book Log Book Log Book	2 2 2 2 2	- - - - -	- - - - -	
BHEL			PARTICULARS		BIDDER/VENDOR							
			NAME									
			SIGNATURE									
			DATE									
									BIDDER'S/VENDORS COMPANY SEAL			



QUALITY PLAN

SHEET 8 OF 9

CUSTOMER :			PROJECT TITLE			SPECIFICATION : NUMBER :		
BIDDER/ VENDOR :			QUALITY PLAN NUMBER PED-506-00-Q-007, REV-03			SPECIFICATION : TITLE		
SYSTEM			ITEM: AC ELECT. MOTORS 55 KW & ABOVE (LV & MV)			SECTION		VOLUME III

SL. NO.	COMPONENT/OPERATION	CHARACTERISTIC CHECK	CAT.	TYPE/ METHOD OF CHECK	EXTENT OF CHECK	REFERENCE DOCUMENT	ACCEPTANCE NORM	FORMAT OF RECORD	AGENCY			REMARKS
									P	W	V	
1	2	3	4	5	6	7	8	9	10			11
3.0	TESTS	1.TYPE TESTS INCLUDING SPECIAL TESTS AS PER BHEL SPEC.	MA	ELECT.TEST	1/TYPE/SIZE	IS-325/ BHEL SPEC./ DATA SHEET	IS-325/ BHEL SPEC./ DATA SHEET	TEST REPORT	2	1*	1	* NOTE - 1
		2.ROUTINE TESTS INCLUDING SPECIAL TEST AS PER BHEL SPEC.	MA	-DO-	100%	-DO-	-DO-	-DO-	2	1 ^s	1	^s NOTE - 2
		3.VIBRATION & NOISE LEVEL	MA	-DO-	100%	IS-12075 & IS-12065	IS-12075 & IS-12065	-DO-	2	1 ^s	1	^s NOTE - 2
		4.OVERALL DIMENSIONS AND ORIENTATION	MA	MEASUREMENT & VISUAL	100%	APPROVED DRG/DATA SHEET	APPROVED DRG/DATA SHEET & RELEVANT IS	INSPC. REPORT	2	1	-	
		5.DEGREE OF PROTECTION	MA	ELECT. & MECH. TEST	1/TYPE/ SIZE	RELEVANT IS	BHEL SPEC. AND DATA SHEET	TC	2	-	1	TC FROM AN INDEPENDENT LABORATORY, REFER NOTE-3
		6. MEASUREMENT OF RESISTANCE OF RTD & BTD	MA	-DO-	100%	-DO-	-DO-	-DO-	2	1 ^s	1	^s NOTE - 2
		7. MEASUREMENT OF RESISTANCE, IR OF SPACE HEATER	MA	-DO-	100%	-DO-	-DO-	-DO-	2	1 ^s	1	^s NOTE - 2
		8. NAMEPLATE DETAILS	MA	VISUAL	100%	IS-325 & DATA SHEET	IS-325 & DATA SHEET	INSPC. REPORT	2	1 ^s	1	^s NOTE - 2
		9.EXPLOSION FLAME PROOF NESS (IF SPECIFIED)	MA	EXPLOSION FLAME PROOF TEST	1/TYPE	IS-3682 IS-8239 IS-8240	IS-3682 IS-8239 IS-8240	TC	2	-	1	TC FROM AN INDEPENDENT LABORATORY, REFER NOTE-3
		10. PAINT SHADE, THICKNESS & FINISH	MA	VISUAL & MEASUREMENT BY ELKOMETER	SAMPLE	BHEL SPEC. & DATA SHEET	BHEL SPEC. & DATA SHEET	TC	2	1 ^s	1	SAMPLING PLAN TO BE DECIDED BY INSPECTION AGENCY ^s NOTE - 2

BHEL			PARTICULARS			BIDDER/VENDOR					
			NAME								
			SIGNATURE								
			DATE						BIDDER'S/VENDORS COMPANY SEAL		



QUALITY PLAN

SHEET 9 OF 9

CUSTOMER :	PROJECT TITLE	SPECIFICATION : NUMBER :
BIDDER/ VENDOR :	QUALITY PLAN NUMBER PED-506-00-Q-007, REV-03	SPECIFICATION : TITLE
SYSTEM	ITEM: AC ELECT. MOTORS 55 KW & ABOVE (LV & MV)	SECTION VOLUME III

SL. NO.	COMPONENT/OPERATION	CHARACTERISTIC CHECK	CAT.	TYPE/ METHOD OF CHECK	EXTENT OF CHECK	REFERENCE DOCUMENT	ACCEPTANCE NORM	FORMAT OF RECORD	AGENCY			REMARKS
									P	W	V	
1	2	3	4	5	6	7	8	9	10			11

NOTES:

- 1 DEPENDING UPON THE SIZE AND CRITICALLY, WITNESSING BY BHEL SHALL BE DECIDED.
- 2 ROUTINE TESTS ON 100% MOTORS SHALL BE DONE BY THE VENDOR. HOWEVER, BHEL SHALL WITNESS ROUTINE TESTS ON RANDOM SAMPLES. THE SAMPLING PLAN SHALL BE MUTUALLY AGREED UPON.
- 3 IN CASE TEST CERTIFICATES FOR THESE TESTS ON SIMILAR TYPE, SIZE AND DESIGN OF MOTOR FROM INDEPENDENT LABORATORY ARE AVAILABLE, THESE TEST MAY NOT BE REPEATED.
- 4 WHEREVER CUSTOMER IS INVOLVED IN INSPECTION, AGENCY (1) SHALL MEAN BHEL AND CUSTOMERS BOTH TOGETHER.

Legends for Inspection agency

1. BHEL/CUSTOMER
2. VENDOR (MOTOR MANUFACTURER)
3. SUB-VENDOR (RAW MATERIAL/COMPONENTS SUPPLIER)

- P. PERFORM
W. WITNESS
V. VERIFY

BHEL	PARTICULARS	BIDDER/VENDOR	
	NAME		
	SIGNATURE		
	DATE		BIDDER'S/VENDORS COMPANY SEAL



**TITLE : TECHNICAL SPECIFICATION
FOR
SELF CLEANING STRAINERS (SCS)**

SPEC. NO. PE-TS-405-165-N003

VOLUME : IIB

SECTION : D

REV. NO. 0

DATE :15.07.2014

SHEET 1of 1

**SECTION D3
STANDARD TECHNICAL SPECIFICATION
FOR
C&I SYSTEMS**



DATA SHEET FOR PRESSURE / DIFFERENTIAL PRESSURE GAUGE

SPECIFICATION NO.:

VOLUME

SECTION

REV. NO.

DATE:

SHEET 1 OF 2

Data Sheet No.: **PE-DC-999-145-I026-A**

TECHNICAL REQUIREMENTS FOR PRESSURE / DIFFERENTIAL
PRESSURE GAUGE

TO BE FILLED-UP /CONFIRMED
BY BIDDER

(TO BE FILLED BY PURCHASER)

GENERAL	MANUFACTURER		
	MODEL NUMBER		
TECHNICAL	SENSING ELEMENT	<input type="checkbox"/> BOURDON <input type="checkbox"/> DIAPHRAGM (BOURDON FOR HIGH PRESS AND DIAPHRAGM FOR LOW PRESS APPLICATION)	
	MATERIAL	SENSING ELEMENT – AISI 316 SS MOVEMENT – AISI 304 SS CASING – <input checked="" type="checkbox"/> DIE CAST AL <input type="checkbox"/> SS	
	ENCLOSURE	CLASS: <input checked="" type="checkbox"/> IP-55 <input type="checkbox"/> IP-65 <input type="checkbox"/> EXPL PROOF PAINT: <input checked="" type="checkbox"/> ENAMEL <input type="checkbox"/> EPOXY	
	DIAL	SIZE: 150 MM COLOR: WHITE NUMERALS: BLACK SCALE: LINEAR, 270° ARC GRADUATED IN METRIC UNITS	
	CASE	COLOUR : BLACK	
	SPAN/ ZERO ADJUSTMENT	INT. MICRO SCREW	
	RANGE SELECTION	SHOULD COVER 125% OF OPRATING PARAMETER	
	OVER RANGE PROTECTION	1.5 TIMES OF FSD	
	BLOW OUT DISC	REQUIRED	
	SWITCHING FACILITY (IF APPLICABLE) TYPE NO. / TYPE OF CONTACTS CONTACT RATING SETTING RANGE REPEATABILITY POWER SUPPLY	NOT REQUIRED <input type="checkbox"/> MICRO SWITCH <input type="checkbox"/> OTHER 2 NOS. SPDT 5A 230V AC, 0.25A 220V DC FIELD ADJUSTABLE OVER FULL RANGE ± 1% OF FSR <input type="checkbox"/> 230V AC <input type="checkbox"/> 110V AC	
PERFORMANCE	ACCURACY	± 1% OR BETTER OF FULL SCALE DEFLECTION	
CONNECTION	PROCESS	<input type="checkbox"/> M20 x 1.5 (M) <input checked="" type="checkbox"/> ½" NPT (M) <input type="checkbox"/> ½" NPT (F) <input type="checkbox"/> OTHER	
	LOCATION	BOTTOM	
ACCESSORIES	NAME PLATE / METAL TAG	SS	
	OTHER	SIPHON FOR STEAM, SNUBBER FOR PUMP DISCHARGE, CHEMICAL SEAL DIAPHRAGM FOR CORROSSIVE, OIL SERVICES and SLURRY APPLICATION TO BE PROVIDED	
OTHER REQUIREMENT	INSTRUMENT LIST	INSTRUMENT LIST COMPRISING OF TAG NO., SERVICE, DESIGN/OPERATING PRESSURE & TEMPERATURE TO BE ATTACHED	
QUALITY REQUIREMENT	CHECK LIST FOR PG/DPG	REFER CHECK LIST NO PE-CL-999-145-I 026-0	

NOTE - Wherever capillary is applicable, length of the capillary shall be 5 metres.



**CHECK LIST FOR
PRESSURE / DIFFERENTIAL PRESSURE GAUGE
(Mechanical Auxiliary Packages)**

SPECIFICATION NO.:

VOLUME

SECTION

REV. NO.

DATE:

SHEET 2 OF 2

Data Sheet No.: PE-CL-999-145-1026-0

SL NO	TESTS/CHECKS	QUANTM OF CHECK	REFERENCE DOC. ACCEPTANCE NORMS	AGENCY			REMARKS
				P	W	V	
1.0	CHECK FOR		APPROVED TECHNICAL REQUIREMENT/ DATA SHEET				MFR TO CARRY OUT ROUTINE TEST ON 100%. WHEN MATL CORELATION ARE NOT AVAILABLE MFR'S COMPLIANCE TO BE PROVIDED
	1.1 DIAL SIZE	100%		M	C	C	
	1.2 MODEL NO/TAG NO	100%		M	C	C	
	1.3 RANGE/SCALE	100%		M	C	C	
	1.4 END CONNECTION	100%		M	C	C	
	1.5 SWITCH CONTACT RATING & NOS	100%		M	C	C	
2.0	CALIBRATION						
	2.1 ACCURACY	100%		M	C	B	
	2.2 REPEATABILITY (FOR SWITCH)	100%		M	C	B	
	2.3 SET POINT ADJUSTMENT FOR SWITCH	100%		M	C	C	
3.0	OVER PRESSURE & LEAK TEST	100%		M	C	C	
4.0	OPERATION OF PR. RELIEF DEVICE	ONE PER TYPE		M	C	C	
5.0	REVIEW OF T.C. FOR MATERIAL OF--						
	5.1 SENSOR	FOR LOT		-	-	B	
	5.2 MOVEMENT			-	-	B	
	5.3 PROCESS CONNECTION		-	-	B		
	5.4 HOUSING		-	-	B		
6.0	REVIEW OF T.C. FOR DEGREE OF PROTECTION	TYPE TEST	-	-	B		
7.0	REVIEW OF T.C. FOR CONTACT RATING OF SWITCH	ONE PER TYPE	-	-	B		
8.0	ACCESSORIES AS APPLICABLE	100%	M	C	C		

LEGEND:

M: MANUFACTURER/ SUB CONTRACTOR, C: CONTRACTOR/ NOMINATED INSP AGENCY, B: BHEL. P: PERFORM, W: WITNESS, V: VERIFICATION.

NOTE:

CONTRACTOR TO PROVIDE COMPLIANCE CERTIFICATE FOR TESTS/CHECKS VERIFIED BY CONTRACTOR AND SUBMIT THE SAME ALONGWITH TEST CERTIFICATES TO BE VERIFIED BY BHEL.



DATA SHEET FOR PRESSURE / DIFFERENTIAL PRESSURE TRANSMITTER

SPECIFICATION NO.:

VOLUME

SECTION

REV. NO.

DATE:

SHEET

1

OF

3

TAG No. Qty.....

Data Sheet No.: PES-145-01-DS1- **A**

Data Sheet A & B

DATA SHEET-A FOR PRESSURE / DIFFERENTIAL PRESSURE TRANSMITTER
(TO BE FILLED BY PURCHASER)

DATA SHEET-B
(TO BE FILLED-UP BY BIDDER)

GENERAL	MANUFACTURER		
	MODEL NUMBER		
TECHNICAL	TYPE	TRANSMITTER OF MICROPROCESSOR BASED 2 WIRE TYPE ,HART PROTOCOL COMPATIBLE	
	TRANSMITTER MEASUREMENT	<input type="checkbox"/> PRESSURE <input checked="" type="checkbox"/> DIFF. PRESSURE	
	OUTPUT RANGE	SIGNAL 4-20MA DC (ANALOG) along WITH SUPERIMPOSED DIGITAL SIGNAL (BASED ON HART PROTOCOL)	
	TURN DOWN RATIO	10:1 FOR VACUUM /VERY LOW PRESSURE APPLICATION 30:1 FOR OTHER APPLICATION	
	ACCURACY	± 0.1% OF CALIBRATED SPAN(MINIMUM)	
	STABILITY	± 0.1% OF CALIBRATED SPAN FOR 6 MONTHS FOR RANGE UPTO AND INCLUDING 70 Kg/cm ² ± 0.25% OF CALIBRATED SPAN FOR 6 MONTHS FOR RANGE MORE THAN 70 Kg/cm ²	
	LOAD IMPEDANCE	500 OHM (MIN)	
	RESPONSE TIME (TIME TAKEN FROM CHANGE IN PHYSICAL PARAMETER INPUT CHANGE TO TRANSMITTER , OUTPUT REACHING 63.2 % OF IT'S TOTAL CHANGE INCLUDING THAT TIME)	100 ms OR BETTER	
	HOUSING	IP 55(with corrosion resistance epoxy coating)	
	OVER PRESSURE	150 % OF MAX OPERATING PRESSURE	
	CONNECTION (ELECTRICAL)	PLUG & SOCKET TYPE	
	PROCESS CONNECTION	1/2 inch NPT(F) / 1",150#RF	
	ZERO DRIFT & SPAN DRIFT	+/- 0.015 PER DEG C AT AT MAX SPAN +/- 0.11 PER DEG C AT AT MAX SPAN	
	SPAN & ZERO	CONTINUOUS TEMPER PROOF,REMOTE AS WELL AS ADJUSTABLY MANUAL FROM INSTRUMENT WITH ZERO SUPPRESSION & ELEVATION FACILITY	
	DAIGNOSTICS	SELF INDICATING FEATURE	
POWER SUPPLY	24 V DC ± 10%		



DATA SHEET FOR PRESSURE / DIFFERENTIAL PRESSURE TRANSMITTER

SPECIFICATION NO.:	
VOLUME	
SECTION	
REV. NO.	DATE:
SHEET 2	OF 3

TAG No. Qty.....


Data Sheet No.: PES-145-01-bs1- A

Data Sheet A & B

DATA SHEET-A FOR PRESSURE / DIFFERENTIAL PRESSURE TRANSMITTER (TO BE FILLED BY PURCHASER)	DATA SHEET-B (TO BE FILLED-UP BY BIDDER)
--	---

	ADJUSTMENT/CALIBRATION/MAINTENANCE	HAND HELD CALIBRATOR/HART .
	ACCESSORIES	DIAPHRAGM SEAL,PULSATIONS DAMPENERS,SYPHON ETC AS REQUIRED BY SERVICE & OPERATING CONDITION, 2 VALVE MANIFOLD FOR ABSOLUTE PRESSURE TRANSMITTER (3 -VALVE MANIFOLD FOR GAUGE /VACUUM PRESSURE TRANSMITTER)AND 5 VALVE MANYFOLD FOR DP /LEVEL/FLOW TRANSMITTER

NOTE - Wherever capillary is applicable, length of the capillary shall be 5 metres.

	CHECK LIST FOR PRESSURE / DIFFERENTIAL PRESSURE TRANSMITTER (Mechanical Auxiliary Packages)	SPECIFICATION NO.:	
		VOLUME	
		SECTION	
		REV. NO.	DATE:
		SHEET 3	OF 3
Data Sheet No.. PE-CL-999-145-1026-0			

SL NO	TESTS/CHECKS	QUANTM OF CHECK	REFERENCE DOC. ACCEPTANCE NORMS	AGENCY			REMARKS
				M	C	B	
1.0	CHECKS FOR VISULA, MODEL TAG NO.	SEE NOTE-1 BELOW	APPROVED TECHINCAL REQUIREMENT/ DATA SHEET	P	W	V	MFR TO CARRY OUT ROUTINE TEST ON 100%. WHEN MATERIAL CORELATION ARE NOT AVAILABLE MFR'S COMPLIANCE TO BE PROVIDED
2.0	PROCESS CONNECTION	-do-		P	W	V	
3.0	ACCURACY	-do-		P	W	V	
4.0	REPEATEABILITY	-do-		P	W	V	
5.0	HYSTERISIS	-do-		P	W	V	
6.0	EFFECT OF TEMP VARIATION ON ACCURACY	-do-		P	W	V	
7.0	SPAN /ZERO ADJUSTMENT	ONE/TYPE		P	W	V	
8.0	EFFECT OF SUPPLY VOLTAGE VARIATION	ONE/TYPE		P	W	V	
9.0	HIGH PRESSURE TEST	SEE NOTE-1 BELOW		P	W	V	
10.0	BURN IN TEST	ONE/TYPE		P	W	V	
11.0	DEGREE OF PROTECTION	ONE/TYPE		P	W	V	

LEGEND:

M: MANUFACTURER/ SUB CONTRACTOR, C: CONTRACTOR/ NOMINATED INSP AGENCY, B: BHEL. P: PERFORM, W: WITNESS, V: VERIFICATION.

NOTE:

- QUANTUM OF CHECK SHALL BE AS BELOW
100 % - BY MANUFACTURER
RANDOM FOR EACH TYPE – BY BHEL & CUSTOMER
- MANUFACTURER TO MAINTAIN CALIBRATED INSTRUMENT HAVING BETTER ACCURACY THAN THE ITEM UNDER TEST. INSPECTING ENGINEER SHALL CHECK THE SAME.
- IN CASE OF IMPORTED ITEMS CONTRACTORS SHALL REVIEW TC's AND NOT INSPECT.

CONTRACTOR TO PROVIDE COMPLIANCE CERTIFICATE FOR TESTS/CHECKS VERIFIED BY CONTRACTOR AND SUBMIT THE SAME ALONGWITH TEST CERTIFICATES TO BE VERIFIED BY BHEL.

TECHNICAL REQUIREMENTS

FIELD MOUNTED LOCAL JUNCTION BOXES

- (i) No. of ways 12/24/36/48/64/72/96/128 with 20% spares terminals.
- (ii) Material and Thickness 4mm thick Fiberglass Reinforced Polyester (FRP).
- (iii) Type Screwed at all four corners for door. Door gasket shall be of synthetic rubber.
- (iv) Mounting clamps and accessories Suitable for mounting on walls, columns, structures etc. The brackets, bolts, nuts, screws, glands required for erection shall be of SS, included in Bidders scope of supply.
- (v) Type of terminal blocks Rail mounted cage-clamp type suitable for conductor size upto 2.5 mm². A M6 earthing stud shall be provided.
- (vi) Protection Class IP: 55 minimum for indoor & IP-65 minimum for outdoor applications.
- (vii) Grounding To be provided.
- (viii) Color RAL 7305.

Process Connection & Piping																	
TESTS	Visual ⑩	GA, BOM, Layout of component & construction feature⑩	Dimension ⑩	Paint Shade/thickness ⑩	Flattening,flaring,hydrotest,hardness check as per ASTM standard (A)	Component Ratings ⑩	Wiring ⑩	Make, Model, Type, Rating⑩	IR & HV ⑩	Review of TC for instrument/devices (R)	Accessibility of TBS/Devices ⑩	Illumination,grounding ⑩	Tubing ⑩	Leak/Hydro test(A)	Chemical/physical properties of material (A)	Proof pressure test,Dismantling & reassembly test,Hydraulic impulse and vibration test (R)	Tests as per standards & specification
ITEMS																	
Local Instrument enclosure	Y	Y	Y	Y		Y	Y	Y	Y	Y	Y	Y	Y	Y			
Local instruments racks	Y	Y	Y	Y		Y	Y	Y	Y	Y	Y	Y	Y	Y			
Junction Box	Y	Y	Y	Y*		Y	Y	Y	Y								
Gauge Board	Y	Y	Y	Y		Y	Y	Y	Y	Y		Y	Y	Y			
Impulse pipes and tubes	Y	Y	Y	Y	Y			Y							Y		Y
Socket weld fittings ANSI B-16.11	Y	Y	Y	Y				Y	Y					Y	Y		
Compression fittings	Y	Y	Y	Y				Y	Y					Y	Y		
Instrument valves & Valve manifolds	Y	Y	Y	Y				Y	Y					Y	Y		
Copper tubings ASTM B75	Y	Y	Y	Y				Y	Y								Y

*-applicable for painted junction boxes.
A- Acceptance Test
Note: R-Routine Test
Note: This is an indicative list of tests/checks. The manufacturer is to furnish a detailed quality plan indicating the Practices and Procedure adopted alongwith relevant supporting documents.

Y – Test applicable



**SPECIFICATION
FOR
MOTORISED VALVE ACTUATOR**

SPECIFICATION NO.: PE-SS-999-145-I007

VOLUME II B

SECTION D

REV. NO. 03

DATE: 20.06.14

SHEET 1 OF 3

Data Sheet A & B

DATA SHEET-A
(TO BE FILLED BY PURCHASER)

DATA SHEET-B
(TO BE FILLED-UP BY BIDDER)

GENERAL*	* PROJECT	3 X 660 MW STPP	
	OFFER REFERENCE		
	* TAG NO. SERVICE		
	* DUTY	<input type="checkbox"/> ON / OFF <input type="checkbox"/> INCHING	
	* LINE SIZE (inlet/outlet): MATERIAL		
	* VALVE TYPE	<input type="checkbox"/> GLOBE <input type="checkbox"/> GATE <input type="checkbox"/> REG. GLOBE <input type="checkbox"/> BUTTERFLY	
	* OPENING / CLOSING TIME		
	* WORKING PRESSURE		
	AMBIENT CONDITION	SHALL BE SUITABLE FOR CONTINUOUS OPERATION UNDER AN AMBIENT TEMP. OF 0-55 DEG C AND RELATIVE HUMIDITY OF 0-95%	
	VALVE SEAT TEST PRESS	BIDDER TO SPECIFY	
	REQUIRED VALVE TORQUE	BIDDER TO SPECIFY	
	ACTUATOR RATED TORQUE	BIDDER TO SPECIFY	
CONSTRUCTION AND SIZING	CONSTRUCTION	TOTALLY ENCLOSED, WEATHER PROOF, IP:55	
	MECHANICAL POSITION INDICATOR	TO BE PROVIDED FOR 0-100% TRAVEL	
	BEARINGS	DOUBLE SHIELDED, GREASE LUBRICATED ANTI-FRICTION.	
	GEAR TRAIN FOR LIMIT SWITCH/TORQUE SWITCH OPERATION	METAL (NOT FIBRE GEARS). SELF-LOCKING TO PREVENT DRIFT UNDER TORQUE SWITCH SPRING PRESSURE WHEN MOTOR IS DE-ENERGIZED.	
	SIZING	OPEN/CLOSE AT RATED SPEED AGAINST DESIGNED DIFFERENTIAL PRESSURE AT 90% OF RATED VOLTAGE. FOR ISOLATING SERVICE THREE SUCCESSIVE OPEN-CLOSE OPERATIONS OR 15 MINS. WHICHEVER IS HIGHER. FOR INCHING /REGULATING SERVICE - 150 STARTS/HR MINIMUM.	
HANDWHEEL	* REQUIRED	<input checked="" type="checkbox"/> YES <input type="checkbox"/> NO	
	* ORIENTATION	<input type="checkbox"/> TOP MOUNTED <input type="checkbox"/> SIDE MOUNTED	
	*TO DISENGAGE AUTOMATICALLY DURING MOTOR OPERATION.		
ELECTRIC ACTUATOR	ACTUATOR MAKE/MODEL	BIDDER TO SPECIFY	
	MOTOR MAKE / MODEL / TYPE / RATING (KW)	BIDDER TO SPECIFY	
	@ MOTOR TYPE	SQUIRREL CAGE INDUCTION MOTOR, STARTING CURRENT LIMITED TO SIX TIMES THE RATED CURRENT- INCLUSIVE OF I.S. TOLERANCE	
	ACTUATOR APPLICABLE WIRING DIAGRAM	<input checked="" type="checkbox"/> ENCLOSED (BIDDER TO CONFIRM) A: <input type="checkbox"/> DRG. NO. 3-V-MISC-24227 R00 B: <input type="checkbox"/> DRG. NO. 3-V-MISC-24550 R00 C: <input type="checkbox"/> DRG. NO. 3-V-MISC-24283 R00 D: <input type="checkbox"/> DRG. NO. 4-V-MISC-90271 R11 E: <input type="checkbox"/> For Thyristor based Integral starter, Bidder/Vendor to furnish wiring diagram	
	COLOUR SHADE	<input checked="" type="checkbox"/> BLUE (RAL 5012) ENAMEL <input type="checkbox"/>	
	PAINT TYPE (## Refer Notes)	<input type="checkbox"/> ENAMEL <input type="checkbox"/> EPOXY <input type="checkbox"/>	
	SHAFT RPM	BIDDER TO SPECIFY	
	OLR SET VALUE	BIDDER TO SPECIFY	
	@ STARTING / FULL LOAD CURRENT	BIDDER TO SPECIFY	
	NO. OF REV FOR FULL TRAVEL	BIDDER TO SPECIFY	
	@ PWR SUPP TO MTR / STARTER	415V +/- 10% , 3PH,3 W, AC 50 HZ +/- 5%	
	@ CONTROL VOLTAGE REQUIREMENT	TO BE DERIVED FROM THE POWER SUPPLY TO THE STARTER <input type="checkbox"/> 230 V <input checked="" type="checkbox"/> 110 V AC/24V DC	



**SPECIFICATION
FOR
MOTORISED VALVE ACTUATOR**

SPECIFICATION NO.: PE-SS-999-145-I007

VOLUME II B

SECTION D

REV. NO. 03

DATE: 20.06.14

SHEET 2

OF 3

Data Sheet A & B

DATA SHEET-A
(TO BE FILLED BY PURCHASER)

DATA SHEET-B
(TO BE FILLED-UP BY BIDDER)

	MOTOR BEARING WITH 2 EARTH TERMINALS	DOUBLE SHIELDED, GREASE LUBRICATED ANTI FRICTION	
	@ ENCLOSURE CLASS OF MOTOR	IP 67 FOR OUTDOOR & IP 55 FOR INDOOR(TOTALLY ENCLOSED SELF VENTILATED)	
	@ INSULATION CLASS	CLASS-F TEMP. RISE LIMITED TO CLASS-B	
	@ WINDING TEMP PROTECTION	<input checked="" type="checkbox"/> THERMOSTAT (3 Nos.,1 IN EACH PHASE) <input type="checkbox"/>	
	SINGLE PHASE / WRONG PHASE SEQUENCE PROTECTION	REQUIRED	
INTEGRAL STARTER	INTEGRAL STARTER	<input checked="" type="checkbox"/> REQUIRED <input type="checkbox"/> NOT REQUIRED	
	TYPE OF SWITCHING DEVICE	<input checked="" type="checkbox"/> CONTACTORS <input type="checkbox"/> THYRISTORS	
	TYPE	<input checked="" type="checkbox"/> CONVENTIONAL <input type="checkbox"/> SMART (NON-INTRUSIVE)	
	IF SMART	(NOT APPLICABLE)	
	a) SERIAL LINK INTERFACE	<input type="checkbox"/> INTEGRAL <input type="checkbox"/> FIELD MOUNTED	
	b) SERIAL LINK PROTOCOL	<input type="checkbox"/> FOUNDATION FIELD-BUS <input type="checkbox"/> PROFI-BUS <input type="checkbox"/> DEVICE NET <input type="checkbox"/>	
	c) SERIAL LINK MEDIA	<input type="checkbox"/> TWISTED PAIR Cu-CBL <input type="checkbox"/> CO-AXIAL Cu-CBL <input type="checkbox"/> OFC	
	d) HAND HELD PROGRAMMER	<input type="checkbox"/> REQUIRED <input type="checkbox"/> NOT REQUIRED	
	e) TYPE OF HAND HELD PROGRAMMER	<input type="checkbox"/> BLUETOOTH <input type="checkbox"/> INFRARED <input type="checkbox"/>	
	f) MASTER STATION	<input type="checkbox"/> REQUIRED <input type="checkbox"/> NOT REQUIRED	
	g) MASTER STN INTRFACE WITH DCS	<input type="checkbox"/> MODBUS <input type="checkbox"/> TCP/IP	
	h) DETAILS OF SPECIAL CABLE	<input type="checkbox"/> ENCLOSED <input type="checkbox"/> NOT REQUIRED	
	STEP DOWN CONT. TRANSFORMER	<input checked="" type="checkbox"/> REQUIRED	
	OPEN / CLOSE PB	<input checked="" type="checkbox"/> REQUIRED <input type="checkbox"/> NOT REQUIRED	
	STOP PB	<input checked="" type="checkbox"/> REQUIRED <input type="checkbox"/> NOT REQUIRED	
	INDICATING LAMPS	<input checked="" type="checkbox"/> REQUIRED <input type="checkbox"/> NOT REQUIRED	
	LOCAL REMOTE S/S	<input checked="" type="checkbox"/> REQUIRED <input type="checkbox"/> NOT REQUIRED	
STATUS CONTACTS FOR MONITORING	<input checked="" type="checkbox"/> REQUIRED <input type="checkbox"/> NOT REQUIRED		
INTEGRAL STARTER DISTURBED SIGNAL	REQUIRED (O/L RELAY OPERATED, CONT./POWER SUPPLY FAILED, S/S IN LOCAL, TORQUE SWITCH OPTD. MID WAY)		
INTERPOSING RELAY/OPTO COUPLER (Applicable for integral Starter)	TYPE OF ISOLATING DEVICE	<input checked="" type="checkbox"/> INTERPOSING RELAY <input type="checkbox"/> OPTO COUPLER <input type="checkbox"/> EITHER	
	QUANTITY	<input checked="" type="checkbox"/> 2 NOs. <input type="checkbox"/> 3 NOs.	
	DRIVING VOLTAGE	<input checked="" type="checkbox"/> 20.5 – 24V DC <input type="checkbox"/> _____ V DC	
	DRIVING CURRENT	<input checked="" type="checkbox"/> 125mA MAX <input type="checkbox"/> _____ mA MAX	
	LOAD RESISTANCE	<input checked="" type="checkbox"/> > 192 ohms - <25 k ohms <input type="checkbox"/> > _____ ohms - < _____ ohms	
TORQUE SWITCH (Not Applicable for Smart Actuator) (\$\$ Refer Notes)	MFR & MODEL NO.	BIDDER TO SPECIFY	
	OPEN / CLOSE	<input checked="" type="checkbox"/> 1 No. <input type="checkbox"/> 2Nos. / <input checked="" type="checkbox"/> 1 No. <input type="checkbox"/> 2Nos	
	CONTACT TYPE	2 NO + 2 NC	
	RATING	5A 240V AC AND 0.5A 220V DC	
	CALIBRATED KNOBS(OPEN&CLOSE TS)	REQUIRED FOR SETTING DESIRED TORQUE	
	ACCURACY	+3% OF SET VALUE	
LIMIT SWITCH (Not Applicable for Smart Actuator) (\$\$)	MFR & MODEL NO.	BIDDER TO SPECIFY	
	OPEN : INT : CLOSE	<input type="checkbox"/> 1 No. <input type="checkbox"/> 1 No. <input checked="" type="checkbox"/> 2 Nos. <input checked="" type="checkbox"/> 2Nos.	
	CONTACT TYPE	2 NO + 2 NC	



**SPECIFICATION
FOR
MOTORISED VALVE ACTUATOR**

SPECIFICATION NO.: PE-SS-999-145-I007

VOLUME II B

SECTION D

REV. NO. 03

DATE: 20.06.14

SHEET 3

OF 3

Data Sheet A & B

DATA SHEET-A
(TO BE FILLED BY PURCHASER)

DATA SHEET-B
(TO BE FILLED-UP BY BIDDER)

Refer Notes

RATING (AC / DC)

5A 240V AC AND 0.5A 220V DC

Limit switches shall be silver plated with high conductivity and non-corrosive type. Contact rating shall be sufficient to meet the requirement of control system subject to a minimum of 60 V, 6 VA rating. Protection class shall be IP 55.

POSITION TRANSMITTER	POSITION TRANSMITTER (For inching duty applications)	<input checked="" type="checkbox"/> REQUIRED <input type="checkbox"/> NOT REQUIRED	
	MFR & MODEL NO.	BIDDER TO SPECIFY	
	TYPE	<input checked="" type="checkbox"/> ELECTRONIC (2 WIRE) R/I CONVERTER <input type="checkbox"/> ELECTRONIC (2 WIRE) CONTACTLESS	
	SUPPLY	<input checked="" type="checkbox"/> 24V DC <input type="checkbox"/>	
	OUTPUT	<input checked="" type="checkbox"/> 4-20mA	
	ACCURACY	± 1% FS	
SPACE HEATER	@SPACE HEATER	REQUIRED	
	@ POWER SUPPLY (NON INTEGRAL)	230V AC,1 PH.,50 Hz	
	@ POWER SUPPLY (INTEGRAL)	POWER SUPPLY DERIVED FROM MAIN POWER SUPPLY AVAILABLE AT ACTUATOR END.	
	@ RATING		
TERMINAL BOX	ACTUATOR/MOTOR TERMINAL BOX	REQUIRED	
	ENCL CLASS ACTUATOR/MOTOR T.B.	<input checked="" type="checkbox"/> IP 67 <input type="checkbox"/> @.....	
	@ EARTHING TERMINAL	REQUIRED	
	PLUG & SOCKET(9 PIN) (FOR COMMD, LS/TS FEED BACK, PoT)	<input checked="" type="checkbox"/> REQUIRED <input type="checkbox"/> NOT REQUIRED <input checked="" type="checkbox"/> 2 NOS. <input type="checkbox"/>	
CABLE GLANDS	@ POWER CABLE GLAND	SIZE:-----	
	@ SPACE HEATER CABLE GLAND	SIZE:-----	
	OTHER CONTROL CABLE GLANDS-1	<input type="checkbox"/> 1No. for BFV of CW PUMP(Cable size 2Px1.5mm2)	
	OTHER CONTROL CABLE GLANDS-2	QUANTITY & SIZE :-----	



**SPECIFICATION
FOR
MOTORISED VALVE ACTUATOR**

SPECIFICATION NO.: PE-SS-999-145-I007

VOLUME II B

SECTION D

REV. NO. 03

DATE: 20.06.14

SHEET 4 OF 3

Data Sheet A & B

DATA SHEET-A
(TO BE FILLED BY PURCHASER)

DATA SHEET-B
(TO BE FILLED-UP BY BIDDER)

WEIGHT

TOTAL WEIGHT (ACTUATOR + ACCESSORIES)

BIDDER TO SPECIFY


_____ Kg.

NOTES:

1. **SCOPE:** DESIGN, MANUFACTURE, INSPECTION, TESTING AND DELIVERY TO SITE OF ELECTRIC ACTUATOR FOR INCHING OR OPEN / CLOSE DUTY.
 2. **CODES & STANDARDS:** DESIGN AND MATERIALS USED SHALL COMPLY WITH THE RELEVANT LATEST NATIONAL AND INTERNATIONAL STANDARD. AS A MINIMUM, THE FOLLOWING STANDARDS SHALL BE COMPLIED WITH:
IS-9334, IS-2147, IS-2148, IS-325, IS-2959, IS-4691 AND IS-4722
 3. TEMPERATURE RISE SHALL BE RESTRICTED TO 70 DEG. C FOR AMBIENT TEMPERATURE OF 50 DEG C.
 4. CABLE GLANDS OF DOUBLE COMPRESSION TYPE, BRASS MATERIAL SHALL BE PROVIDED.
 5. THE TORQUE SWITCHES SHALL BE PROVIDED WITH MECHANICAL LATCHING DEVICE TO PREVENT OPERATION WHEN UNSEATING FROM THE END POSITIONS. THE LATCHING DEVICE SHALL UNLATCH AS SOON AS THE VALVE LEAVES THE END POSITION. IF SUCH PROVISION IS NOT POSSIBLE, THE TORQUE SWITCHES SHALL BE BYPASSED BY END-POSITION LIMIT SWITCHES WHICH OPENS ON VALVE LEAVING END POSITION. THESE LIMIT SWITCHES ARE ADDITIONAL TO THE NUMBER OF LIMIT SWITCHES SPECIFIED ELSEWHERE.
 6. THE MOTOR SHALL OPERATE SATISFACTORILY UNDER THE +/- 10% SUPPLY VOLTAGE VARIATION AT RATED FREQUENCY, -5% TO +3% VARIATION IN FREQUENCY AT RATED SUPPLY VOLTAGE, SIMULTANEOUS VARIATION IN VOLTAGE & FREQUENCY THE SUM OF ABSOLUTE PERCENTAGE NOT EXCEEDING 10%.
 7. THE MOTOR SHALL BE SUITABLE FOR DIRECT ON LINE STARTING.
- \$\$ TORQUE SWITCH & LIMIT SWITCH SHALL ACT INDEPENDENT OF EACH OTHER. TANDEM OPERATION IS NOT ACCEPTABLE.**
- ## EPOXY PAINT IS RECOMMENDED FOR COASTAL AREAS.**
8. It shall be possible to operate the actuator locally. Lockable local/remote selection shall be provided on the actuator.
 9. Position indicator shall be provided for 0 to 100 % travel
 10. Wiring shall be suitable voltage grade copper wire.

	PREPARED BY	CHECKED BY	APPROVED BY	VENDOR COMPANY SEAL
NAME	Madhav gupta	Mayank kesharwani	Bharat Singh	NAME
SIGNATURE				SIGNATURE
DATE	22.07.2014	22.07.2014	22.07.2014	DATE



NOTES* = TO BE FILLED BY MPL (LEAD AGENCY). @= TO BE FILLED BY ES

CLAUSE NO.	TECHNICAL REQUIREMENTS			
1.00.00	CONTROL DESK & PANELS			
1.01.00	GENERAL			
1.01.01	All control desk, panels, LVS panel etc. shall be furnished fully wired with necessary provision for convenience outlets, internal lighting, grounding, ventilation, space heating, anti-vibration pads, internal piping & accessories as required for completeness of the system.			
1.01.02	All panels, desks, cabinets shall be free standing type & have bottom / top entry for cables to be finalised application wise during detailed engineering stage. The bottom of desk & cabinets shall be sealed with bottom plate, compression cable glands (double for field and single for inside rooms) and fire proof sealing material to prevent ingress of dust and propagation of fire. Sufficient number of power receptacles with disconnect switches shall be installed within all panels/desk.			
1.01.03	Exterior steel surface shall be sand blasted, ground smooth, filled, primed, sanded and smooth enamel painted to give a good finish subject to minimum paint thickness of 65-75 microns for sheet thickness of 3 mm and 50 microns for sheet thickness of 2mm. The exact color shall be finalised during detailed engineering.			
1.01.04	The design shall conform to the EN ISO 11064 (Ergonomical design of control room), Part-1,2 and 3.			
2.00.00	CONTROL DESK & PANEL			
2.01.00	GENERAL			
2.01.01	The exact dimensions, material, construction details, grounding, general arrangement etc. of Control Desk etc. shall be as per the actual requirement and shall be finalised during detailed engineering and subjected to Employer's Approval.			
NORTH KARANPURA STPP (3X660 MW) EPC PACKAGE	TECHNICAL SPECIFICATIONS SECTION – VI, PART-B BID DOC. NO.: CS-4410-001-2	SUB-SECTION-IIIC-12 CONTROL DESK & PANELS	PAGE 1 OF 4	

CONTROL DESK, LVS PANEL, PLC PANEL, SMOKE DETECTOR, FIRE ALARM & CONTROL SYSTEM

ITEMS	TESTS														
	Visual ®	GA, BOM ,Lay Out of components ®	Dimensions ®	Paint Shade/Thickness/Adhesion ®	Alignment of Section ®	Component Rating/ Make / Type ®	Wiring ®	IR & HV ®	Review of TC for instruments/ Devices/ Recorders, Indicators/ osaic Items/ Transducers ®	Accessibility of TBS/ Devices ®	Illumination ®	Functional Check for Control Element ,	Mimic ®	Test as per IEC 1131 ® *	Test as per Std ® & (A)
1. Control Desk	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y		
2. LVS Panel	Y	Y	Y	Y	Y	Y	Y	Y	Y						Y
3. Annunciation, Control, PLC Panel	Y	Y	Y	Y		Y	Y	Y	Y	Y	Y			Y	Y
4.Smoke Detectors (UL-268,EN-54 PT-7), Heat Detectors(UL-521/EN 54 PT-5) Annunciation/ Control Panel (UL -864, EN-54, PT-2)															Y
<p>Note: 1) Detailed procedure of Environmental Stress Screening test shall be as per Quality Assurance Programme in General Technical Conditions</p> <p>2) This is an indicative list of test/ checks. The manufacturer is to furnish a detailed quality plan indicating the Practice and Procedure alongwith relevant supporting documents.</p> <ul style="list-style-type: none"> *Applicable for PLC Y - Test Applicable , ® - Routine Test (A) - Acceptance Test 															

DRAWING NO. 3-V-MISC-24283



SETTING PROCEDURE OF POSITION LIMIT AND TORQUE SWITCH

VALVES	OPEN		CLOSE	
	MAIN	BACK UP	MAIN	BACK UP
GATE VALVE OF 100 mm AND ABOVE IN 1500 CL AND ABOVE RATINGS	OLS	OTS *	CLS	CTS
ALL OTHER GATE & GLOBE VALVES	OLS	OTS *	CTS	#

- CLS NOT TO BE CONNECTED IN TRIP CIRCUIT
 * - BYPASS OTS FOR INITIAL 5% OF TRAVEL (FOR GATE VALVES ONLY)

- NOTE:-
- ALL TORQUE AND LIMIT SWITCHES (OTS, CTS, OLS1&2, CLS1&2) ARE WITH 2NO+2NC CONTACTS '1NO+1NC' IS TERMINATED IN TBS 1-24, REMAINING CONTACTS ARE FOR INTERNAL USE. ANY SPARE CONTACTS WHICH ARE NOT USED INTERNALLY ARE TO BE TERMINATED IN TBS 25-32
 - CTS - TORQUE SWITCHES FOR CW ROTATION (CLOSE)
 - OTS - TORQUE SWITCHES FOR CCW ROTATION (OPEN)
 - OLS-1, OLS-2 - LIMITSWITCHES FOR POSITION OPEN
 - CLS-1, CLS-2 - LIMITSWITCHES FOR POSITION CLOSE
 - EPT - ELECTRONIC POSITION TRANSMITTER (CONTACTLESS TYPE, FOR INCHING DUTY)
 - R1-R2-POTENTIOMETER 2 x 100 OHMS (FOR ON-OFF DUTY)
 - FOR COMMANDS & EPT EITHER INTERNALLY GENERATED 24 VDC OR EXTERNAL SUPPLY OF 24VDC CAN BE USED
 - M - MOTOR 3φ 415V 50 Hz AC SUPPLY
 - TORQUE SWITCH BYPASS WITH LIMITSWITCH BOTH ON OPEN & CLOSE DIRECTION TO BE DONE INTERNALLY.

REV	DATE	ALTERED
		CHD & APPD

TYPE OF PRODUCT ELECTRICAL VALVE ACTUATORS (AC) WITH INTEGRAL STARTERS
OR NAME OF PROJECT FOR NTPC PROJECTS
CUSTOMER/PROJECT (DRAWN FOR INTERMEDIATE POSITION OF VALVES)

	BHARAT HEAVY ELECTRICALS LTD. UNIT: HIGH PRESSURE BOILER PLANT. TIRUCHIRAPALLI-620014.	DRN N.P.ESWAR	SIGN N.P	DATE 17.03.05	NO. OF VAR.
365-121		CHD D.DINAKARAN	D.D	17.03.05	-
		APPD K.ARUNACHALAM	K.A	17.03.05	-

DEPT VL	SCALE NTS	WEIGHT (KG.)	REFERENCE INFORMATION	NO. OF ITEMS

TITLE WIRING DIAGRAM (TERMINAL PLAN) FOR ACTUATOR WITH INTEGRAL STARTER WITH PLUG & SOCKET FOR NTPC PROJECTS	CARD CODE U 01	DRAWING NO. 3-V-MISC-24283	REV 0
--	----------------------	-------------------------------	----------

CAUTION: The information on this document is the property of BHARAT HEAVY ELECTRICALS LTD. It must not be used directly or indirectly in any way detrimental to the interest of the company.



**TITLE : TECHNICAL SPECIFICATION
FOR
SELF CLEANING STRAINERS (SCS)**

SPEC. NO. PE-TS-405-165-N003

VOLUME : IIB

SECTION : D

REV. NO. 0

DATE :15.07.2014


SHEET 1of 1

LIST OF SUB-VENDORS

PROJECT : NORTH KARANPURA STPP (3 x 600 MW)		LIST OF ITEMS REQUIRING OP		REF. NO :							
PACKAGE : EPC PACKAGE		APPROVAL & ACCEPTABLE		REVISION NO : 00							
CONTRACTOR : BHEL - PEM, HYD, Trichy, PC, EDN		VENDOR AS APPROVED BY		DATE : 20/12/2013							
CONTRACT NO : 4410-001											
No.	Major Equipment	QP Inspec tion Cate gory	QP No. 4410 001-QV1-Q	QP Submi sion SCH	QP Appr oval SCH	Proposed Sub Supplier	Country	SS Approv al Status	SS Detail Sub-SCH	SS Approv al SCH	Remark
		III				M System	JAPAN	A			
		III				ABB	GERMANY/Farida bad	A			
		III				ENDRESS & HOUSER	Aurangabad	A			
		*				Khrono		DR			
		*				Tokyo Keliso	Japan	DR			
		*				INOR	Sweden	DR			
		*				P & F	India	DR			
		*				Siemens		DR			
		*				Yamatate	JAPAN	DR			
		*				Yamart	JAPAN	DR			
		*				Foxboro		DR			
24	Conduits/Pipe(GI)					Refer Electrical List					
25	Electronic transmitters (Pressure, DP)	III				EMERSON (Rosenmount)	USA/ Pawane	A			
		III				FUJI ELECTRIC	China	A			
		III				YOKOGAWA	JAPAN	A			
		I				ABB	FARIDABAD	A			
		III				ABB	GERMANY / Italy	A			
		III				Siemens	France / India	A			
		*				ENDRESS & HOUSER	Aurangabad/ Germany	DR			
26	Thermocouples, RTD & Thermowell	III				HERAUS SENSOR	GERMANY	A			
	Reler Note - 2	III				WISE Control	Korea	A			
		II				Temposans	Udaipur	A			
		II				Pyroelectric	Goa	A			
		II				Delriv Instrumentation & Electronics Ltd	Mumbai	A			
		III				Mico	USA	A			
		III				OKAZAKI corporation	JAPAN	A			
		III				Yamart	JAPAN	A			



PROJECT : NORTH KARANIPURA STPP (3 x 660 MW)		LIST OF ITEMS REQUIRING QP APPROVAL & ACCEPTABLE VENDOR AS APPROVED BY		REF. NO. : REVISION NO. : 00 DATE : 20/12/2013				
PACKAGE : EPC PACKAGE		CONTRACTOR : BHEL - PEM, HYD, Trichy, PC, EDN		VENDOR AS APPROVED BY				
CONTRACT NO. : 4410-001		Proposed Sub Supplier		SS Approval Status				
No.	Major Equipment	QP Inspection Category	QP No. 4410-001-QV-I-Q SCH	QP Approval SCH	Country	SS Detail Sub.SCH	SS Approval SCH	Remark
29	Pressure, DP Gauge	III	Pyroelectric BUJENBERG ASHCROFT		Mumbai UK USA/Germany/India	DR A A		
		III	Wilka WISE Control		GERMANY Korea Japan	A A A		
		III	H.Guru South India		Bangalore	A		Not for MS & FW application
		III	A.N. Instruments		Kolikkatta	A		Not for MS & FW application
		III	Gauge Bourdon(GIC)		Panvel	A		Not for MS & FW application
		III	Goa Thermoelastic		GOA	A		Not for MS & FW application
		III	Wilka		Pune	A		Not for MS & FW application
		III	Baumer		Vapi	A		Not for MS & FW application
		III	Ashcroft (Mass Brand)		Gandhinagar	A		Not for MS & FW application
		III	H.Guru		Rishra/Muzaffarpur	A		Not for MS & FW application
		*	US Gauge		USA	DR		Not for MS & FW application
		*	Winiers		USA	DR		Not for MS & FW application
		*	Forbes Marshall		Hyderabad	DR		Not for MS & FW application
		*	Manometer		Mumbai	DR*		Not for MS & FW application
		*	Walchandnagar Industries Ltd.		Mumbai	DR		Not for MS & FW application
		*	Gauges Bourdon		UK	DR		Not for MS & FW application
30	Level gauge (Transparent & Reflex, Tubular type)	III	Nihon Klingege Co., Ltd.		Japan	NOTED		
		III	Bunkabokai Kogyo Co., Ltd		Japan	NOTED		
		III	Iokyo Keiso		Japan	NOTED		
		III	Samji Industries Inc.		Korea	NOTED		
		III	HITROL		Korea	NOTED		
		III	Leveon		Kolikkatta	NOTED		Up to 40 Kg/cm2
		III	Sigma		Mumbai	NOTED		Up to 40 Kg/cm2
		III	SREM		Pune	NOTED		Up to 40 Kg/cm3
		III	Chemtrol		GOA	NOTED		Up to 40 Kg/cm4
		III	ASIAN INDUSTRIAL VALVES		CHENNAI	NOTED		Up to 40 Kg/cm5
		III	D.K. Instruments		Kolikkatta	NOTED		Up to 40 Kg/cm2
		III	Flow Star		Fardabad	NOTED		Up to 40 Kg/cm2
		III	V-Automat		NewDelhi	NOTED		Up to 40 Kg/cm2
		III	DEMPER KOGYO		JAPAN	NOTED		Up to 40 Kg/cm2



143

NTPC		PROJECT : NORTH KARAMPURA STPP (3 x 660 MW)				LIST OF ITEMS REQUIRING OP APPROVAL & ACCEPTABLE			REF. NO.	REMARK
		PACKAGE : EPC PACKAGE				APPROVAL & ACCEPTABLE			REVISION NO. : 00	
		CONTRACTOR : BHEL - PEMI, HYD, Trichy, PC, EDN				VENDOR AS APPROVED BY			DATE : 20/12/2013	
		CONTRACT NO : 4410-001								
No.	Major Equipment	QP Inspec tion Cate gory	QP No. 4410 001-QV-I-Q Submi sion SCH	QP Appr oval SCH	Proposed Sub Supplier	Country	SS Appro val Status	SS Detail Sub.SCH	SS Approva l SCH	Remark
		II			Thermo electric Bv	Netherlands	A			PVC,FRLS type
		I			Universal Cable	Satna	A			
		I			Thermocables	Hyderabad	A			
		I			Finalex Cable	Pune	DR*			
		I			Incab	Pune	DR*			
		*			Lapp cables	India	DR			
		*			Liont cable	Pune	DR			M/s BHEL will forward only two proposals after details review of NTPC Technical specification requirements.
		*			Gupla Cable	Orisa	DR			
		*			CMI	Fardabad	DR			
47	Electrical actuator	III			Aurua	Germany	A			
		III			Limitorge	USA	A			
		III			Rotorq	UK	A			
		II			Limitorque	Fardabad	A			
		II			Rotorq	Chennai/ Bangalore	A			
		III			Nippon gear	Japan	A			
		II			Aurua	Bangalore	A			
		III			Harold Beck	USA	A			
		III			Drehmo	Germany	A			
		*			Lindco	USA	DR			
		*			Siemens	Germany	DR			
47A	Electrical actuator for ID/FD/PA Blade pitch and Guide vane control	III			Harold Beck	USA	A			
48	Flow nozzle assembly	II			SIPCS Aktorik GmbH	Germany	A			
		II			Microprecision	Fardabad	A			DR for P-91 Material
		II			SEIKO	Austria	A			
		II			TECHNOMATIC	Italy	A			
		II			Instrumentation Limited	Paighat	A			
		II			Starmech	Pune	A			
		*			WISE Control	Korea	A			DR for P-91 Material
		*			SAMIL	Korea	DR			
		*			MINCO	GOA	DR			
		*			Engg. Specialities	Kolkata	DR			
		*			Pyroelectric	Mumbai	DR			
49	HIGH Temp. cable (PTFE/PEP)	II			Habia cables	Sweden	A			

APPROVED BY
DATE : 20/12/2013

APPROVED BY
DATE : 20/12/2013

APPROVED BY
DATE : 20/12/2013

