


**NTPC 1x500 MW FIROZ GANDHI UNCHAHR THERMAL POWER PLANT**


**TECHNICAL SPECIFICATION  
FOR SELF CLEANING STRAINER (SCS).**

**Specification No. : PE-TS- 401-165-N003(REV. 0)**

**VOLUME -IIB**



**BHARAT HEAVY ELECTRICALS LIMITED  
POWER SECTOR  
PROJECT ENGINEERING MANAGEMENT  
PPEI BLDG., SEC-16A, PLOT NO. 25  
NOIDA – 201301 (UP)**

	<b>TITLE : TECHNICAL SPECIFICATION FOR SELF CLEANING STRAINERS (SCS)</b>	<b>SPEC. NO. PE-TS- 401-165-N003</b>	
	<b>PREAMBLE</b>	<b>VOLUME : II B</b>	
		<b>REV. NO. 0</b>	<b>DATE :16.06.14</b>
		<b>SHEET1 OF 2</b>	

1.0 The tender document contains three (3) volumes. The bidder shall meet the requirements of all the three volumes.

**1.1 Volume -I CONDITIONS OF CONTRACT**

This consists of four parts as below :

Volume - I A : This part contains instructions to bidders for making bids to BHEL.

Volume - I B : This part contains general commercial conditions of the tender and include provision that vendor shall be responsible for the quality of item supplied by their sub-vendors.

Volume - I C : This part contains special conditions of contract.

Volume - I D : This part contains commercial conditions for erection and commissioning site work, as applicable.

**1.2 Volume - II TECHNICAL SPECIFICATIONS**

Technical requirements are stipulated in Volume II which comprises of :

Volume - II A : General Technical Conditions

Volume - II B : Technical specification including drawings, if any

**1.2.1 Volume - II B :**

This volume is sub-divided into following sections:

Section - A : This section outlines the scope of enquiry.

Section - B : This section provides "Project Information"

Section - C : This section indicates technical requirements specific to the contract, not covered in Section-D.

Section - D : This section comprises of standard technical specifications of equipments complete with data sheet A, B & C.

Data sheet-A specifies data and other requirements pertaining to the equipment.

Data sheet - B specifies data to be filled by the bidder (Data Sheet B is contained in Volume - III)



TITLE : TECHNICAL SPECIFICATION  
FOR  
SELF CLEANING STRAINERS (SCS)

SPEC. NO. PE-TS- 401-165-N003

VOLUME : II B

REV. NO. 0 | DATE :16.06.14

SHEET 2 OF 2

PREAMBLE

1.2.2 **Volume - III TECHNICAL SCHEDULES**

- 1.0 This volume contains technical schedules and Data Sheets - B, which are to be duly filled by the bidder and the same shall be furnished with the technical bid as per instructions given in Document No.PES-100-901 in Volume-III.
- 2.0 The requirements mentioned in Section C/Data Sheets-A of Section-D shall prevail and govern in case of conflict between the same and the corresponding requirements mentioned in the descriptive portion in Section -D.



**TITLE : TECHNICAL SPECIFICATION  
FOR  
SELF CLEANING STRAINERS (SCS)**

**SPEC. NO. PE-TS-401-165-N003**

**VOLUME : II B**

**SECTION : A**

**REV. NO. 0**

**DATE : 16.06.14**

**SHEET 1 of 1**

## INDEX

<b>SECTION</b>	<b>TITLE</b>
<b>A</b>	<b>SCOPE OF ENQUIRY</b>
<b>B</b>	<b>PROJECT INFORMATION</b>
<b>C</b>	<b>SPECIFIC REQUIREMENTS</b>
C1	SPECIFIC TECHNICAL REQUIREMENTS FOR SELF CLEANING STRAINERS.
C2	SPECIFIC TECHNICAL REQUIREMENTS (ELECTRICAL)
C3	SPECIFIC TECHNICAL REQUIREMENTS (C&I)
<b>D</b>	<b>STANDARD TECH. SPECIFICATIONS</b>
D1	SELF CLEANING STRAINER <ul style="list-style-type: none"><li>◆ STANDARD TECHNICAL SPEC.NO. PE-TS-999-165-N002</li><li>◆ DATA SHEET-A</li><li>◆ QUALITY PLAN</li></ul>
D2	ELECTRICAL SYSTEMS
D3	CONTROL & INSTRUMENTATION SYSTEMS



TITLE : TECHNICAL SPECIFICATION  
FOR  
SELF CLEANING STRAINERS (SCS)

SPEC. NO. PE-TS-401-165-N003

VOLUME : II B

SECTION : A

REV. NO. 0

DATE : 16.06.14

SHEET

1

of

1

SECTION - A  
SCOPE OF ENQUIRY



TITLE : TECHNICAL SPECIFICATION  
FOR  
SELF CLEANING STRAINERS (SCS)

SPEC. NO. PE-TS-401-165-N003

VOLUME : II B

SECTION : A

REV. NO. 0

DATE : 16.06.14

SHEET 1 of 2

#### 1.00.0 SCOPE

This enquiry covers the design, manufacture, assembly, inspection and testing at manufacturer's and/or his sub-contractors works properly packed for delivery of the items as follows:

##### 1.01.0 Self Cleaning Strainers :


Self Cleaning Strainers (SCS) complete with all accessories as per the requirements specified in different sections of this specification for NTPC 1x500 MW FIROZ GANDHI UNCHAHAR THERMAL POWER PLANT.

The bidder's scope also includes installation checks, commissioning, trial runs & PG Testing at site of SCS.

##### 1.01.1 The bids shall be evaluated as per NIT.


#### 2.00.00 GENERAL TECHNICAL INSTRUCTIONS:


- 2.01.00 It is not the intent to specify herein all the details of design and manufacture. However the equipment shall conform in all respects to high standard of design, engineering and workmanship, and shall be capable of performing the required duties in a manner acceptable to Engineer/ Owner, who will interpret the meaning of drawing and specifications, and shall be entitled to reject any component or material, which in his judgement is not in full accordance herewith.
- 2.0.2.00 The omission of specific reference to any component/ accessory necessary for the proper performance of the equipments shall not relieve the bidder of the responsibility of providing such facilities to complete the supply of the equipments at quoted prices.
- 2.03.00 In case of any deviation from this Technical specification (Vol. IIB) and General Technical Conditions (Vol. IIC), the same shall be indicated in the schedule of deviations enclosed in Volume-III, Part-A. In the absence of duly filled schedules it will be assumed that the bid strictly conforms to the specification.
- 2.04.00 BHEL's/ Customer's representatives shall be given full access to the shop in which the equipments are being manufactured or tested and all test records shall be made available to him.
- 2.05.00 The equipments covered under this specification shall not be despatched unless the same have been finally inspected, accepted and shipping release issued by BHEL/ Customer
- 2.06.00 Un-priced copy of price bid shall be furnished alongwith the technical bid.


	<b>TITLE : TECHNICAL SPECIFICATION FOR SELF CLEANING STRAINERS (SCS)</b>	<b>SPEC. NO. PE-TS-401-165-N003</b>	
		<b>VOLUME : II B</b>	
		<b>SECTION : C</b>	
		<b>REV. NO. 0</b>	<b>DATE : 16.06.14</b>
		<b>SHEET 1</b>	<b>of 1</b>

SECTION – B


PROJECT INFORMATION

CLAUSE NO.	PROJECT INFORMATION <b>11748</b>		
1.00.00	<p><b>BACKGROUND</b></p> <p>Feroze Gandhi Unchahar Thermal Power Station, FGUTPS was conceived as a Load Centre coal based Power Station of 1050 MW capacity by UPSEB. The land for the project was acquired and stage-I (2x210MW) was implemented by UPSEB. The 2x210 MW Unchahar station was taken over by NTPC from Uttar Pradesh Rajya Vidyut Utpadan Nigam of Uttar Pradesh in 1992. Thereafter, NTPC implemented Stage- II (2x210 MW) and Stage-III (1X 210 MW).</p> <p>The present expansion proposal is to install one additional unit of 500 MW under Stage-IV thus making the ultimate capacity of the FGUTPP 1550 MW.</p>		
1.01.00	<p><b>LOCATION AND APPROACH</b></p> <p>The plant is located in Raebareli district of Uttar Pradesh, having latitude and longitude of 25°54'50"N and 81°19'50"E respectively. It is bounded by villages Khnapur, Faridpur and Khaliqpur Khurd. Mustafabad town is located at a distance of about 3 Kms from the plant. Unchahar railway station on Allahabad-Raebareli broad gauge (BG) section of Northern Railway (NR) is 2 Kms away. The nearest airport is located at Lucknow a distance of approximately 110 km from the project site.</p> <p>Vicinity Plan of the project is placed at <b>Annexure-I</b></p>		
1.02.00	<p><b>LAND REQUIREMENT</b></p> <p>During the implementation of FGUTPS, Stage-I, II &amp; III total area of about 2203 acres of land was acquired. The plant facilities, ash disposal and township for this expansion Stage-IV (1x500 MW) would be accommodated within the available land with dismantling and relocation of some buildings. No additional land has been envisaged to be acquired for this expansion project.</p>		
1.03.00	<p><b>WATER</b></p> <p>As per agreement between NTPC &amp; Irrigation department, 105 Cusec of water is supplied through S.S Canal to NTPC-Unchahar. The Stage-IV (500MW) consumptive water requirement shall be accommodated within the existing commitment of water to FGUTPP. Sharda sahayak canal and Dalmau Pump House (DPH) on Purwa Branch Canal are available sources of water for the project and therefore, the make up water requirement for the plant is proposed to be drawn from these sources.</p>		
1.04.00	<p><b>COAL AVAILABILITY AND TRANSPORTATION</b></p>		
1.04.01	<p><b>Coal Availability</b></p>		
<p>FGUTPP STAGE-IV (1X500 MW) EPC PACKAGE</p>	<p>TECHNICAL SPECIFICATION SECTION - VI PART-A</p>	<p>SUB-SECTION-II PROJECT INFORMATION</p>	<p>PAGE 1 OF 12</p>




CLAUSE NO.	845	PROJECT INFORMATION	11749	
------------	-----	---------------------	-------	---

1.04.02	<p>The coal requirement shall be about 2.7 Million tonnes per year.</p> <p>The matter has been taken up with Ministry of Coal, Govt. of India for Long Term Coal Linkage for Stage-IV (1x500 MW)..Coal requirement for FGUTPP, Stage-I ,II &amp; III is being met from North Karanpura Coal fields of CCL. For FR purposes, coal from North Karanpura Coal fields of CCL has been considered.</p> <p><b>Coal Transportation</b></p> <p>The envisaged mode of coal transportation from the coal mines to the power plant is by Indian Railways rakes. The rakes shall be unloaded at the track hopper.</p>												
1.04.03	<p><b>Coal Quality Parameters and Fuel Oil Characteristics</b></p> <p>The Coal quality parameters and Fuel Oil Characteristics are enclosed as Annexures-II-1 and II-2 to this subsection.</p>												
1.05.00	<p><b>CAPACITY &amp; POWER EVACUATION</b></p> <table border="0"> <tr> <td>Stage-I</td> <td>: 2x210 MW</td> <td>Under Commercial Operation</td> </tr> <tr> <td>Stage-II</td> <td>: 2x210 MW</td> <td>Under Commercial Operation</td> </tr> <tr> <td>Stage-III</td> <td>: 1x210 MW</td> <td>Under Commercial Operation</td> </tr> <tr> <td>Stage-IV</td> <td>1x 500 MW</td> <td>Present proposal</td> </tr> </table> <p>The existing capacity of plant is 1050 MW Step up/ power evacuation voltage for station is 220 KV. Presently 1000 MW is already being evacuated at 220 KV, addition of another 500 MW at 220 KV may cause overloading of 220 KV systems and lead to increase in fault levels at 220 KV system. Considering this 400 KV has been considered as step-up/power evacuation voltage for Stage-IV. Power Generated from FGUTPP- Stage IV, 500 MW unit would be stepped up to the evacuation voltage level through suitably rated Generator Transformer.</p> <p>The power generated from Stage-IV is envisaged to be absorbed by Northern Region beneficiaries. For finalisation of Associated Transmission System (ATS) of the project, the matter would be taken up with Power Grid Corporation of India Ltd. (PGCIL)/CEA/appropriate authority depending on the various routes/options of power sale envisaged for the project.</p>	Stage-I	: 2x210 MW	Under Commercial Operation	Stage-II	: 2x210 MW	Under Commercial Operation	Stage-III	: 1x210 MW	Under Commercial Operation	Stage-IV	1x 500 MW	Present proposal
Stage-I	: 2x210 MW	Under Commercial Operation											
Stage-II	: 2x210 MW	Under Commercial Operation											
Stage-III	: 1x210 MW	Under Commercial Operation											
Stage-IV	1x 500 MW	Present proposal											
1.06.00	<p><b>METEOROLOGICAL DATA</b></p> <p>Important meteorological data from nearest observatory at Allahabad is placed at Annexure - III.</p>												
1.07.00	<p><b>PLANT WATER SCHEME</b></p>												



*(Handwritten signature)*

	The Plant water scheme is described below.		
1.07.01	<b>Source of Water</b>	The source of water for the project is normally from the Allahabad branch canal of the Sharda Sahayak link canal. During the canal closure period, water will be drawn from the Dalmau canal.	
1.07.02	<b>Water Requirement</b>	Normal Make up water requirement for this project would be about 2000 Cu.M/hr with ash water re-circulation system in operation. However, whenever ash water system needs to be operated in once thru mode, water drawl shall be of the order of 3300 cum/hr.	
1.07.03	<b>Raw Water System</b>	Raw water shall be drawn from the source by a gravity channel upto raw water pump house located inside the plant. It is envisaged to provide three (3) numbers (3 x 50 % Capacity) of raw water pumps for supplying water to Water PT Plant in the raw water pump house. In addition two (2) numbers (2 x 100% capacity) of pumps shall be provided to supply raw water for ash handling plant which shall be operated as and when required. Separate set of pipelines of carbon steel construction shall be provided from respective raw water pumps to Water treatment plant and Ash Water tanks.	
1.07.04		The quality of Raw water and Clarified water is enclosed with this sub-section	
1.08.00	<b>Criteria for Wind Resistant Design of Structures and Equipment</b>	All structures and equipment of the power plant, including plant auxilliary structures and equipment, shall be designed for wind forces as given in Sub-Section- D-01, Part-B, Section-VI, i.e. Technical Specification for Civil and Structural Works.	
1.09.00	<b>Criteria for Earthquake Resistant Design of Structures and Equipment</b>	All power plant structures and equipment, including plant auxiliary structures and equipment shall be designed for seismic forces as given in Sub-Section- D-01, Part-B, Section-VI, i.e. Technical Specification for Civil and Structural Works.	



CLAUSE NO.


11751

## PROJECT INFORMATION


 NTPC

## DESIGN RAW WATER ANALYSIS

S.No	Constituent	As	mg/l
1	Calcium	CaCo3	110
2	Magnesium	CaCo3	95
3	Sodium+ Potassium	CaCo3	130
4	Total cations	CaCo3	335
5	Bicarbonates	CaCo3	250
6	Chloride	CaCo3	50
7	Sulphate	CaCo3	35
8	Total Anions	CaCo3	335
9	Silica	As SiO2	12
10	Iron	Fe	1
11	pH Value	-	7.7-8.3
12	Turbidity (NTU)	NTU	Upto 700
13	Organic Matter(As per KMnO4 method)	Number	7.2


 FGUTPP STAGE-IV  
 (1X500 MW)  
 EPC PACKAGE

 TECHNICAL SPECIFICATION  
 SECTION - VI  
 PART-A

 SUB-SECTION-II  
 PROJECT INFORMATION

 PAGE  
 4 OF 12

CLAUSE NO.


PROJECT INFORMATION

11752



DESIGN CLARIFIED WATER ANALYSIS FOR DM PLANT

S.No	Constituent	As	mg/l
1	Calcium	CaCo3	135.2
2	Magnesium	CaCo3	95
3	Sodium+ Potassium	CaCo3	130
4	Total cations	CaCo3	360.2
5	Bicarbonates	CaCo3	245.7
6	Chloride	CaCo3	57
7	Sulphate	CaCo3	57.5
8	Total Anions	CaCo3	360.2
9	Silica	As SiO2	12
10	Iron	Fe	0.3
11	pH Value	-	7.0-8.2
12	Turbidity (NTU)	NTU	10



CLAUSE NO.



11753

PROJECT INFORMATION



VICINITY PLAN

ANNEXURE-I



FGUTPP STAGE-IV  
(1X500 MW)  
EPC PACKAGE

TECHNICAL SPECIFICATION  
SECTION - VI  
PART-A

SUB-SECTION-II  
PROJECT INFORMATION

PAGE  
6 OF 12

CLAUSE NO.


PROJECT INFORMATION **11754**



ANNEXURE-II-1 (PAGE 1 OF 2)

**TABLE - 1 COAL CHARACTERISTICS.**

Sl. No.	Description	Unit	Range of 95% coal Supplies			Range of Adequacy
			Design Coal	Worst Coal	Best Coal	
1	2	3	4	5	6	7
<b>A. PROXIMATE ANALYSIS (As received basis)</b>						
1.	Total Moisture	%	13.00	15.00	10.00	16 - 9
2.	Ash	%	40.00	45.00	38.00	46 - 37
3.	Volatile matter	%	22.00	19.00	25.00	18 - 26
4.	Fixed carbon	%	25.00	21.00	27.00	20 - 28
<b>B. ULTIMATE ANALYSIS (As received basis)</b>						
1.	Carbon	C%	34.6	30.00	40.39	29-41.39
2.	Hydrogen	H2%	3.1	2.42	3.2	2.32-3.3
3.	Nitrogen	N2%	1.2	0.47	0.63	0.37 - 0.73
4.	Oxygen	O2%	7.31	6.25	7.23	6.15 - 7.33
5.	Sulphur	S%	0.4	0.6	0.36	0.6 - 0.36
6.	Carbonates	CO3%	0.2	0.21	0.1	0.21 - 0.1
7.	Phosphorous	P2%	0.19	0.05	0.09	0.05 - 0.09
8.	Total Moisture	H2O%	13	15	10	15.3 - 9.7
9.	Ash	%	40	45	38	46-37
10.	Total	%	100	100	100	
11.	Gross Calorific Value	KCal/Kg	3400	3000	4000	2800 - 4200
12.	Hard grove index		55	50	60	48 - 62
<b>C. ASH ANALYSIS</b>						
1.	Silica	(SiO2)%	58.58	59.15	58.1	59.15-58.1
2.	Alumina	(Al2O3)%	28.87	28.95	28.2	28.95-28.2
3.	Iron Oxide	(Fe2O3)%	5.5	6.9	4.5	6.9-4.5
4.	Titania	(TiO2)%	1.8	1.1	2.2	1.1 - 2.2




CLAUSE NO.

11755

PROJECT INFORMATION




Sl. No.	Description	Unit	Range of 95% coal Supplies			Range of Adequacy
			Design Coal	Worst Coal	Best Coal	
1	2	3	4	5	6	7
5.	Phosphoric Anhydride	(P2O5)%	0.7	0.5	1.2	0.5-1.2
6.	Lime	(CaO)%	1.5	1	2.35	1.0 - 2.35
7.	Magnesia	(MgO)%	1.3	1.1	1.4	1.1-1.4
8.	Sulphuric Anhydride	(SO3)%	0.5	0.4	0.6	0.4 - 0.6
9.	Alkalies (By diff.)	Na2O + K2O%	1.25	0.9	1.45	0.9 - 1.45
<b>D. ASH FUSION RANGE (Under reducing atmosphere)</b>						
a)	Initial Deformation Temperature	(IDT) °C	1100	1100	1100	1100
b)	Hemispherical temperature	°C	1300	1300	1300	1300
c)	Fusion temperature	°C	1400	1400	1400	1400
<b>E. ASH FUSION RANGE (Under oxidising atmosphere)</b>						
a)	Initial Deformation Temperature	(IDT) °C	1100	1100	1100	1100
b)	Hemispherical temperature	°C	1300	1300	1300	1300
c)	Fusion temperature	°C	1400	1400	1400	1400-1450



FUEL OIL CHARACTERISTICS

Sl. No.	Characteristics	Heavy Furnace Oil Grade HV IS-1593-1982	Low Sulphur Heavy Stock (LSHS) IS-11489-1985	Heavy Petroleum Stock (HPS) IS-11489-1985
1.	Total sulphur content	4.5% Max.	1.0% Max.	4.5% Max.
2.	Gross calorific value (KCal/kg)	of the order of 10,000	of the order of 10,000	of the order of 10,000
3.	Flash Point (Min)	66 deg C	66 deg C	72 deg C
4.	Water content by volume (Max)	1.0%	1.0%	1.0%
5.	Sediment by weight (Max)	0.25%	0.25%	0.25%
6.	Asphaltene content by weight (Max.)	2.5%	2.5%	2.5%
7.	Kinematic viscosity in Centistokes at - (Max)	370 at 50deg C	100 at 100deg C	100 at 100deg C
8.	Ash Content by weight (Max.)	0.1%	0.1%	0.1%
9.	Acidity (inorganic)	Nil	Nil	Nil
10.	Pour Point (Max.)	57 deg C	66 deg C	72 deg C
11.	Sodium content	—	—	100 ppm
12.	Vanadium content	25 ppm	25 ppm	25 ppm
13.	Specific heat below pour point (KCal/Kg °C)		0.65	



CLAUSE NO.

11757

PROJECT INFORMATION




ANNEXURE-II-2 (PAGE 2 OF 2)

LIGHT DIESEL OIL CHARACTERISTICS

AS PER IS 1460-2000

Characteristics	LDO
1. Pour Point (max)	21 °C & 12°C for Summer and Winter respectively
2. Kinematic viscosity in centistokes at 40 deg.C	2.5 to 15.7
3. Sediment percent by mass (max)	0.10
4. Total sulphur percent by mass (max)	1.8
5. Ash percentage by mass (max)	0.02
6. Carbon residue (Rans bottom) percent by pass (max.)	1.50
7. Acidity inorganic	Nil
8. Flash point (Min.) - Pensky Martens	66 deg.C
9. Copper strip corrosion for 3 hours at 100°C	Not worse than No. 2
10. Water content, % by volume (max)	0.25



CLAUSE NO.

# 11758 PROJECT INFORMATION



## CLIMATOLOGICAL TABLE

ANNEXURE-III  
(PAGE 1 OF 2)

**जलवायवी सारणी**  
**CLIMATOLOGICAL TABLE**

1951 से 1980 तक के वर्षों पर आधारित  
BASED ON OBSERVATIONS FROM 1951 TO 1980

संयुक्त प्रजासत्ताक भारत  
INDIA

राज्य उत्तर प्रदेश से उत्तर  
U.P. DISTRICT

वर्ष


वर्षों के अलग-अलग मासों के लिए  
MONTHLY DATA FOR EACH YEAR

वर्षों के लिए औसत मासिक और वार्षिक  
MONTHLY AND ANNUAL AVERAGES FOR YEARS


वर्षों के लिए औसत मासिक और वार्षिक  
MONTHLY AND ANNUAL AVERAGES FOR YEARS

वर्षों के लिए औसत मासिक और वार्षिक  
MONTHLY AND ANNUAL AVERAGES FOR YEARS

STATION PRESSURE	WET BULB GLOB. TEMPERATURE		DAILY MEAN TEMPERATURE		HIGHEST AND LOWEST MONTHLY MEAN TEMPERATURE		EXTREMES		HUMIDITY		CLOUD AMOUNT		MONTHLY AND ANNUAL AVERAGES FOR YEARS		MEAN WIND SPEED AND DIRECTION				
	W.B.G. °C	GLOB. °C	DAILY °C	MEAN °C	HIGHEST °C	LOWEST °C	DATE YEAR	DATE YEAR	RELATIVE HUMIDITY %	WIND SPEED km/h	ALL CLOUDS	LOW CLOUDS	NO. OF RAINY DAYS	TOTAL RAINFALL mm					
I 1000.2	12.5	10.5	23.0	6.7	27.9	4.5	31.3	20	07	26	2.0	0.7	19.2	1.8	126.0	0.0	70.9	2.4	
I 1000.1	20.6	16.0					16.4	1972	53	12.7	2.0	0.5			180.0				
I 1003.0	16.0	12.5	27.2	11.2	32.4	6.1	36.1	07	05	66	11.9	0.9	19.8	1.4	103.8	0.0	51.3	4.1	
I 1000.0	24.0	16.5					18.6	1925	40	12.1	1.0	0.6			182.0				
I 1000.0	23.0	16.0	33.8	16.5	39.9	10.9	45.5	02	02	46	12.5	1.5	9.2	0.9	81.0	0.0	35.6	1.1	
I 1000.9	31.4	18.5					19.75	1905	26	10.8	2.0	0.5			184.4				
I 1000.5	30.2	15.1	38.4	22.5	43.5	17.3	46.1	20	01	92	13.1	1.5	0.7	0.5	43.7	0.0	28.0	0.1	
I 1002.3	37.3	20.5					19.75	1966	10	10.0	1.9	0.5			192.3				
I 1001.0	33.5	22.2	42.3	26.7	49.9	22.5	47.3	20	11	98	12.4	1.4	0.6	0.7	62.3	0.0	54.0	1.9	
I 1001.4	40.1	22.8					19.60	1924	20	13.8	1.5	0.8			187.1				
I 1001.0	32.8	25.3	40.1	20.5	45.2	24.0	40.3	06	19.4	35	25.9	3.0	0.5	4.4	526.5	0.0	178.0	2.3	
I 1001.2	37.9	25.5					19.79	1930	41	23.2	4.2	2.1			191.8				
I 1000.0	35.2	28.4	34.1	23.4	30.3	20.5	45.6	01	22.0	80	32.1	6.4	3.6	300.1	702.1	26.2	229.4	15	
I 1000.7	31.5	27.0					19.01	1975	71	32.0	6.5	3.7			182.5				
I 1000.0	29.2	25.5	32.7	25.7	30.5	23.6	42.7	03	21.1	95	32.4	5.5	3.6	307.0	844.7	53.3	335.3	20	
I 1001.5	30.2	26.9					19.72	1972	77	32.7	6.8	3.8			185.3				
I 1000.0	28.2	25.5	33.2	24.7	30.2	22.3	39.8	11	10.3	90	38.4	4.0	2.0	169.0	791.5	6.5	286.2	0.8	
I 1000.0	35.4	26.1	33.1	20.5	35.8	15.8	40.6	03	11.7	89	23.1	1.9	0.8	40.1	576.8	0.0	160.3	0.4	
I 1000.0	25.8	21.0	29.7	13.8	32.7	9.5	36.9	07	5.6	95	22.0	2.0	1.0	11.7	188.4	0.0	96.0	0.1	
I 1001.4	39.0	15.8	29.7	13.8	32.7	9.5	36.9	07	5.6	95	22.0	2.0	1.0	11.7	188.4	0.0	96.0	0.1	
I 1001.4	25.2	18.4	24.0	9.3	28.4	5.3	31.1	02	0.7	75	12.1	1.8	0.3	3.4	60.3	0.0	64.8	1.1	
I 1000.5	20.7	15.6					19.65	1961	50	13.8	1.7	0.3			105.3				
ANNEXURE III	997.6	24.5	19.4	32.0	19.5	48.1	48.0	-0.7		64	18.0	2.0	1.3	1017.7	40.9	1835.5	410.5	335.3	6.1
ANNEXURE III	994.0	20.0	21.5							46	18.2	3.1	1.4		189.4	189.8			24
ANNEXURE III	30	30	30	30	30	30	100	100	30	30	30	21	2.9	29	98	98			
ANNEXURE III	30	30	30	30	30	30	100	100	30	30	30	21	2.9	29	98	98			





	<b>TITLE : TECHNICAL SPECIFICATION FOR SELF CLEANING STRAINERS (SCS)</b>	<b>SPEC. NO. PE-TS-401-165-N003</b>	
		<b>VOLUME : II B</b>	
		<b>SECTION : C</b>	
		<b>REV. NO. 0</b>	<b>DATE : 16.06.14</b>
		<b>SHEET 1</b>	<b>of 1</b>

## SECTION – C

### SPECIFIC REQUIREMENTS

- SECTION C1 : SELF CLEANING STRAINERS
- SECTION C2 : ELECTRICAL SYSTEMS
- SECTION C3 : C&I SYSTEMS



TITLE : TECHNICAL SPECIFICATION  
FOR  
SELF CLEANING STRAINERS (SCS)

SPEC. NO. PE-TS-401-165-N003

VOLUME : IIB

SECTION : D

REV. NO. 0

DATE : 16.06.14

SHEET 1 of 1

**SECTION C1**  
**SELF CLEANING STRAINERS**  
**(MECHANICAL DETAILS)**



TITLE : TECHNICAL SPECIFICATION  
FOR

SELF CLEANING STRAINERS(SCS).

SPEC. NO: PE-TS-401-165-N003

VOLUME : II B

SECTION:C1

REV. NO. 0

DATE : 16.06.14

SHEET 1 OF 8

## 1.0 GENERAL

The Self Cleaning Strainers(SCS) complete with all accessories shall conform to the standard technical specifications (Section-D) and Data Sheet-A enclosed herewith. In addition the requirements of this section C shall also be complied with. However, wherever the details given in Section-D and Data Sheet-A are different, the requirements of Data Sheet-A shall prevail. Similarly in the event of contradictions between Section-C & Section-D/ Data Sheet-A, Section-C shall prevail.

Section C consists of 3 parts viz. Sec. C1, C2 and C3 for Mechanical, Electrical and C&I respectively, the requirements of all 3 sections shall be complied with.

## 2.0 DESCRIPTION OF EQUIPMENTS :

### 2.1 Self Cleaning Strainers (SCS) :

Self Cleaning Strainers per unit where specified shall be installed on the discharge side of ACW booster pumps. The water through the self cleaning strainers outlet shall be supplied to the Secondary side of Plate Heat Exchangers. The water analysis is indicated in project information in section B.

## 3.0 SCOPE OF SUPPLY UNDER THE SPECIFICATION IN THE BIDDER'S SCOPE FOR SELF CLEANING STRAINERS.

3.1 The scope of supply for Self Cleaning Strainers covered under this specification is as under.

The size, MOC's and other particulars of the equipments are detailed in Data Sheet A annexed with Section – D of the specification.

SL.NO.	PROJECT	SELF CLEANING STRAINERS
1.	NTPC 1x500 MW FIROZ GANDHI UNCHAHAR THERMAL POWER PLANT	2 SETS



TITLE : TECHNICAL SPECIFICATION  
FOR

SELF CLEANING STRAINERS(SCS).

SPEC. NO: PE-TS-401-165-N003

VOLUME : II B

SECTION:C1

REV. NO. 0

DATE : 16.06.14

SHEET 2 OF 8

### 3.2 SCOPE OF SUPPLY OF SCS INCLUDED IN THE BIDDER'S SCOPE :

The Qty of SCS covered under the specification shall be as per Data Sheet A of respective projects.

Each self cleaning strainer shall be complete with following accessories and auxiliaries.

- a) Flushing pump with drive Motor (as per manufacturer's design) - 1 No.
- b) Supply of complete debris disposal pipe work shall be in scope of Bidder. However bidder is to consider minimum 40 mtr. of debris disposal pipework and 5 numbers bends for each SCS in their scope of supply. In case actual piping comes out to be less than 40 mtrs. and number of bends less than 5 nos. still bidder has to supply 40 mtrs pipework and 5 nos. bends as minimum requirement. Bidder shall finalize the pipework to suit the layout at contract stage in such a way that no site welding is required for his pipework otherwise the same shall be carried out by bidder at site.
- c) Filter body/ housing Vent and Drain connections along with their isolating valves.
- d) SCS shall be supplied along with flanges as well as the Counter flanges, complete with bolts, nuts and gaskets.
- e) Differential pressure measuring system for SCS. DP measuring system shall comprise of 2 Nos. DPT + 1 No. DPG for SCS and shall be with *Remote seal* arrangement . Stubs for DPT and DPG shall be independent.
- f) Supporting arrangement complete with foundation plates, anchor bolts, nuts, sleeves, inserts, all installation materials, fixing bolts, clamps, saddle supports (if applicable) and other accessories etc for complete equipment supplied under this package.
- g) Set of commissioning spares, on "As required basis".
- h) The Electrical & C&I items/ accessories as specified in succeeding clause / respective sections herein.
- i) Scope of Starter Panel (Switch Gear Panel) shall be as follows:  
  
2 Sets of SCS shall have one Common Starter Panel (Switch Gear Panel) for DCS based control system.

Switch Gear Panel should have suitable arrangement like Bus Coupler for



TITLE : TECHNICAL SPECIFICATION  
FOR

SELF CLEANING STRAINERS(SCS).

SPEC. NO: PE-TS-401-165-N003

VOLUME : II B

SECTION:C1

REV. NO. 0

DATE : 16.06.14

SHEET 3 OF 8

providing redundancy to incoming supply feeder (1 Working + 1 Standby feeder).

- j) Power and Control cables between Starter Panel(Switch Gear Panel) and various drives in bidder's scope of supply.
- k) Control cables between field instruments and junction box / Starter Panel(Switch Gear Panel) .
- l) Set of mandatory spares as indicated in Data Sheet A.
- m) All the field instruments stipulated in this specification shall be in Bidder's scope.
- n) Finish paints for touch up painting of equipment after erection at site, in sealed containers.
- o) Set of special tools and tackles if required for maintenance and erection of the equipment supplied.
- p) Various drawings, data test reports/ certificates instruction manuals for erection operation and maintenance etc. as specified in Data Sheet-C. and cables schedule indicating BOQ for power & control cables.
- q) Local Control Panels & Instruments: Scope and Type as specified in C&I section wherever required.

Any item not specified but required to make SCS a complete package shall also be in bidders scope.

#### 4.0 SCOPE OF SERVICES INCLUDED IN THE BIDDER'S SCOPE :

The bidder's scope also includes following services at site, for scope under this specification for SCS for respective projects

- a) Installation checks (Erection in BHEL's scope).
- b) Commissioning of equipment.
- c) Trial run for requisite period
- d) Performance Testing

The trial run of equipment shall be generally conducted immediately after commissioning while PG testing shall be conducted at a later date. These activities for different units shall be timed separately.

The no. of visits may be suitably assessed by bidders as per their experience with site stay periods on as required basis.



TITLE : TECHNICAL SPECIFICATION  
FOR

SELF CLEANING STRAINERS(SCS).

SPEC. NO: PE-TS-401-165-N003

VOLUME : II B

SECTION:C1

REV. NO. 0

DATE : 16.06.14

SHEET 4 OF 8

In the event of order no. of visits as follows shall be made as a minimum with charges included in the bidder's base price itself.

- **For drawings/documents approval**

In the event of order all drawings / documents in soft as well as hard copy shall be submitted as per NIT.

Further on receipt of Customer comments, if required bidder's engineer shall visit BHEL/ Customer alongwith soft copy to resolve all issues and incorporate comments in the soft copy for across the table finalisation and Category-I approval.

- **Site Visits :**

- i. No. of site visits for combined activities of erection checks and commissioning for SCS as applicable shall be one per unit - for both sets of equipments of one unit. Time duration for erection and commissioning shall be "on as required basis" with equipments run for trial operation thereafter for requisite period to demonstrate satisfactory operation.

However the no. of visits may be suitably assessed by bidders as per their experience with site stay periods on as required basis.

- ii. Bidder shall demonstrate guarantees including pressure drops at site during subsequent visit for SCS of each unit.
- iii. For trouble shooting on "as required basis".

## 5.0 EXCLUSIONS :

The following are excluded from the bidder's scope .

- 5.1 Civil foundation works required for installation
- 5.2 Erection of Equipment at site.

## 6.0 DESIGN CONSTRUCTION :

In addition to the requirements of Section-D the following shall also be complied under scope of this specification:

- 6.1 The materials of construction specified in Data Sheet-A are minimum requirements and materials of construction for other components not specified shall be similarly selected by the bidder for the intended duty which shall be subject to purchaser's approval during



TITLE : TECHNICAL SPECIFICATION  
FOR

SELF CLEANING STRAINERS(SCS).

SPEC. NO: PE-TS-401-165-N003

VOLUME : II B

SECTION:C1

REV. NO. 0

DATE : 16.06.14

SHEET 5 OF 8

detailed engineering in the event of order.

- 6.2 Housing/ body of SCS Filter shall be designed and manufactured as per the applicable codes for pressure vessels and to take care of force and moments as enclosed in the specification. However in no case thickness of housing/ body shall be less than the thickness as specified in "Pipe size Table" enclosed in Data Sheet-A of SCS.
- 6.3 Adequate provision for future installation of Cathodic Protection for SCS (Sacrificial type shall be in Purchaser Scope) shall be kept by the bidder in the equipment.
- 6.4 Velocity in the pipe work shall be less than 1.5 m/ sec for pump suction and less than 2.2 m/ sec. in other pipe work. All valves upto 150 NB shall be ball valves. For higher sizes, gate/ globe/ B.F. valves shall be provided. All instrument valves shall be needle valves.

## 7.0 Self Cleaning Strainers :

- 7.1.1 Performance Guarantee Parameters shall be as under :
- Pressure drop in Self Cleaning Strainers in clean condition viz. after backwashing.
- 7.1.2 Bidder to note that bids shall be evaluated on account of pressure drop across Self Cleaning Strainers (in clean condition) & liquidated damages on account of not meeting the same shall be in accordance with following :

### A) Bid Evaluation Criteria and Liquidated Damages:

The bids received shall be evaluated for Pressure drop across Self Cleaning strainers :

- The permissible limit of pressure drop across self cleaning strainers in clean condition shall be 0.6 MWC.
- If the pressure drops quoted are higher than above limit, the bids shall be technically loaded @ Rate as mentioned in Data Sheet-A on pro-rata basis per **0.1 MWC** pressure drop (viz. per unit).
- However no advantage shall be given for pressure drops quoted less than above permissible limit.
- The maximum acceptable limit for pressure drop across self cleaning strainer (with technical loadings) shall be 1.0 MWC. The bids will be technically rejected for pressure drops quoted higher than above maximum limit.
- The guaranteed pressure drops shall be demonstrated at site by vendors and if found higher shall be subject to LD @ twice the bid evaluation factor as above.



TITLE : TECHNICAL SPECIFICATION  
FOR

SELF CLEANING STRAINERS(SCS).

SPEC. NO: PE-TS-401-165-N003

VOLUME : II B

SECTION:C1

REV. NO. 0

DATE : 16.06.14

SHEET 6 OF 8

## 8.0 SPARES :

### 8.1 Recommended Spares :

Bidder to submit the list of recommended spares (along with prices) as per NIT required for three (3) years of reliable operation and maintenance of SCS for BHEL reference purpose only.

The recommended spares shall not be considered for evaluation and ordering purpose.

### 8.2 Mandatory Spares

Mandatory Spares shall be as per Data Sheet-A or annexure enclosed with data sheet A.

## 9.0 Quality Plan

Bidder shall submit QP in the event of order based on the guidelines given in the specification & QP enclosed therein. QP will be subject to BHEL/ Customer approval and customer hold points for inspection/ testing shall be marked in the QP at the contract stage. Inspection/ testing shall be witnessed as per same apart from review of various test certificates/ Inspection records etc. Charges for 3<sup>rd</sup> party inspection (TUV/ equivalent) for imported components wherever required shall be included by bidder in the base price itself. Witness for all the test identified under agency "C" & "N" in Quality plan shall be by third party.

If BHEL or BHEL customer decides to witness the tests along with third party, the cost of travel of BHEL or BHEL customer shall be borne by BHEL or BHEL customer themselves.

## 10.0 DELIVERY & DRAWINGS/ DOCUMENTS DISTRIBUTION SCHEDULE :

a. Delivery of Equipment for each project shall be as per NIT.

b. Drawings submission schedule shall be as per NIT/as advised by Project Group.

11.0 The makes of various bought out items shall be subjected to purchaser's approval in the event of order.

12.0 It is mandatory for the bidders to submit along with the bid the deviations if any whether major or minor in the schedule of deviations only. ***In the absence of deviations listed in the schedule of deviations the offer shall be deemed to be in full conformity with the specification "non-withstanding" any thing else stated elsewhere in bidder's offer, data sheets etc. The implied/ indirect deviations in data sheets etc. Shall not be binding on the purchaser.***



TITLE : TECHNICAL SPECIFICATION  
FOR

SELF CLEANING STRAINERS(SCS).

SPEC. NO: PE-TS-401-165-N003

VOLUME : II B

SECTION:C1

REV. NO. 0

DATE : 16.06.14

SHEET 7 OF 8

**13.0** The following documents shall be furnished by the bidder with his offer :

- Compliance certificate duly signed and stamped (Enclosed at Schedules).
- Guarantee schedule duly signed and stamped (Enclosed at Schedules).
- GA drawings of following with empty/ filled-ups.
  - GA of SCS (As applicable).
  - Debris Flushing pumps (if applicable)
  - Other equipments considered necessary for Layout/ Civil.
- Electrical Load Data (Enclosed at Vol. III of Specification)
- Schedule of Deviation (Enclosed at Schedules).

The bidder to note that load requirement furnished and finalised during tender stage shall only be provided by BHEL and any changes or additional requirement of Electrical load by bidder during contract stage shall be provided by BHEL with cost repercussions to the bidder.

NOTE: Apart from above, no other drawing/ document/ data sheet etc. shall be submitted along with the offer. If any drawing/ document etc. is submitted with the offer, same shall be considered as for 'Reference' purpose only and shall not be reviewed/ commented upon and any deviation, exclusion to scope, etc. taken in documents but not highlighted in the deviation schedule shall not be taken cognizance of.



TITLE : TECHNICAL SPECIFICATION  
FOR

SELF CLEANING STRAINERS(SCS).

SPEC. NO: PE-TS-401-165-N003

VOLUME : II B

SECTION:C1

REV. NO. 0

DATE : 16.06.14

SHEET 8 OF 8

**ANNEXURE-I**

**SELF CLEANING STRAINERS**

SL.NO.	Projects	Size (NB)	Length of SCS (Including Counter Flange)	Scope of Counter Flange	Scope of nuts and bolts.
1.	NTPC 1x500 MW FIROZ GANDHI UNCHAHAR THERMAL POWER PLANT	700 NB	2800 mm	In Bidder's Scope	In Bidder's Scope



TITLE : TECHNICAL SPECIFICATION  
FOR  
SELF CLEANING STRAINERS (SCS)

SPEC. NO. PE-TS-401-165-N003

VOLUME : IIB

SECTION : D

REV. NO. 0

DATE : 16.06.14

SHEET 1 of 1

**SECTION C2**  
**SELF CLEANING STRAINERS**  
**ELECTRICAL DETAILS**

**ELECTRICAL EQUIPMENT SPECIFICATION**

**1 x 500 MW UNCHAHAR STAGE-IV**

SPECIFICATION NO.

VOLUME NO. : **II-B**

SECTION : **C**

REV NO. : **00** DATE : 07.01.14

SHEET : 2 OF 3

**1.0 EQUIPMENT & SERVICES TO BE PROVIDED BY BIDDER:**

- a) Services and equipment as per “Electrical Scope between NBPPL and Vendor”.
- b) Any item/work either supply of equipment or erection material which have not been specifically mentioned but are necessary to complete the work for trouble free and efficient operation of the plant shall be deemed to be included within the scope of this specification. The same shall be provided by the bidder without any extra charge.
- c) Supply of mandatory spares as specified in the specifications of mechanical equipments.
- d) Erection and Commissioning spares.
- e) Erection & Maintenance tools & tackles.
- f) Electrical load requirement for COLTCS & SCS system.
- g) All equipment shall be suitable for the power supply fault levels and other climatic conditions mentioned in the enclosed project information.
- h) Bidder to furnish list of makes for each equipment at contract stage, which shall be subject to customer /NBPPL approval without any commercial and delivery implications to NBPPL
- i) Various drawings, data sheets as per required format, Quality plans, calculations, test reports, test certificates, operation and maintenance manuals etc shall be furnished as specified at contract stage. All documents shall be subject to customer/NBPPL approval without any commercial implication to NBPPL.
- j) Motor shall meet minimum requirement of motor specification.
- k) LT power & control cables shall meet minimum requirement of LT power & control cables specification.
- l) Cabling, earthing & lightning protection shall meet minimum requirement of cabling, earthing & lightning protection specification.

**2.0 EQUIPMENT & SERVICES TO BE PROVIDED BY PURCHASER FOR ELECTRICAL & TERMINAL POINTS:**

Refer “Electrical Scope between NBPPL and Vendor”.

**3.0 DOCUMENTS TO BE SUBMITTED ALONG WITH BID**

3.1 Bidder shall confirm total compliance to the electrical specification without any deviation from the technical/quality assurance requirements stipulated. In line with this two signed and stamped copies of the following shall be furnished by the bidder as technical offer:

- a) A copy of this sheet ”Electrical equipment Specification for COLTCS & SCS” and sheet “Electrical Scope between NBPPL and Vendor” with bidder’s signature and company stamp.
- b) List of Erection and Commissioning spares.
- c) List of Erection & Maintenance tools & tackles.
- d) Electrical load requirement

3.2 No technical submittal such as copies of data sheets, drawings, write-up, quality plans, type test certificates, technical literature, etc, is required during tender stage. Any such submission even if made, shall not be considered as part of offer.

**ELECTRICAL EQUIPMENT SPECIFICATION**

**1 x 500 MW UNCHAHAR STAGE-IV**

SPECIFICATION NO.

VOLUME NO. : **II-B**

SECTION : **C**

REV NO. : **00** DATE : 07.01.14

SHEET : 3 OF 3

- 4.0 List of enclosures :
- a) Electrical scope between NTPC & vendor.
  - b) Technical specification, datasheets & quality plans for 415V Electric motors.
  - c) Technical Specification, datasheets & quality plans for LT power & control cables.
  - d) Technical Specification, datasheets & quality plans for cabling, earthing & lightning protection.
  - e) Electrical Load data format.

## ANNEXURE – I TO SECTION – C : STANDARD ELECTRICAL SCOPE BETWEEN BHEL AND VENDOR

PACKAGE: SCS

PROJECT:

S.NO	DETAILS	SCOPE SUPPLY	SCOPE E&C	REMARKS
1	415V MCC	NBPPL	NBPPL	1. 415 V AC/240 V AC supply shall be provided by NBPPL based on load data provided by vendor at contract stage for all equipment supplied by vendor as part of contract including power supply equipment (battery charger etc) required for the PLC/control panel (as applicable) for the system supplied by vendor. 2. Interposing relays (RE 302 of Jyoti make or equivalent), if required for PLC and microprocessor based systems, shall be provided by NBPPL in MCCs. Requirement of these relays shall be furnished by vendor during detailed engineering stage.
2	Local Push Button Station (for motors)	NBPPL	NBPPL	Located near the motor.
3	Power cables, control cables and screened control cables for a) both end equipment in NBPPL's scope b) both end equipment in vendor's scope c) one end equipment in vendor's scope	NBPPL NBPPL NBPPL	NBPPL Vendor NBPPL	1. Sizes and quantity of cables required shall be informed by vendor at contract stage (based on inputs provided by NBPPL). Finalisation of cable sizes shall be done by NBPPL. Vendor shall provide lugs & glands accordingly. 2. Laying of cables by NBPPL except for cabling in vendor scope. 3. Termination at NBPPL equipment terminals by NBPPL L. 4. Termination at Vendor equipment terminals by Vendor.
4	Any special type of cable like compensating, co-axial, prefab, MICC, fibre optical etc.	Vendor	Vendor	
5	Cable trays, accessories & cable trays supporting system	NBPPL	NBPPL	
6	Cable glands and lugs for equipments supplied by Vendor	Vendor	Vendor	1. Double compression Ni-Cr plated brass cable glands 2. Solder less crimping type heavy duty tinned copper lugs for power cables 3. Solder less crimping type heavy duty copper lugs for control cables.
7	Conduit and conduit accessories for cabling between equipments supplied by vendor	Vendor	Vendor	Conduits shall be medium duty, hot dip galvanised cold rolled mild steel rigid conduit as per IS: 9537. Makes of conduits shall be subject to customer/ NBPPL approval at contract stage.
8	Lighting	NBPPL	NBPPL	
9	Equipment grounding & lightning protection	NBPPL	NBPPL	
10	Below grade grounding	NBPPL	NBPPL	

## ANNEXURE – I TO SECTION – C : STANDARD ELECTRICAL SCOPE BETWEEN BHEL AND VENDOR

PACKAGE: SCS

S.NO	DETAILS	SCOPE SUPPLY	SCOPE E&C	REMARKS
11	LT Motors with base plate and foundation hardware	Vendor	Vendor	Makes shall be subject to customer/ NBPPL approval at contract stage.
12	Mandatory spares	Vendor	-	Vendor to quote as per specification.
13	Recommended O & M spares, E & C spares, erection & maintenance tools & tackle.	Vendor	-	As per specification
14	Any other equipment/material/service required for completeness of system but not specified above (to ensure trouble free and efficient operation of the system).	Vendor	Vendor	
15	a) Input cable schedules (C & I) b) Cable interconnection details for above c) Cable block diagram	Vendor Vendor Vendor	- - -	Cable listing for C & I systems for vendor supplied equipment shall be furnished during detail engineering by vendor in soft copies in the NBPPL cable schedule format.
16	Equipment layout drawings	Vendor	-	For ensuring cabling requirements are met, vendor shall furnish layout drawings (both in print form as well as in AUTOCAD) of the complete plant (including electrical area) indicating location and identification of all equipments requiring cabling, and shall incorporate cable trays routing details marked on the drawing as per PEM interface comments. Electrical equipment layout drawing shall be to NBPPL approval.
17	Electrical Equipment GA drawing	Vendor	-	For necessary interface review.

NOTES:

1. Make of all electrical equipments/items supplied shall be reputed make & shall be subject to approval of NBPPL/customer after award of contract.
2. All QPs shall be subject to approval of BHL/customer after award of contract without any commercial implication.
3. For skid mounted system, 2 nos. (1W+1S) supply of 415 V, 3 phase AC shall be provided by NBPPL. Complete electrical distribution for the skid including changeover between feeder/starters/LCP/inter-locks/protection devices / any other supply etc. shall be in bidder's scope.

TITLE  <b>LV MOTORS</b>  <b><u>DATA SHEET-A</u></b>	SPECIFICATION NO.	
	VOLUME	II B
	SECTION	D
	REV NO. 00	DATE 01/10/2012
	SHEET 1	OF 1

- 1.0 Design ambient temperature : 50 °C
- 2.0 Maximum acceptable kW rating of LV motor : ≤200KW
- 3.0 Installation (Indoors/ Outdoors) : As required
- 4.0 Degree Of Protection (Indoor/Outdoor) : IP54/IP55
- 5.0 Type of Cooling : TEFC/CACA/TETV
- 6.0 Details of supply system
- a) Rated voltage (with variation) : 415V ± 10%
  - b) Rated frequency (with variation) : 50 Hz (Variation: +3% TO -5%)
  - c) Combined voltage & freq. variation : 10%
  - d) System fault level at rated voltage : 45 kA for 1 sec
  - e) Short time rating for terminal boxes
    - o 110kW& Above : 45 kA for 1 sec  
(Breaker controlled)
    - o Below 110kW(SFU+ : 45 KA for 0.20 sec.  
Contactor controlled)
  - f) LV System grounding : Solidly
- 7.0 Class of insulation : Class 'F', with temp rise limited to class B.  
(Refer clause 5.00.00 of Motors)
- 8.0 Minimum voltage for starting : 85% of rated voltage  
(As percentage of rated voltage)
- 9.0 Power cables data : Shall be given during Detailedengg.
- 10.0 Earth Conductor Size & Material : Shall be given during Detailedengg.
- 11.0 Space heater supply : 240 V, 1Φ , 50 Hz
- 12.0 Rating up to which Single phase motor : Acceptable below 0.20 kW
- 13.0 Tests : As per Customer motor spec. (enclosed)
- 14.0 Energy efficient/ Flame proof motor : As per Customer spec. requirement

- **Also detail Customer spec. for Motors to be referred as enclosed with spec.**



TITLE : TECHNICAL SPECIFICATION  
FOR  
SELF CLEANING STRAINERS (SCS)

SPEC. NO. PE-TS-401-165-N003

VOLUME : IIB

SECTION : D

REV. NO. 0

DATE : 16.06.14

SHEET 1 of 1

**SECTION C3**  
**SELF CLEANING STRAINERS**  
**C&I DETAILS**



## **1 X 500 MW FGUTPP**

### **SCS**

#### **BIDDER'S SCOPE FOR C&I**

##### **1. GENERAL**

The Contractor shall provide complete Instrumentation for control, monitoring and operation of entire Self Cleaning Strainer system. The requirements given below are to be read in conjunction with detailed Technical specification enclosed in the specification. Further in case of any discrepancy in the requirement within the same section noted by the bidder in the specification, the same will be brought to the notice of BHEL in the form of pre- bid clarification. In absence of any pre-bid clarification, the more stringent requirement as per interpretation of customer shall prevail without any commercial implication.

Further Bidder shall also include in his proposal and shall furnish all equipment, devices and services which may not be specifically stated in the specification but are needed for completeness of the equipment/systems furnished by the Bidder and for meeting the intent and requirements of the specification.

In addition to requirements specified under this Section-C, all C&I systems/ sub-systems/ equipment/ devices shall also meet other requirements stipulated under other Sub-sections/ parts/ sections of specification.

The make/model of various instruments/items/systems shall be as per NTPC/NBPPL approved vendor list. No commercial and delivery implication in this regard shall be acceptable.

In case of any conflict and repetition of clauses in the specification, the more stringent requirements among them are to be complied with.

##### **2. CONTROL SYSTEM**

- a) The controls for Self Cleaning Strainer system shall be realized in DDCMIS based control system (Owner's scope).
- b) Contractor shall furnish Instrument Schedule, I/O list, Drive list, Cable Schedule, Cable interconnection, JB grouping, Annunciation list, SOE list, List of Instruments/devices for HART in BHEL approved format. Also reusable database format like MS Excel, MS Access etc. of these documents shall also be provided by Contractor in BHEL approved format. Soft copy of the formats shall be provided to the successful bidder.



- c) Interface of MCC, HT SWGR, field instruments, Actuators etc. with DDCMIS based control system shall be as per Drive Control Philosophy enclosed in Sub Section- Control System, C&I Specification, Section-D of technical specification.

### **3. MEASURING INSTRUMENTS**

Primary instruments like Microprocessor based transmitters, pressure, diff. Pressure switches & gauges for :

- a) Complete Condenser Self Cleaning Strainer system package as per tender PID as of minimum.
- b) Integral to equipment which are not indicated in the tender drawings, but are required for control, monitoring and operation of the equipment / plant systems for which no P&IDs are enclosed, all the instruments shall be provided to meet the actual system requirements and meeting redundancy and other requirements specified under technical specifications subject to Employer's approval.
- c) For Binary and analog inputs required in major equipment protection, triple-sensing devices shall be provided. Binary and analog inputs, which are, required for protection of more than one equipment as well as protection signals for important auxiliaries and HT Drives (fed by a supply feeder of ratings 3.3 kV onwards) etc., triple sensing devices shall be provided.
- d) For other critical binary and analog inputs required for protection and interlock purpose of other equipment (e.g. those interlocks which may result in loss of generation, non-availability of a major equipment etc.), triple sensors shall be provided.
- e) Temperature elements (if applicable), electronic transmitters etc. are to be provided for all the cases.
- f) Temperature transmitters (if applicable), are to be provided by the contractor for all the temperature elements in the scope of the contractor. Compensating Cables, JB/rack & other erection hardware shall also be in scope of contractor.
- g) Rail mounted/ Rack mounted (Dual input Field mounted temperature transmitters)/ Field Bus Compatible temperature transmitters for temperature elements (for all the temperature elements being procured by the contractor) are to be provided (if applicable), by the contractor as per the followings.
  - i. Contractor shall provide atleast one dual input transmitter for temperature measurements being used in trip/protection/major interlock of Turbine Generator and Major auxiliaries. Eg when three/two temperature measurement points are being used to for monitoring one bearing temperature, both elements



of one duplex temperature element is to be connected to one dual input temperature transmitter.

- ii. Remaining temperature transmitter are to be Single Input DIN rail mounting type.
  - iii. Head mounted transmitters may be provided for temperature elements which are located in accessible areas as decided during detailed engineering.
- h) All the instruments shall be terminated upto JBs by Contractor. JBs shall be in Contractor's scope.
- i) Instrument installation and accessories required for the same shall be in Contractor's scope and shall be as per the instrument installation diagrams enclosed in the specification.
- j) Detailed specification of instruments, JB, Control panel etc. & Instrument Stub details, Instrument installation diagrams shall be as defined in Sub Section- Measuring Instruments, C&I Specification, Section-D of technical specification.
- k) Generally electronic transmitter shall be provided for the process measurements that are in the scope of the bidder. However the use of process actuated switches are also acceptable if it is a standard and proven practice of the bidder.

#### **4. INSTRUMENTATION CABLES & CONTROL CABLES**

Scope of Instrumentation cables(Screened Control Cables) & Control cables shall be as per Electrical Cable scope matrix in Electrical portion of specification.

#### **5. ELECTRICAL ACTUATORS**

Electrical Actuators with Integral starter shall be provided for all on/off and inching type valves in main plant and offsite areas along with necessary interface units for linking to Control System as applicable as detailed out in Sub Section- Electric Actuator, C&I Specification, Section-D of Technical Specification.

#### **6. TYPE TEST REQUIREMENT**



The type tests to be conducted for C&I systems & equipments shall be as detailed out in Sub Section- CNI TYPE TEST, Section-D of technical Specification.

#### **7. QUALITY ASSURANCE**

Contractor shall perform tests of C&I items/instruments/systems as per Sub-Section- Quality Assurance for C&I, Section-D of the technical specification.

#### **8. DOCUMENTS TO BE SUBMITTED AFTER AWARD OF CONTRACT**

Documents to be submitted after award of Contract shall be as defined in Sub Section- C&I Documents to be submitted after Award of Contract, C&I Specification, Section-D of technical specification.



TITLE : TECHNICAL SPECIFICATION  
FOR  
SELF CLEANING STRAINERS (SCS)

SPEC. NO. PE-TS-401-165-N003

VOLUME : IIB

SECTION : D

REV. NO. 0

DATE : 16.06.14

SHEET 1 of 1

## SECTION – D

### STANDARD TECHNICAL SPECIFICATION

SECTION D1 : SELF CLEANING STRAINERS

SECTION D2 : ELECTRICAL SYSTEMS

SECTION D3 : C&I SYSTEM



**TITLE : TECHNICAL SPECIFICATION  
FOR MOU  
SELF CLEANIGN STRAINER (SCS)**

**SPEC. NO. PE-TS-XXX-165-N001**

**VOLUME : III**

**SECTION :**

**REV. NO. 0**


**DATE : 12.06.2012**

**SHEET 1 of 1**

**SECTION D1**

**STANDARD TECHNICAL SPECIFICATION  
FOR  
SELF CLEANING STRAINER**

DMS (BHEL-PMM)  
6169430-2014/06/16

	TITLE :	SPEC. NO. <b>PE-TS- 999-165-N002</b>
	<b>STANDARD TECHNICAL SPECIFICATION</b>	VOLUME : II B
	<b>SELF - CLEANING FILTERS</b>	SECTION : D
		REV. NO. 0      DATE : 02.12.2009
		SHEET 1 OF 10

1.00.00    **GENERAL**

This specification covers the Design, Performance and Operational Requirements, Constructional Features, Manufacture, Assembly. Inspection and Testing at the Manufacturer's and/or his Sub-contractor's works and Painting for delivery of Self-cleaning filter (Backwash Type) complete with all accessories as specified hereinafter.

2.00.00    **CODES AND STANDARDS**

2.01.00    The design, materials manufacture, inspection and testing of the self-cleaning filter complete with all accessories, shall comply with the requirements of the latest revisions of the following appropriate codes and standards :

2.01.01    IS / BS / DIN / US Standards regarding pressure vessels, pipes, flanges and others as necessary.

2.01.02    IS / BS / DIN / ASTM Standards for materials specification and testing procedures.

2.01.03    IS / BS / DIN / AWWA Standards for valves and their testing.

2.02.00    In case of any conflict between the above codes / standards and this specification, the later shall prevail and in case of any further conflict in the matter, the interpretation of the specification by the Engineer shall be final and binding.

3.00.00    **DESIGN AND CONSTRUCTION**

3.01.00    **General Requirements**

3.01.01    Unless otherwise necessary manufacturer's standard and proven models of the self cleaning filter shall be supplied.

3.01.02    The self-cleaning filter shall be capable of safe, proper and continuous operation. Vibration, noise, mechanical stresses shall be kept within allowable limits specified by relevant codes / standards, In design due attention shall be given to ease of maintenance, repair and cleaning.


3.01.03    Suitable corrosion allowance shall be provided wherever necessary.

3.01.04    Unless otherwise specified in Data Sheet-A, the inlet and outlets of the filter shall be co-axial without any off set between the centre lines of inlet and outlet pipes.

3.02.00    **Performance Requirements**

The self-cleaning filter with all accessories shall be designed and guaranteed to meet the following requirements :-

3.02.01    The self - cleaning filter shall perform satisfactorily under the flow and pressure conditions specified in Data Sheet -A and shall be capable of housing the various forms of debris / sludge i.e., suspended particles / matter, mussels, grass, leaves,

	TITLE :	SPEC. NO. PE-TS- 999-165-N002
	STANDARD TECHNICAL SPECIFICATION	VOLUME : II B
	SELF - CLEANING FILTERS	SECTION : D
		REV. NO. 0      DATE : 02.12.2009
		SHEET 2 OF 10

wood pieces etc. The performance of the filter shall be continuous with minimum number of flushing / backwashing operations.

3.02.02 The self-cleaning filter shall be designed such that the pressure drop across the filter (i.e., between inlet and outlet connections) under clean conditions and partially (50%) choked conditions shall not be more than those specified in Data Sheet -A.

3.02.03 Unless otherwise specified in Data Sheet -A, debris discharge / wash water flow rate during flushing/back washing operation shall be limited to 10% of the total flow rate and flushing / backwashing operation shall be completed within a period of maximum three (3) minutes. The pressure drop across the debris filter during flushing/backwashing operation shall not be more than the pressure drop under partially (50%) choked condition.

3.02.04 The coarse particles and floating matter accumulating at the filter section/screen are flushed out of the system by the debris flushing / backwash unit such that the pressure drop across the filter after flushing / backwashing, shall not be more than the pressure drop under clean conditions.

3.03.00 **Operational Requirement**

The self-cleaning filter and other accessories shall be designed for the following flushing/backwashing operation modes :

3.03.01 Complete automatic flushing/backwashing operation effected by the following :-

- ◆ differential pressure measuring system at a pre-determined differential pressure across the filter
- ◆ adjustable timer (0-24 hours)
- ◆ push button (for manual initiation of sequential flushing / backwashing)


3.03.02 Manual operation in the event of failure of control system.

3.04.00 **Filter Housing / Body**

3.04.01 The self-cleaning filter housing/body shall be designed and manufactured as per the applicable codes for pressure vessels. However in no case thickness of housing/ body shall not be less than connecting pipe thickness as specified in Data Sheet-A. It shall house the filter section / screen assembly and shall have flanged inlet, outlet, flushing / debris discharge openings and pressure measuring tappings etc.

3.04.02 In design of filter housing / body due attention shall be given for easy removal and replacement of filter section / screen assembly.

3.04.03 The filter shall be provided with inspection hole with bolted cover.

	TITLE :	SPEC. NO. PE-TS- 999-165-N002
	STANDARD TECHNICAL SPECIFICATION	VOLUME : II B
	SELF - CLEANING FILTERS	SECTION : D
		REV. NO. 0      DATE : 02.12.2009
		SHEET 3 OF 10

3.04.04 The filter body / housing shall be provided with vent and drain connections with isolating valves. It shall be possible to drain unfiltered and filtered water.

3.04.05 If specified in Data Sheet-A, filter body/housing shall be epoxy painted.

3.05.00 **Filter Section / Screen assembly.**

3.05.01 The filter section/screen shall be designed for the maximum differential pressure across the filter and shall be securely positioned by a supporting cage and shall be securely mounted in the housing or body.

3.05.02 The perforation/mesh size of the filter section shall not be more than that specified in Data Sheet-A.

3.05.03 The arrangement of the filter section shall be such that there shall be no forced accumulation of debris.

3.06.00 **Differential Pressure Measuring System**

3.06.01 The self-cleaning filter shall be provided with a measuring system for differential pressure across the filter section/screen, to check debris accumulation and to initiate flushing / backwashing operation. This shall consist of a separate differential pressure transmitter for normal automatic flushing operation and separate DP Switch as a backup in the event of DPT failure, a differential pressure gauge for manual observation with adequate no. of tappings with isolating valves and equalizing valves.

3.06.02 The contacts for differential pressure transmitter, differential pressure switch and for differential pressure gauge shall be independent so that in the event of failure of one, the other is available .


3.06.03 The differential pressure measuring system shall also be equipped with built in flushing arrangement consisting of flushing pump, valves and associated piping, to prevent blockage of the system with any debris. Unless otherwise specified in Section C, water required for flushing the differential pressure measuring system shall be taken from downstream side of the strainer/ screen.

3.07.00 **Flushing / Backwash Unit :**

3.07.01 The self-cleaning filter shall be provided with suitable flushing/backwash unit (to be installed at ground floor) and debris discharge/backwash outlet valve with associated actuator to flush out the accumulated debris / sludge.

3.07.02 The flushing pump shall be provided with mechanical seals to the extent possible. If gland packing is provided it should be of good quality to prevent leakage of water from pump glands.

3.07.3 The flushing backwash unit shall be either fixed type with actuator operated

	TITLE :	SPEC. NO. PE-TS- 999-165-N002
	STANDARD TECHNICAL SPECIFICATION	VOLUME : II B
	SELF - CLEANING FILTERS	SECTION : D
		REV. NO. 0      DATE : 02.12.2009
		SHEET 4 OF 10

flushing valves or electric motor driven (through reduction gear) backwash rotor. In case of backwash rotor, it shall be fitted with removable shoes for smooth and close running contact with the filter section/screen and to prevent the unfiltered water from bypassing to waste.

3.07.04 If any water is to be injected for backwashing the filter section/screen, water shall be taken from down-stream side of the filter section/ screen with necessary pump, valves and piping for water injection supplied by the bidder.

3.07.05 View glass to be provided in debris outlet pipe to monitor the flushing of debris.

3.08.00 **Valves**

The flushing valves (if any,) the debris discharge/backwash outlet valve, isolation, vent and drain valves shall conform to appropriate codes / standards. The debris discharge/backwash outlet valve shall be larger than the debris discharge/back wash outlet pipe.

3.09.00 **Instrumentation and Control System**

3.09.01 Complete instrumentation and control system for automatic flushing / backwashing operation, protection, interlocking, indication/annunciation of high differential pressure and other malfunctions etc. shall be provided. This shall consist of adequate operational hardware, local control panel and interconnecting control and power cabling between the control panel and the self-cleaning filter and its associated electrical devices.

3.09.02 The control panel shall house all necessary instruments, indicating/ annunciation lamps, alarms, differential pressure indicator, timer, function selector switches, relays, protection and interlocking systems, start/stop push buttons, counter to register number of flushing operations etc., and shall be complete with internal wiring. In addition to the above, the control panel shall meet the requirements of the enclosed specification.

3.09.03 All instrumentation shall be of reputed make and shall meet the requirement of the enclosed specification.

3..10.00 **Other Accessories.**

3.10.01 Counter flanges, flat faced slip on type, complete with gaskets, bolts and nuts etc., shall be supplied for the filter inlet, outlet connections and all other terminal points. Fabrication, dimensions and drilling of the flanges shall conform to the codes/standards specified in Data Sheet-A.

3.10.02 Self-cleaning filter shall be provided with suitable lifting arrangement for handling during erection and maintenance.

3.10.03 Necessary supporting arrangement (wherever applicable) complete with foundation plates, bolts, nuts etc., shall be provided.

	TITLE :	SPEC. NO. PE-TS- 999-165-N002
	STANDARD TECHNICAL SPECIFICATION	VOLUME : II B
	SELF - CLEANING FILTERS	SECTION : D
		REV. NO. 0      DATE : 02.12.2009
		SHEET 5 OF 10

3.11.00 **Material of Construction**

Material of self-cleaning filter and other accessories shall be corrosion resistant and consistent with the fluid handled. However material specification for various components shall be equal or superior to those specified in Data Sheet-A.

4.00.00 **PAINTING**

4.01.00 The surface preparation of the filter housing / body and other parts shall be done as per the standard mentioned in Data Sheet-A and shall include the following :

- a) Removal of oil, grease, dirt and swarf etc.
- b) Removal of rust and scale etc.
- c) Sand blasting/shot blasting.

4.02.00 All internal surfaces of the filter which are subject to immersion or water spray and which are not made of stainless steel or other corrosion resistant materials after surface preparation, shall be coated with adequate coats (minimum 200 to 250 microns thick) of epoxy paint of approved make and quality over a coat of zinc chromite primer, unless otherwise specified in Data sheet-A.

4.03.00 The external surfaces of the filter and other accessories after surface preparation, shall be coated with adequate coats (minimum 175 to 200 microns thick) of synthetic enamel paint of approved make and quality over two coats of red oxide primer, unless otherwise specified in Data Sheet-A.

5.00.00 **SHOP INSPECTION AND TESTS**


5.01.00 **General :**

5.01.01 Manufacturer shall conduct all tests and stage inspections as per the approved quality plan to ensure that the self-cleaning filter and other accessories shall conform to the requirements of this specification and of the applicable codes/standards.


5.01.02 All materials used for manufacture/fabrication of the filter shall be of tested quality. Relevant test certificates for chemical analysis, mechanical tests and heat treatment shall be made available before the final shop inspection. In case the relevant test certificates are not available, the manufacturer shall arrange to carry out the necessary tests as per approved quality plan and applicable codes at his cost, for which samples shall be identified by BHEL's representative.

5.01.03 All shop tests shall be conducted in the presence of BHEL's representative and test certificates / reports for the same shall be furnished to BHEL for approval.

5.01.04 Qualification of welding procedures and welders shall be as per ASME B&PV

	TITLE :	SPEC. NO. PE-TS- 999-165-N002
	STANDARD TECHNICAL SPECIFICATION	VOLUME : II B
	SELF - CLEANING FILTERS	SECTION : D
		REV. NO. 0      DATE : 02.12.2009
		SHEET 6 OF 10

- Code, Section-IX / applicable codes.
- 5.02.00 **Filter Housing / Body**
- 5.02.01 Chemical analysis, mechanical tests shall be carried out on housing/body material.
- 5.02.02 All butt welded joints shall be subjected to radiographic / ultrasonic testing as per applicable codes. However all welded joints shall be subjected to 100% magnetic particle / penetrant testing to ensure freedom from defects.
- 5.03.00 **Rubber Lining (as applicable)**
- Rubber lining shall be subjected to surface crack test, 100% spark and hardness tests and shall be checked for layer thickness, defects etc.
- 5.04.00 **Filter Section/Screen assembly**
- Supporting cage and filter section/screen materials shall be tested for chemical properties. Checks shall be carried out for perforation/mesh size, defects etc.
- 5.05.00 **Flushing / Backwash Unit**
- 5.05.01 Material of various components of the flushing/Backwash Unit shall be tested for chemical and mechanical properties.
- 5.05.02 Hollow shaft of backwash rotor shall be ultrasonically tested as per ASTM-A 388 for internal flaws. Penetrant test shall be carried out for surface flaws.
- 5.06.00 **Valves**
- Inspection and testing of valves including leakage test shall be carried out as per the requirements of the applicable standards. Correlating test certificates for materials of the valve components shall be furnished.
- 5.07.00 **Flanges**
- 5.07.01 In case of fabricated flanges, all the welds shall be subjected to 100% radiography as per ASME B&PV code, section VIII, Division-1.
- 5.07.02 In case of forged flanges, ultrasonic testing shall be carried out as per ASTM-E 388.
- 5.07.03 If the thickness of the plate used for flanged is 40mm or more the same shall be checked ultrasonically as per ASTM-A 435 to demonstrate the absence of lamination and lack of fusion etc.
- 5.07.04 Chemical and mechanical test certificates shall furnish for flange materials.
- 5.07.05 Flanges shall be checked for edge preparation, fit up and satisfactory working with

	TITLE :	SPEC. NO. PE-TS- 999-165-N002
	STANDARD TECHNICAL SPECIFICATION	VOLUME : II B
	SELF - CLEANING FILTERS	SECTION : D
		REV. NO. 0      DATE : 02.12.2009
		SHEET 7 OF 10

5.08.00 matching parts.  
All materials for various nozzles, seals, pipes, gaskets, nuts bolts etc., shall be of tested quality and correlating test certificates for chemical and mechanical properties shall be furnished.

5.09.00 **Dimensional Checks**

Dimensional checks of various components of the filter shall be carried out as per the drawings approved by BHEL.

5.10.00 **Hydrostatic Test**

Hydrostatic test shall be conducted on the filter housing/body at a pressure of 2 times the design pressure. The duration of the test shall be minimum 30 minutes.

5.11.00 **Leakage Test**

Leakage test shall be conducted at the design pressure to demonstrate that the filter assembly is leak tight and no water seepage shall take place at various nozzle and valve connections.

5.12.00 **Functional Tests**

The self-cleaning filter assembly complete with valves, actuators and other accessories shall be subjected to functional tests and the following shall be checked :-

5.12.01 Smooth and free operation of all movable parts.

5.12.02 Interlocks and sequential operation.

5.12.03 Satisfactory operation of actuator torque switches, limit switches etc.

6.00.00 **TESTING AT SITE**

After completion of installation at site, the self cleaning filter with complete accessories, will be tested to check that the filter performance meets the requirements of its specification, Rectification of all defects shall have to be done by the supplier at no extra cost to the Owner / Purchaser. However the Owner / Purchaser reserves the right to reject the equipment / parts not meeting the requirement if the deficiency still persists.

7.00.00 **PERFORMANCE GUARANTEE**

7.00.00 **PERFORMANCE GUARANTEE & Bid evaluation criteria**

The Self cleaning strainer shall be guaranteed to meet the performance requirements specified in Section-D , Data Sheet A and Guarantee schedule and also for trouble free operation after commissioning. Schedule of performance guarantees (enclosed in

	TITLE :	SPEC. NO. PE-TS- 999-165-N002
	STANDARD TECHNICAL SPECIFICATION	VOLUME : II B
	SELF - CLEANING FILTERS	SECTION : D
	REV. NO. 0	DATE : 02.12.2009
	SHEET 8 OF 10	

Volume III) duly filled and signed shall be furnished with the bid.

The Performance guarantees of equipments shall stand valid till the satisfactory completion of performance testing & its acceptance by BHEL/ Customer. If the guarantee period specified in the Commercial Specification is higher, same shall prevail.

7.01.00 Performance Guarantee Parameters shall be as under :

- Pressure drop in Self cleaning strainer in clean condition viz. after backwashing.

7.02.01 Bidder to note that bids shall be evaluated on account of pressure drop across Self cleaning strainer (in clean condition) & liquidated damages on account of not meeting the same shall be in accordance with following :

**A) Bid Evaluation Criteria and Liquidated Damages:**

The bids received shall be evaluated for Pressure drop across Self cleaning strainer:

- The permissible limit of pressure drop across Self cleaning strainer in clean condition shall be 0.6 MWC.
- If the pressure drops quoted are higher than above limit, the bids shall be technically loaded @ Rate as mentioned in Data Sheet-A for respective projects per 1 MWC pressure drop (viz. per unit).
- However no advantage shall be given for pressure drops quoted less than above permissible limit.
- The maximum acceptable limit for pressure drop across self cleaning strainer ( with technical loadings) shall be 1.0 MWC

The bids will be technically rejected for pressure drops quoted higher than above maximum limit.

- The guaranteed pressure drops shall be demonstrated at site by vendors and if found higher shall be subject to LD @ twice the bid evaluation factor as above.


**8.00.00 QUALITY ASSURANCE & QUALITY PLAN**

8.01.00 The self - cleaning filter and other accessories to be supplied shall have assured quality and workmanship.

8.02.00 Typical quality plans (Q.P. No. PEM-MSE-SQP-07) are enclosed herewith this specification for bidder's guidance. The bidder shall comply with these minimum requirements and shall furnishing own quality plan based on materials and components of the filter being offered.

**9.00.00 NAME PLATE AND TAG NUMBERS**

9.01.00 The filter shall be provided with a permanently attached brass or stainless steel plate indicating the following details:-

	TITLE :	SPEC. NO. PE-TS- 999-165-N002
	STANDARD TECHNICAL SPECIFICATION	VOLUME : II B
	SELF - CLEANING FILTERS	SECTION : D
		REV. NO. 0      DATE : 02.12.2009
		SHEET 9 OF 10

- a) Design flow
- b) Design and test pressures
- c) Design temperature
- d) Filter section/screen mesh size
- e) Empty and operating weights
- f) Revolving speed of backwash rotor

9.02.00 Each valve shall be provided with a name plate indicating the following :-

- a) Service
- b) Design and test pressures
- c) Maximum flow and flow direction
- d) Size
- e) Engineer's Tag Number

Tag numbers will be indicated on the drawing submitted for approval during contract stage.

9.03.00 Each motor / actuator shall be provided with a name plate indicating the following details :

- a) Supply conditions.
- b) KW Rating
- c) Make

10.00.00 **DRAWINGS, DATA & INFORMATION TO BE SUBMITTED WITH THE BID**

The bidder shall furnish the following drawings, data and information alongwith the bid without which the offer will be deemed incomplete.

10.01.00 Data sheet-B with all particulars / data duly filled in.

10.02.00 General arrangement / installation drawings of the self-cleaning filter with all accessories, incorporating the principal dimensions and weights of equipment offered, size and location of various nozzle connections, supporting arrangement (if applicable) and scope of supply etc.

10.03.00 Cross-sectional / detailed drawings of filter housing / body, filter section / screen assemblies, flushing / backwashing unit, differential pressure measuring system, actuators, motors, control panel etc., indicating bill of quantities and materials of construction.

10.04.00 Flow and control logic diagrams for complete filter during normal and flushing / backwashing operations.

10.05.00 Performance evaluation procedure at site.

	TITLE :	SPEC. NO. PE-TS- 999-165-N002
बी एच ई एम	STANDARD TECHNICAL SPECIFICATION	VOLUME : II B
	SELF - CLEANING FILTERS	SECTION : D
		REV. NO. 0      DATE : 02.12.2009
		SHEET 10 OF 10

- 10.06.00 Control panel layout and list of instruments provided on control panel.
- 10.07.00 List of annunciations, protections and interlocks provided.
- 10.08.00 Write-up on operation, control, monitoring, interlocks and protection of filter.
- 10.09.00 Manufacturer's descriptive and illustrative literature on the equipments / components being offered.
- 10.10.00 A detailed experience list about the successful installations of similar equipment of equal or higher inlet / outlet sizes and flow capacities for similar application.
- 10.11.00 A comprehensive write-up on the testing facilities, tests to be conducted inspection methods and QA system adopted by the manufacturer.
- 10.12.00 Quality plan for the self-cleaning filter and for all its accessories.
- 11.00.00 **DRAWINGS, DATA & INFORMATION TO BE SUBMITTED AFTER THE AWARD OF CONTRACT :**
- The drawings, data and other documents as required in Data Sheet-C shall be furnished after the award of contract.



TITLE :  
**DATA SHEET – A2 FOR  
 SELF CLEANING STRAINERS (SCS)**

SPECIFICATION NO. SPEC. NO. **PE-TS-401-165-N003**

VOLUME : **II B**  
 SECTION : **D**

REV. NO. **00** DATE : **16.06.2014**

Page 1 of 8

S. No.	DESCRIPTION	UNITS	1x500 MW Firoz Gandhi Unchahar Thermal Power Plant
1.0	GENERAL		
1.1	Type of Strainers/ Filters	-	Self Cleaning Strainers
1.2	No. of Strainers/ Filters required	Nos.	Total 2 Sets viz. i.e.( 1 Working + 1 Standby) per unit
1.3	Inlet connection	mm Nb	700
1.3	Outlet connection	mm Nb	700
1.4	Filter type/ duty	-	On line / continuous
1.5	Location	-	ACW Pump Discharge Header (Indoor)
1.6	Liquid handled	-	Clarified Water as per analysis attached in Project information in section-B
<b>2.0</b>	<b>DESIGN DATA</b>		
2.1	Operating pressure	Bar (g)	2.0 to 3.0
2.2	Design pressure	Kg/cm <sup>2</sup>	7.5
2.3	Design temperature	Deg. C	60
2.4	Flow rate through filter		
	a) Normal		3200
	b) Maximum		4160



TITLE :  
**DATA SHEET – A2 FOR  
 SELF CLEANING STRAINERS (SCS)**

SPECIFICATION NO. SPEC. NO. **PE-TS-401-165-N003**

VOLUME : **II B**  
 SECTION : **D**

REV. NO. **00** DATE : **16.06.2014**

Page 2 of 8

S. No.	DESCRIPTION	UNITS	1x500 MW Firoz Gandhi Unchahar Thermal Power Plant
2.5	Design differential pressure for filter section/ screen	Bar (g)	1.5 (Min.)
2.6	Type of suspended matter likely to enter the filter	-	Typical debris encountered in closed circuit CW system with Cooling Tower
2.7	Differential pressure measuring system set pressure <ul style="list-style-type: none"> <li>• For initiating flushing/ backwashing</li> <li>• For alarm/ annunciation</li> </ul>	mbar	110
		mbar	160
2.8	Filter section/ screen perforation size	mm	2 mm (Max)
2.9	Free flow area in the screen basket	-	At least 120 % of pipe inlet area
3.0	<b>GUARANTEED PERFORMANCE REQUIREMENT</b>		
3.1	Pressure drop across the filter (i.e. between inlet and outlet connection) at normal flow	-	



TITLE :  
**DATA SHEET – A2 FOR  
 SELF CLEANING STRAINERS (SCS)**

SPECIFICATION NO. SPEC. NO. **PE-TS-401-165-N003**

VOLUME : **II B**  
 SECTION : **D**

REV. NO. **00** DATE : **16.06.2014**

Page 3 of 8

S. No.	DESCRIPTION	UNITS	1x500 MW Firoz Gandhi Unchahar Thermal Power Plant
	a) Clean condition	mbar	Refer Section – C of specification
	b) Partially (50%) chocked condition	mbar	Not to exceed 110
3.2	Debris discharge flow during flushing period	Cub m/ Hr.	Not to exceed 2.5% of total flow rate
4.0	<b>MATERIALS OF CONSTRUCTION</b>		
4.1	Filter body/ housing	-	Carbon Steel as per IS:210 Gr. FG 260 with epoxy painted inside Or ASTM-A-515 Gr. 75 OR CS to IS 2602
4.2	Filter screen/ section	-	SS-316
4.3	Shaft	-	SS-316
4.4	Supporting cage	-	SS-316
4.5	Differential measuring system	-	SS-316
4.6	Flushing/ backwashing unit	-	SS-316
4.7	Backwash rotor shoes	-	Neoprene
4.8	Any other internal hardware /pipes etc.	-	SS-316 or eq.



TITLE :  
**DATA SHEET – A2 FOR  
 SELF CLEANING STRAINERS (SCS)**

SPECIFICATION NO. SPEC. NO. **PE-TS-401-165-N003**

VOLUME : **II B**  
 SECTION : **D**

REV. NO. **00** DATE : **16.06.2014**

Page 4 of 8

S. No.	DESCRIPTION	UNITS	1x500 MW Firoz Gandhi Unchahar Thermal Power Plant
--------	-------------	-------	--

4.9	Valves	-	
4.9.1	Check Valves All Sizes		For size 50 NB and below – Piston type For sizes 65 NB and above-Swing check type or dual plate type.
	a) Body & Bonnet		CI, IS-210 Gr. FG 260 / BS 1452 Gr. 14, Flanged Ends
	b) Seating Surface and rings		13 % Chromium Steel
	c) Disc for check valve		CI, IS-210 Gr. FG 260 / BS 1452 Gr. 14
	d) Hing Pin		AISI 316
	e) Backseat		13 % Chromium Steel
4.9.2	Globe Valves 50 Nb & Below		
	Body, Bonnet & trim		IS 318 Gr. 2 / Eq
4.9.3	➤ BF Valves (65 Nb & above)		
	➤ Body & Disc		ASTM A48, Gr. 40 with 2% Ni / IS 210 Gr. FG 260 with 2% Ni and epoxy painted.
	➤ Shaft		BS 970 431 S: 291 / EN 57, <b>or</b> AISI-410 <b>or</b> AWWA-permitted shaft material equivalent to EN-57/AISI-410 or better.
	➤ Stem		Nitrile rubber
	➤ Sealing, Retaining segment & internals		18 – 8 SS
	➤ Bearings		Sleeve type Self lubricated
	➤ Companion Flange		IS 2062, Gr. B



TITLE :  
**DATA SHEET – A2 FOR  
 SELF CLEANING STRAINERS (SCS)**

SPECIFICATION NO. SPEC. NO. **PE-TS-401-165-N003**  
 VOLUME : **II B**  
 SECTION : **D**  
 REV. NO. **00** DATE : **16.06.2014**  
 Page 5 of 8

S. No.	DESCRIPTION	UNITS	1x500 MW Firoz Gandhi Unchahar Thermal Power Plant
	<b>C) Ball valves</b>		
	i) Body		SA 351 CF8M
	ii) Ballv		SA 351 CF8M
	iii) Stem		SS 316
4.10	Piping	-	By Bidder
	Material a) upto 150 Nb		<ul style="list-style-type: none"> <li>Carbon steel ERW, IS:1239 (Heavy Grade)</li> </ul>
	a) 200 Nb and above		<ul style="list-style-type: none"> <li>Greater than 150NB – CS to IS 2062 Gr. B, rolled &amp; butt welded, conforming to IS 3589</li> </ul>
4.11	Inspection Hole		Required, 600 NB
5.0	COUNTER FLANGES		In Bidder's Scope
5.1	Material		
	Flanges		IS 2062, Gr. B, epoxy painted
5.2	Drilling Standard	-	BS 4504 or equivalent
6.0	Connecting pipe size (OD & Thk)	mm	710 X 7.0
7.0	<b>PAINTING</b>		
7.1	External Surface	-	



TITLE :  
**DATA SHEET – A2 FOR  
 SELF CLEANING STRAINERS (SCS)**

SPECIFICATION NO. SPEC. NO. **PE-TS-401-165-N003**  
 VOLUME : **II B**  
 SECTION : **D**  
 REV. NO. **00** DATE : **16.06.2014**  
 Page 6 of 8

S. No.	DESCRIPTION	UNITS	1x500 MW Firoz Gandhi Unchahar Thermal Power Plant
	a) Surface preparation	-	SA 2.5 of Swedish Specification SIS 05.5900.197
	b) Primer		Epoxy based Zinc Phosphate
	Intermediate		Epoxy based TiO2 pigmented coat
	c) Final paint		Synthetic enamel paint to achieve DFT of 175 to 200 microns. Colour code shall be as per IS-1904
	d)		(Appendix-A)
7.2	Internal Surface		
	a) Surface preparation		SA 2.5 of Swedish Specification SIS 05.5900.197
	b) Primer		One coat of epoxy resin based primer
	c) Final paint		Applicable no. Of coats of coal tar epoxy paint to achieve total DFT of 200 to 250 microns
8.0	<b>SHOP TEST</b>		
8.1	Hydrostatic test		
	a) Test Pressure	bar (g)	1.5 times design pressure
	b) Test duration	min.	30
8.2	Leakage test		
	a) Test Pressure	bar (g)	Design Pressure
	b) Test duration	min.	30

# Bidder to note that electrical power supply shall be provided by purchaser based on electrical load list of bidder furnished at tender stage and any changes or additional requirement of electrical load by bidder during contract stage shall be provided by BHEL(purchaser) with cost repercussions to the bidder



TITLE :  
**DATA SHEET – A2 FOR  
 SELF CLEANING STRAINERS (SCS)**

SPECIFICATION NO. SPEC. NO. **PE-TS-401-165-N003**

VOLUME : **II B**  
 SECTION : **D**

REV. NO. **00** DATE : **16.06.2014**

Page 7 of 8

S. No.	DESCRIPTION	UNITS	1x500 MW Firoz Gandhi Unchahar Thermal Power Plant
--------	-------------	-------	--

9.0	Adequate provision for future installation of cathodic protection required		YES
10.0	Flow straightener for streamlining the ACW flow in SCS		If required as per bidder's design – the same to be incorporated by bidder in its constructional feature.
11.0	Performance Guarantee & Bid Evaluation		
11.1	Performance Parameters to be Guaranteed		
	❖ Pressure drop SCS		As per Guarantee schedule of bidder
11.2	Bid evaluation Criteria & Liquidated damages		As per clause no. 8.00.00 of section C1
11.3	Bid evaluation rate		@ Rs 80000 per 0.05 MWC pr. Drop across each SCS
11.4	Liquidated damages		Twice the bid evaluation rate
12.0	Whether automatic flushing/ back- washing operation effected by the following :  i. Differential pressure ii. Adjustable timer iii. Push button		YES  YES YES



TITLE :  
**DATA SHEET - A2 FOR  
SELF CLEANING STRAINERS (SCS)**


SPECIFICATION NO. SPEC. NO. PE-TS-401-165-N003

VOLUME : II B  
SECTION : D

REV. NO. 00 DATE : 16.06.2014

Page 8 of 8

S. No.	DESCRIPTION	UNITS	1x500 MW Firoz Gandhi Unchahar Thermal Power Plant
13.0	Whether provision for manual flushing / backwashing operation is made in the event of control system failure.		YES
14.0	Whether built in flushing arrangement complete with flushing pump, valves, and associated piping, is provided.		YES (if required)
15.0	Mandatory Spare to be supplied under this specification		NOT APPLICABLE

	TITLE :	SPECIFICATION NO. PE-TS-317/326-165-N002	
	DATA SHEET - C	VOLUME : II - B	
	SELF - CLEANING FILTER	SECTION : D	
	( Backwash Type )	REV. NO. 02	DATE : 02.12.2009
		SHEET 1 OF 2	

1.00.00 **DRAWINGS, DATA AND INFORMATION TO BE SUBMITTED AFTER THE AWARD OF CONTRACT :**

After the award of contract, the following drawings, data and information is to be submitted for review / approval of BHEL as per the distribution schedule given in Section -C.

1.01.00 Within 3 (three) weeks of the data of LOI, the following shall be submitted :

1.01.01 Data Sheet -B duly revised conforming to accepted bid.

1.01.02 Final versions of the following drawings to enable BHEL to finalise the layout and to design foundations and structures.

a) General arrangement / Installation drawings of the self-cleaning filter with all accessories, indicating the principal dimensions and weights of equipment offered, size and location of various nozzle connections, withdrawal space and scope of supply etc.

b) Foundation arrangement drawings (wherever applicable) showing load data on supports, size and location of another bolts etc.

1.02.00 **With in the stipulated time period as per vendor's drawing/document list, the following shall be submitted :**

1.02.01 Cross-sectional/detailed drawings of filter housing/body, filter screen/section assembly, flushing / backwash unit, differential pressure measuring system, actuators, motors, control panel etc. indicating bill of quantities and materials of construction.

10.02.02 Flow and control logic diagrams for complete filter during normal and flushing operation and system write-up covering all modes of operation.

1.02.03 Final version of performance evaluation procedures at site.


1.02.04 Detailed schedule of valves indicating tag numbers, type, make, size, pressure & temperature ratings, materials etc.

1.02.05 Detailed schedule of power & control cable.

1.02.06 Detailed schedule of piping and fittings indicating sizes, materials, maximum working pressure & temperatures etc.

1.02.07 Control panel layout and list of instruments provided on control panel and internal wiring diagrams.

1.02.08 List of annunciations, protections and interlocks provided.

	<b>TITLE :</b>	<b>SPECIFICATION NO. PE-TS-317/326-165-N002</b>	
	<b>DATA SHEET - C</b>	<b>VOLUME : II - B</b>	
	<b>SELF - CLEANING FILTER</b>	<b>SECTION : D</b>	
	<b>( Backwash Type )</b>	<b>REV. NO. 02</b>	<b>DATE : 02.12.2009</b>
		<b>SHEET 2 OF 2</b>	

- 1.02.09 Detailed drawings of flanges.
- 1.02.10 Quality Plan
- 1.02.11 Material test certificates.
- 1.02.12 Shop tests reports and certificates.
- 1.02.13 Write-up and instruction manuals for erection, operation and maintenance.
- 1.02.14 Storage instructions.
- 1.02.15 Vendor to send 3 sets of final documents (O&M Manual, GA drg, P&ID) direct to site under intimation to PEM.

DMS (BHEL-PEM)  
 6169430-2014/06/16



Manufacturer's Name & Address		STANDARD QUALITY PLAN		BHEL Doc No.: PE-V4-XXX-165-N08	
P.O. No.		Item :	Vendor O.P. NO.	PROJECT:	
		Self Cleaning Strainer	PACKAGE : SELF CLEANING STRAINER	CUSTOMER:	
			Date :	PURCHASER:	
			Page 01 of 12	CONSULTANT:	
SL. NO.	DESCRIPTION			PAGE NOS.	
1	SELF CLEANING STRAINER			2-4	
2	BALL VALVES			5	
3	BUTTERFLY VALVES			6	
4	PRESSURE GAUGE, DP GAUGE, DP SWITCH			7	
	DP TRANSMITTER				
5	GEAR MOTOR DRIVE & WORM PLANETARY GEAR BOX			8	
6	ACTUATORS			9	
7	STARTER PANEL			10	
8	FASTENERS			11	
9	ALL COMPONENT / EQUIPMENT			12	
	ANNEXURES				
	DRY RUN TEST PROCEDURE			2	
	HYDRO TEST PROCEDURE			2	
	HYDRO STATIC LEAK TIGHTNESS TESTING PROCEDURE			2	
	PACKING PROCEDURE			1	
<p>Note: Items not included in quality plan to be inspected as per Approved datasheet/drawings.</p>					
<p><b>LEGEND</b></p> <p>* Records identified with "STAR" shall be essentially included by contractor in QA Documentation.</p> <p>** M : Manufacturer/ Sub-contractor</p> <p>C : CONTRACTOR</p> <p>D : OWNER</p> <p>Indicate : "p" - Perform, "W" - Witness and "V" - Verification</p>					
Manufacturer / Sub-Contractor Signature		Contractor		Name & Sign. Of approving authority & Seal	

BHEL Logo		Manufacturer's Name & Address		STANDARD QUALITY PLAN		BHEL Doc No.: PE-V4-XXX-165-N08	
Item :		Vendor O.P. NO.		PROJECT:		CUSTOMER:	
Self Cleaning Strainer		PACKAGE : SELF CLEANING STRAINER		PURCHASER:		CONSULTANT:	
P.O. No.		Date :		Page 02 of 12		Agency	
Characteristics Checked		Reference Documents		Acceptance Norms		Format of Record	
Class		Type of Check		Quantum of Check		M C O	
3		4		5		6	
2		3		4		5	
1.0.0	SELF CLEANING STRAINER						
1.1.0	Raw Material						
[a]	Housing Shell, Nozzle flanges & Main flanges/Counter Flange	Major	Chemical Analysis	One sample/cast / heat / batch	Approved drg/Data sheet	MI Test Certificate / lab test report / raw material flow sheet	P V
	Physical properties	Major	Physical test	One sample/cast / heat / batch	Approved drg/Data sheet	MI Test Certificate / lab test report / raw material flow sheet	P V
	Surface Defects	Minor	Visual	100%	Approved drg/Data sheet	MI Test Certificate / Inspection Report	P V
	Sub Surface Defects	Major	Ultrasonic Test	100%	ASME A 435/A609	Inspection report	P V
[b]	Nozzle Pipes	Major	Chemical Analysis	One sample/cast / heat / batch	Approved drg/Data sheet	MI Test Certificate / lab test report / raw material flow sheet	P V
	Physical properties	Major	Physical test	One sample/cast / heat / batch	Approved drg/Data sheet	MI Test Certificate / lab test report / raw material flow sheet	P V
	Surface defects	Minor	Visual	100%	Approved drg/Data sheet	MI Test Certificate / Inspection Report	P V
	Leak tightness	Major	Hydrostatic test	100%	Approved drg/Data sheet	MI Test Certificate / Inspection Report	P V
[c]	Screen basket, Nozzle flanges	Major	Chemical Analysis	One sample/cast / heat / batch	Approved drg/Data sheet	MI Test Certificate / lab test report / raw material flow sheet	P V
	Physical properties	Major	Physical test	One sample/cast / heat / batch	Approved drg/Data sheet	MI Test Certificate / lab test report / raw material flow sheet	P V
	Surface Defects	Minor	Visual	100%	Approved drg/Data sheet	MI Test Certificate / Inspection Report	P V
	Sub-surface defects	Major	Ultrasonic test	100%	ASME A 745	Inspection report	P V
	Corrosion Resistance	Major	IGCI	One/Heat	ASTM A 262	Test Report	P V
<b>LEGEND</b> * Records identified with "STAR" shall be essentially included by Contractor in QA Documentation. ** M - Manufacturer/ Sub-contractor C - CONTRACTOR O- OWNER Indicate : P - Perform, "V" - Witness and "Y" - Verification							
Manufacturer / Sub-Contractor Signature		Contractor		Name & Sign. Of approving authority & Seal			

Manufacturer's Name & Address		STANDARD QUALITY PLAN		BHEL Doc No.: PE-V4-XXX-165-N08						
Item :		Vendor O.P. NO.		PROJECT:						
Self Cleaning Strainer		PACKAGE : SELF CLEANING STRAINER		CUSTOMER:						
P.O. No.		Date :		PURCHASER:						
		Page 03 of 12		CONSULTANT:						
Sl. No.	Component / Operation	Class	Type of Check	Quantum of Check	Reference Documents	Acceptance Norms	Format of Record	Agency	Remarks	
3	4	5	6	7	8	9	10	11		
[d]	Nozzle Pipes	Major	Chemical Analysis	One sample/cast / heat / batch	Approved drg/Data sheet	Approved drg/Data sheet	Mill Test Certificate / lab test report / raw material flow sheet	P	V	11
	Physical properties	Major	Physical test	One sample/cast / heat / batch	Approved drg/Data sheet	Approved drg/Data sheet	Mill Test Certificate / lab test report / raw material flow sheet	P	V	
	Surface defects	Minor	Visual	100%	Approved drg/Data sheet	Approved drg/Data sheet	Mill Test Certificate/ Inspection Report	P	V	
	Leak tightness	Major	Hydrostatic test	100%	Approved drg/Data sheet	Approved drg/Data sheet	Mill Test Certificate/ Inspection Report	P	V	
1.2.0	Inprocess Quality Control									
1.2.1	Welding procedure specification	Critical	Scrutiny	100%	ASME Sec. IX	ASME Sec. IX	QW 482 of ASME Sec.IX	P	V	Welders already qualified by BHEL/ LRQA / NTPC in the past shall be employed for this job.
1.2.2	Welding procedure qualification	Critical	Physical test	100%	ASME Sec. IX	ASME Sec. IX	QW 483 of ASME Sec.IX	P	V	Welding procedure already approved by BHEL/ LRQA / NTPC shall be followed.
1.2.3	Welder performance qualification	Critical	Physical test	100%	ASME Sec. IX	ASME Sec. IX	QW 484 of ASME Sec.IX	P	V	Welders already qualified by BHEL/ LRQA / NTPC shall be employed for this job.
1.2.4	Fit-up of butt weld	Major	Template, visual	100%	Manufacturing Drawing	ASME Sec.VIII Div. I	Log book	P	V	BHEL to witness >20mm thick butt joint.
1.2.5	Fit-up of shell flange and nozzle assembly to shell	Major	Template, visual	100%	Manufacturing Drawing	ASME Sec.VIII Div. I	Log book	P	V	
1.2.6	Weld quality for Pressure Parts									
1.2.7	(a) Root run	Major	Penetrant test / Visual	100%	ASME Sec.VIII Div. I / sec V Appendix 8	ASME Sec.VIII Div. I / sec V Appendix 8	Operation Process Sheet	P	V	
	1. Surface defects	Major	Penetrant test	100%	ASME Sec.VIII Div. I / sec V Appendix 8	ASME Sec.VIII Div. I / sec V Appendix 8	Inspection report	P	V	
	2. Sub-surface defects	Critical	Radiography test	10% of total weld length* 100% Joints	ASME Sec.VIII Div. I / sec V Appendix 4 / UW 52	ASME Sec.VIII Div. I / sec V Appendix 4 / UW 52	(Radiographs and inspection report	P	V	RT films will be reviewed by BHEL
	(b) Completed fillet welds	Major	Penetrant test	100%	ASME Sec.VIII Div. I / sec V Appendix 8	ASME Sec.VIII Div. I / sec V Appendix 8	Inspection report	P	V	
<b>LEGEND</b>										
* Records identified with "STAR" shall be essentially included by contractor in QA Documentation.										
** M - Manufacturer/ Sub-contractor										
C - CONTRACTOR										
O - OWNER										
Indicate "P" - Perform, "W" - Witness and "V" - Verification										
Manufacturer / Sub-Contractor Signature										
Contractor										
Name & Sign. Of approving authority & Seal										

BHEL Logo		STANDARD QUALITY PLAN									
Manufacturer's Name & Address		Item :		Vendor O.P. NO.		BHEL Doc No.:		PROJECT:		PE-V4-XXX-165-N08	
P.O. No.		Self Cleaning Strainer		PACKAGE : SELF CLEANING STRAINER		CUSTOMER:		PURCHASER:			
Characteristics Checked		Class		Type of Check		Reference Documents		Acceptance Norms		Format of Record	
3		4		5		7		8		9	
Component / Operation		Checked		Check		Check		Check		Check	
2		4		5		7		8		9	
1		3		5		7		8		9	
1.2.8 Pickling and Passivation		Major		Visual		IS : 10117		IS : 10117		Log Book	
1.2.9 Fabricated Shell (Prior to sand blasting)		Major		Measurement by visual		Manufacturing Drawing		Manufacturing Drawing		Inspection report	
1.3.0 Final tests (completed equipments) - After assembly		Critical		Hydrostatic Pr. @ 1.5 times of design pr.(positive) [Duration 30 minutes]		ASME Sec.VIII Div.1		ASME Sec.VIII Div.1		Inspection report	
1.3.0 Final tests (completed equipments) - After assembly		Major		Measurement by visual		G.A.drawing		G.A.drawing		Inspection report	
1.3.0 Final tests (completed equipments) - After assembly		Critical		Leak test @ design pr.(positive) [Duration 30 minutes]		ASME Sec.VIII Div.1		ASME Sec.VIII Div.1		Inspection report	
1.3.0 Final tests (completed equipments) - After assembly		Critical		Operational test		Approved Procedure		Approved Procedure		Inspection report	
1.4.0 Rubber Lining ( Shell )		Major		Physical test		Manufacturer's procedure		BS 6374/Equivalent		Manufacturers certificate	
1.4.1 Rubber Formulation		Major		Flame test		For Semi Ebonite /Ebonite / polymer/Ebonite Polymer catches on removal from fire and on removal from fire continues to burn		For Semi Ebonite /Ebonite / polymer/Ebonite Polymer catches on removal from fire and on removal from fire continues to burn		Inspection report	
1.4.2 Surface preparation of items to be lined		Major		Immersion test (One per lot bleeding test)		ASTM D 471		+/- 1%		Inspection report	
1.4.3 Vulcanising		Major		Visual		SA 2.5		SA 2.5		Manufacturers inspection report	
1.4.4 Vulcanised Rubber Lined Items		Major		Process monitoring		Manufacturer's procedure		Manufacturer Procedure		Process Procedure	
1.4.4 Vulcanised Rubber Lined Items		Major		Chip test		Approved Drawing & BS 6374/Equivalent		BS 6374/Equivalent		Inspection report	
1.4.4 Vulcanised Rubber Lined Items		Major		Measurement, Visual defects, Thickness & Hardness		100% Thickness/ Visual inspection hardness at random		Approved Drawing & BS 6374/Equivalent		Inspection report	
1.4.4 Vulcanised Rubber Lined Items		Major		Spark test for Pin Holes at 5 kv/mm		100%		Approved Drawing & BS 6374/Equivalent		Inspection report	
<b>LEGEND</b> * Records identified with "STAR" shall be essentially included by contractor in QA Documentation. ** M - Manufacturer/ Sub-contractor C - CONTRACTOR O - OWNER Indicate : "P" - Perform, "W" - Witness and "V" - Verification											
Manufacturer / Sub-Contractor Signature		Contractor		O - OWNER		C - CONTRACTOR		M - Manufacturer/ Sub-contractor		Name & Sign. of approving authority & Seal	



STANDARD QUALITY PLAN		BHEL Doc No.: PE-V4-XXX-165-N08							
Item :		PROJECT :							
Self Cleaning Strainer		CUSTOMER :							
P.O. No.		PURCHASER :							
Date :		CONSULTANT :							
Page 06 of 12									
Sl. No.	Component / Operation	Class	Type of Check	Quantum of Check	Reference Documents	Acceptance Norms	Format of Record	Agency	Remarks
1	2	3	4	5	6	7	8	9	10
3.0.0	Materials								
3.1.0	Butterfly valves Body and Disc	Major	Chemical properties	One Sample/Cast / heat	Approved drg/Data sheet	Approved drg/Data sheet	Manufacturer's T.C.	P	V
3.1.1	Shaft	Major	Physical properties	One Sample/Cast / heat / batch	Approved drg/Data sheet	Approved drg/Data sheet	Manufacturer's T.C.	P	V
3.1.2	Seat	Major	Chemical properties	One Sample/Cast / heat	Approved drg/Data sheet	Approved drg/Data sheet	Manufacturer's T.C.	P	V
3.1.3	Stem	Major	Physical properties	One Sample/Cast / heat / batch	Approved drg/Data sheet	Approved drg/Data sheet	Manufacturer's T.C.	P	V
3.2.0	Assembly	Major	Chemical properties	One Sample/Cast / heat	Approved drg/Data sheet	Approved drg/Data sheet	Manufacturer's T.C.	P	V
3.3.0	Testing	Major	Physical properties	One Sample/Cast / heat / batch	Approved drg/Data sheet	Approved drg/Data sheet	Manufacturer's T.C.	P	V
		Major	Measurement	100%	EN ISO 17292/ Appd data sheet	EN ISO 17292/ Appd data sheet	Manufacturer's T.C.	P	V
		Major	Operation	100%	--	As per approved data sheet	--	P	--
		Critical	Hydraulic test	100%	EN 12266-1&2/API 598	EN 12266-1&2/API 598 & Appd. Data sheet	Manufacturer's T.C.	P	V
		Critical	Hydraulic test	100%	EN 12266-1&2/API 598	EN 12266-1&2/API 598 & Appd. Data sheet	Manufacturer's T.C.	P	V
		Critical	Air test	100%	EN 12266-1&2/API 598	EN 12266-1&2/API 598 & Appd. Data sheet	Manufacturer's T.C.	P	V
		<b>LEGEND</b> * Records identified with "STAR" shall be essentially included by contractor in QA Documentation. ** M : Manufacturer/ Sub-contractor C : CONTRACTOR O: OWNER Indicate : "p" - Perform, "W" - Witness and "V" - Verification							
		Manufacturer / Sub-Contractor Signature Contractor Name & Sign. Of approving authority & Seal							



Manufacturer's Name & Address		Manufacturing Quality Plan				BHEL Doc No.: PE-V4-XXX-165-N08				
P.O. No.		Vendor O.P. NO. PACKAGE: SELF CLEANING STRAINER PURCHASER: CONSULTANT:				PROJECT: PURCHASER: CONSULTANT:				
Item : Geared Motor drive & Worm planetary Gear box		Date : Page 08 of 12				M C O				
Sl. No.	Component / Operation	Characteristics Checked	Class	Type of Check	Quantum of Check	Reference Documents	Acceptance Norms	Format of Record	Agency	Remarks
1	2	3	4	5	6	7	8	9	10	11
5.0.0	GEARED MOTOR DRIVE	Running Test No load Noise test Oil leakage test	Critical Critical Critical Critical	Functional Test Functional test Functional test Functional test	100% 100% 100% 100%	Approved Data Sheet Approved Data Sheet Approved Data Sheet Approved Data Sheet	Approved Data Sheet Approved Data Sheet Approved Data Sheet Approved Data Sheet	Manufacturer's compliance certificate	* * * *	P V V V V V V V
5.1.0	Complete Unit of planetary gear	No Leak Test Noise Level Visual Name plate Verification	Critical Minor Minor	Functional test Functional test -	One Sample/lot One Sample/lot 100%	Approved Data Sheet Approved Data Sheet Approved Data Sheet	Approved Data Sheet Approved Data Sheet Approved Data Sheet	Supplier Catalogue Approved Data Sheet Approved Data Sheet	*  P P P	P V V V V V V V
<b>LEGEND</b> * Records identified with "STAR" shall be essentially included by contractor in QA Documentation. * M : Manufacturer/Sub-contractor C : CONTRACTOR IO : OWNER Indicate - "P" - Perform, "N" - Witness and "V" - Verification										
Manufacturer / Sub-Contractor Signature										Name & Sign. Of approving authority & Seal

Component / Operation		Manufacturer's Name & Address		Item : Actuators		Manufacturing Quality Plan		BHEL Doc No.: PE-V4-XXX-165-N08	
Sl. No.	Characteristics Checked	Class	Type of Check	Quantum of Check	Reference Documents	Acceptance Norms	Format of Record	P	M
1	3	4	5	6	7	8	9	C	O
6.0.0	Actuators	Major	Electrical test	100%	Supplier catalogue/Appd data sheet	Supplier catalogue/Appd Test certificate data sheet	Test certificate	*	V
	Functional test	Major	Visual	100%	Supplier catalogue/Appd data sheet	Supplier catalogue/Appd data sheet	Inspection Report	-	-
	Make, Range, Model	Major	Visual	100%	Supplier catalogue/Appd data sheet	Supplier catalogue/Appd data sheet	Inspection Report	-	-
	Assembly check alongwith valves	Major	Visual	100%	Supplier catalogue/Appd data sheet	Supplier catalogue/Appd data sheet	Inspection Report	-	-
	Functional Check along with settings / Auxiliary Contacts	Major	Visual	100%	Supplier catalogue	Supplier catalogue/Appd data sheet	Inspection Report	-	Review of TC's
<p><b>LEGEND</b></p> <ul style="list-style-type: none"> <li>* Records identified with "STAR" shall be essentially included by contractor in QA Documentation.</li> <li>** M : Manufacturer/ Sub-contractor</li> <li>C : CONTRACTOR</li> <li>O: OWNER</li> </ul> <p>Indicate : 'P' - Perform, 'W' - Witness and 'V' - Verification</p>									
<p>Manufacturer / Sub-Contractor Signature</p>									
<p>Name &amp; Sign. Of approving authority &amp; Seal</p>									

Manufacturer's Name & Address		Manufacturer's Name & Address		Item : Starter Panel		Manufacturing Quality Plan		BHEL Doc No.: PE-V4-XXX-165-N08	
P.O. No.		Vendor Q.P. NO.		PACKAGE : SELF CLEANING STRAINER		PROJECT:		CUSTOMER:	
Characteristics Checked		Reference Documents		Acceptance Norms		Format of Record		PURCHASER:	
Class		Quantum of Check		Type of Check		Agency		CONSULTANT:	
3		6		5		M C O		Remarks	
4		7		8		9		10	
1		2		3		4		5	
7.0.0	<b>Starter panel</b>								
7.1.0	Incoming Material								
7.1.1	Fabricated & Painted Panel	Dimension	Major	Measurement	100%	Approved Drgs.	Inspection report	P	7 tank treatment before painting
		Panel G.A.	Major	Measurement	100%	Approved Drgs.	Inspection report	P	
		Paint colour	Major	Visual	100%	Approved Drgs.	Inspection report	P	
		Paint thickness	Major	Measurement	100%	Approved Drgs.	Inspection report	P	
		Paint Shade,	Major	Visual	Sample	Approved Drgs.	Inspection report	P	
		Adhesion	Major	Visual	Sample	Approved Drgs.	Inspection report	P	
7.1.2	Wire	Size / Colour / Rating / Surface Defects	Major	Dimension / Electrical	100%	IS 694	Inspection report	P	ISI Marked wire
7.1.3	Panel Mounting	Make, Functional, Type & Rating	Major	Visual / Electrical	100%	Approved BOM	---	P	For bolt list refer starter panel document Part - II
7.2.0	In Process Inspection								
7.2.1	Name Plate, Component Mounting, Etc.	Workmanship, Finish, Correctness	Major	Visual	100%	Approved Drgs.	Inspection report	P	
7.2.2	Electrical Wiring of Panels	Continuity, Colour of wires, Bundling and Grouping	Major	Visual	100%	Mounting Drawing	Inspection report	P	
7.2.3	Ferruling of Cables	Start & End	Major	Visual	100%	Manufacturer's drawing	Inspection report	P	
7.3.0	Final Inspection								
7.3.1	Workmanship, Finish & Paint shade / Thickness	Visual	Major	Visual	100%	G.A Drawing	Inspection report	P	
7.3.2	Overall Dimension, G.A of starter panel	Measurement	Major	Visual	100%	G.A Drawing	Test Certificate	P	
7.3.3	Component Identification	Visual	Major	Visual	100%	G.A Drawing	Inspection report	P	
7.3.4	IR - HV - IR	Electrical	Critical	Electrical	100%	Mfg.Procedure Appd Drawing	Inspection report	P	
7.3.5	Functional & Continuity	Functional	Major	Functional	100%	Mfg.Procedure Appd Drawing	Inspection report	P	
<p><b>LEGEND</b></p> <p>* Records identified with "STAR" shall be essentially included by contractor in QA Documentation.</p> <p>** M : Manufacturer/ Sub-contractor</p> <p>C : CONTRACTOR / O. OWNER</p> <p>Indicate : 'P' - Perform, 'W' - Witness and 'V' - Verification</p>									
Manufacturer / Sub-Contractor Signature		Contractor						Name & Sign. Of approving authority & Seal	

Manufacturer's Name & Address		Item : Fasteners		Manufacturing Quality Plan		BHEL Doc No.: PE-V4-XXX-165-N08					
P.O. No.		Vendor Q.P. NO.		PACKAGE : SELF CLEANING STRAINER		PROJECT:					
Characteristics Checked		Date :		Page 11 of 12		CUSTOMER:					
Class		Reference Documents		Acceptance Norms		PURCHASER:					
Type of Check		Quantum of Check		Format of Record		CONSULTANT:					
3		4		5		M A G C O					
2		3		4		10					
1		3		4		11					
1	Component / Operation	2	3	4	5	6	7	8	9	10	11
B.1.0	Internal Fasteners - SS										
B.1.1	Stainless Steel Fasteners	Chemical properties	Major	Chemical analysis	1 Per heat/HT Batch	Approved Drawing	Approved Drawing	Approved Drawing	Test certificate/Compliance certificate	P	V
		Physical properties	Major	Physical test	1 per heat	Approved Drawing	Approved Drawing	Approved Drawing	Test certificate/Compliance certificate	P	V
		Visual Workmanship and finish	Major	Visual	Sample	Approved Drawing	Approved Drawing	Approved Drawing	Inspection report	P	V
		Dimensions	Major	Measurement	Sample	Approved Drawing	Approved Drawing	Approved Drawing	Inspection report	P	V
B.2.0	Carbon steel fasteners	Visual	Major	Visual	Sample	Approved Drawing	Approved Drawing	Approved Drawing	Manufacturer's certificate / Lab Report	P	V
		Dimensions	Major	Measurement	Sample	Approved Drawing	Approved Drawing	Approved Drawing	Manufacturer's certificate / Lab Report	P	V
		Physical properties	**	Physical test	1 sample per IS : 1367 heat	IS : 1367	IS : 1367	IS : 1367	Manufacturer's certificate / Lab Report	P	V
				a) Tensile							
				b) Yield							
				c) Elongation							
				d) Proof load							
<p><b>LEGEND</b></p> <p>* Records identified with "STAR" shall be essentially included by contractor in QA Documentation.</p> <p>** Manufacturer Sub-contractor</p> <p>C : CONTRACTOR W : Witness and V : Verification</p>											
<p>Manufacturer / Sub-Contractor Signature</p> <p>Contractor</p>											
<p>Name &amp; Sign. Of approving authority &amp; Seal</p>											





TITLE : TECHNICAL SPECIFICATION  
FOR  
SELF CLEANING STRAINERS (SCS)

SPEC. NO. PE-TS-401-165-N003

VOLUME : IIB

SECTION : D

REV. NO. 0

DATE : 16.06.14

SHEET 1 of 1

## SECTION D2

### STANDARD TECHNICAL SPECIFICATION FOR ELECTRICAL SYSTEMS

<b>TITLE :</b> <b>GENERAL TECHNICAL REQUIREMENTS</b>  <b>FOR</b>  <b>LV MOTORS</b>	<b>SPECIFICATION NO.</b> PE-SS-999-506-E101
	<b>VOLUME NO. :</b> <b>II-B</b>
	<b>SECTION :</b> <b>D</b>
	<b>REV NO. : 00</b> <b>DATE :</b> 28.01.10
	<b>SHEET :</b> 1 OF 1

**GENERAL TECHNICAL REQUIREMENTS**

**FOR**

**LV MOTORS**

**SPECIFICATION NO.: PE-SS-999-506-E101 Rev 00**

<b>TITLE :</b> <b>GENERAL TECHNICAL REQUIREMENTS</b>  <b>FOR</b>  <b>LV MOTORS</b>	<b>SPECIFICATION NO.</b> PE-SS-999-506-E101
	<b>VOLUME NO. : II-B</b>
	<b>SECTION : D</b>
	<b>REV NO. : 00 DATE : 28.01.10</b>
	<b>SHEET : 1 OF 4</b>

### 1.0 INTENT OF SPECIFICATION

The specification covers the design, materials, constructional features, manufacture, inspection and testing at manufacturer's work, and packing of Low voltage (LV) squirrel cage induction motors along with all accessories for driving auxiliaries in thermal power station.

Motors having a voltage rating of below 1000V are referred to as low voltage (LV) motors.

### 2.0 CODES AND STANDARDS

Motors shall fully comply with latest edition, including all amendments and revision, of following codes and standards:

IS:325	Three phase Induction motors
IS : 900	Code of practice for installation and maintenance of induction motors
IS: 996	Single phase small AC and universal motors
IS: 4722	Rotating Electrical machines
IS: 4691	Degree of Protection provided by enclosures for rotating electrical machines
IS: 4728	Terminal marking and direction of rotation rotating electrical machines
IS: 1231	Dimensions of three phase foot mounted induction motors
IS: 8789	Values of performance characteristics for three phase induction motors
IS: 13555	Guide for selection and application of 3-phase A.C. induction motors for different types of driven equipment
IS: 2148	Flame proof enclosures for electrical appliance
IS: 5571	Guide for selection of electrical equipment for hazardous areas
IS: 12824	Type of duty and classes of rating assigned
IS: 12802	Temperature rise measurement of rotating electrical machines
IS: 12065	Permissible limits of noise level for rotating electrical machines
IS: 12075	Mechanical vibration of rotating electrical machines

In case of imported motors, motors as per IEC-34 shall also be acceptable.

### 3.0 DESIGN REQUIREMENTS

3.1 Motors and accessories shall be designed to operate satisfactorily under conditions specified in data sheet-A and Project Information, including voltage & frequency variation of supply system as defined in Data sheet-A

3.2 Motors shall be continuously rated at the design ambient temperature specified in Data Sheet-A and other site conditions specified under Project Information  
 Motor ratings shall have at least a 15% margin over the continuous maximum demand of the driven equipment, under entire operating range including voltage & frequency variation specified above.

#### 3.3 Starting Requirements

3.3.1 Motor characteristics such as speed, starting torque, break away torque and starting time shall be properly co-ordinated with the requirements of driven equipment. The accelerating torque at any speed with the minimum starting voltage shall be at least 10% higher than that of the driven equipment.

3.3.2 Motors shall be capable of starting and accelerating the load with direct on line starting without exceeding acceptable winding temperature.

<b>TITLE :</b> <b>GENERAL TECHNICAL REQUIREMENTS</b>  <b>FOR</b>  <b>LV MOTORS</b>	<b>SPECIFICATION NO.</b> PE-SS-999-506-E101
	<b>VOLUME NO. : II-B</b>
	<b>SECTION : D</b>
	<b>REV NO. : 00 DATE : 28.01.10</b>
	<b>SHEET : 2 OF 4</b>

The limiting value of voltage at rated frequency under which a motor will successfully start and accelerate to rated speed with load shall be taken to be a constant value as per Data Sheet - A during the starting period of motors.

3.3.3 The following frequency of starts shall apply

- i) Two starts in succession with the motor being initially at a temperature not exceeding the rated load temperature.
- ii) Three equally spread starts in an hour the motor being initially at a temperature not exceeding the rated load operating temperature. (not to be repeated in the second successive hour)
- iii) Motors for coal conveyor and coal crusher application shall be suitable for three consecutive hot starts followed by one hour interval with maximum twenty starts per day and shall be suitable for minimum 20,000 starts during the life time of the motor

3.4 **Running Requirements**

3.4.1 Motors shall run satisfactorily at a supply voltage of 75% of rated voltage for 5 minutes with full load without injurious heating to the motor.

3.4.2 Motor shall not stall due to voltage dip in the system causing momentary drop in voltage upto 70% of the rated voltage for duration of 2 secs.

3.5 **Stress During bus Transfer**

3.5.1 Motors shall withstand the voltage, heavy inrush transient current, mechanical and torque stress developed due to the application of 150% of the rated voltage for at least 1 sec. caused due to vector difference between the motor residual voltage and the incoming supply voltage during occasional auto bus transfer.

3.5.2 Motor and driven equipment shafts shall be adequately sized to satisfactorily withstand transient torque under above condition.

3.6 Maximum noise level measured at distance of 1.0 metres from the outline of motor shall not exceed the values specified in IS 12065.

3.7 The max. vibration velocity or double amplitude of motors vibration as measured at motor bearings shall be within the limits specified in IS: 12075.

4.0 **CONSTRUCTIONAL FEATURES**

4.1 Indoor motors shall conform to degree of protection IP: 54 as per IS: 4691. Outdoor or semi-indoor motors shall conform to degree of protection IP: 55 as per IS: 4691 and shall be of weather-proof construction. Outdoor motors shall be installed under a suitable canopy

4.2 Motors upto 160KW shall have Totally Enclosed Fan Cooled (TEFC) enclosures, the method of cooling conforming to IC-0141 or IC-0151 of IS: 6362.

Motors rated above 160 KW shall be Closed Air Circuit Air (CACA) cooled

4.3 Motors shall be designed with cooling fans suitable for both directions of rotation.

<b>TITLE :</b> <b>GENERAL TECHNICAL REQUIREMENTS</b>  <b>FOR</b>  <b>LV MOTORS</b>	SPECIFICATION NO. PE-SS-999-506-E101
	VOLUME NO. : <b>II-B</b>
	SECTION : <b>D</b>
	REV NO. : <b>00</b> DATE : 28.01.10
	SHEET : 3 OF 4

- 4.4. Motors shall not be provided with any electric or pneumatic operated external fan for cooling the motors.
- 4.5. Frames shall be designed to avoid collection of moisture and all enclosures shall be provided with facility for drainage at the lowest point.
- 4.6. In case Class 'F' insulation is provided for LV motors, temperature rise shall be limited to the limits applicable to Class 'B' insulation.  
In case of continuous operation at extreme voltage limits the temperature limits specified in table-1 of IS:325 shall not exceed by more than 10°C.
- 4.7. **Terminals and Terminal Boxes**
- 4.7.1 Terminals, terminal leads, terminal boxes, windings tails and associated equipment shall be suitable for connection to a supply system having a short circuit level, specified in the Data Sheet-A.  
  
Unless otherwise stated in Data Sheet-A, motors of rating 110 kW and above will be controlled by circuit breaker and below 110 kW by switch fuse-contactor. The terminal box of motors shall be designed for the fault current mentioned in data sheet "A".
- 4.7.2 Unless otherwise specified or approved, phase terminal boxes of horizontal motors shall be positioned on the left hand side of the motor when viewed from the non-driving end.
- 4.7.3 Connections shall be such that when the supply leads R, Y & B are connected to motor terminals A B & C or U, V & W respectively, motor shall rotate in an anticlockwise direction when viewed from the non-driving end. Where such motors require clockwise rotation, the supply leads R, Y, B will be connected to motor terminals A, C, B or V W & V respectively.
- 4.7.4 Permanently attached diagram and instruction plate made preferably of stainless steel shall be mounted inside terminal box cover giving the connection diagram for the desired direction of rotation and reverse rotation.
- 4.7.5 Motor terminals and terminal leads shall be fully insulated with no bare live parts. Adequate space shall be available inside the terminal box so that no difficulty is encountered for terminating the cable specified in Data Sheet-A.
- 4.7.6 Degree of protection for terminal boxes shall be IP 55 as per IS 4691.
- 4.7.7 Separate terminal boxes shall be provided for space heaters.. If this is not possible in case of LV motors, the space heater terminals shall be adequately segregated from the main terminals in the main terminal box. Detachable gland plates with double compression brass glands shall be provided in terminal boxes.
- 4.7.8. Phase terminal boxes shall be suitable for 360 degree of rotation in steps of 90 degree for LV motors.
- 4.7.9 Cable glands and cable lugs as per cable sizes specified in Data Sheet-A shall be included. Cable lugs shall be of tinned Copper, crimping type.
- 4.8 Two separate earthing terminals suitable for connecting G.I. or MS strip grounding conductor of size given in Data Sheet-A shall be provided on opposite sides of motor frame. Each terminal box shall have a grounding terminal.

<b>TITLE :</b> <b>GENERAL TECHNICAL REQUIREMENTS</b>  <b>FOR</b>  <b>LV MOTORS</b>	SPECIFICATION NO. PE-SS-999-506-E101
	VOLUME NO. : <b>II-B</b>
	SECTION : <b>D</b>
	REV NO. : <b>00</b> DATE : 28.01.10
	SHEET : 4 OF 4

**4.9 General**

- 4.9.1 Motors provided for similar drives shall be interchangeable.
- 4.9.2 Suitable foundation bolts are to be supplied alongwith the motors.
- 4.9.3 Motors shall be provided with eye bolts, or other means to facilitate safe lifting if the weight is 20Kgs. and above.
- 4.9.4 Necessary fitments and accessories shall be provided on motors in accordance with the latest Indian Electricity rules 1956.
- 4.9.5 All motors rated above 30 kW shall be provided with space heaters to maintain the motor internal air temperature above the dew point. Unless otherwise specified, space heaters shall be suitable for a supply of 240V AC, single phase, 50 Hz.
- 4.9.6 Name plate with all particulars as per IS: 325 shall be provided
- 4.9.7 Unless otherwise specified, the colour of finish shall be grey to Shade No. 631 and 632 as per IS:5 for motors installed indoor and outdoor respectively. The paint shall be epoxy based and shall be suitable for withstanding specified site conditions.

**5.0 INSPECTION AND TESTING**


- 5.1 All materials, components and equipments covered under this specification shall be procured, manufactured, as per the BHEL standard quality plan No. PED-506-00-Q-006/0 and PED-506-00-Q-007/2 enclosed with this specification and which shall be complied.
- 5.2 LV motors of type-tested design shall be provided. Valid type test reports not more than 5 year shall be furnished. In the absence of these, type tests shall have to be conducted by manufacturer without any commercial implication to purchaser.
- 5.3 All motors shall be subjected to routine tests as per IS: 325 and as per BHEL standard quality plan.
- 5.4 Motors shall also be subjected to additional tests, if any, as mentioned in Data Sheet A.


**6.0 DRAWINGS TO BE SUBMITTED AFTER AWARD OF CONTRACT**


- a) OGA drawing showing the position of terminal boxes, earthing connections etc.
- b) Arrangement drawing of terminal boxes.
- c) Characteristic curves:  
*(To be given for motor above 55 kW unless otherwise specified in Data Sheet).*
  - i) Current vs. time at rated voltage and minimum starting voltage.
  - ii) Speed vs. time at rated voltage and minimum starting voltage.
  - iii) Torque vs. speed at rated voltage and minimum voltage.  
For the motors with solid coupling the above curves i), ii), iii) to be furnished for the motors coupled with driven equipment. In case motor is coupled with mechanical equipment by fluid coupling, the above curves shall be furnished with and without coupling.
  - iv) Thermal withstand curve under hot and cold conditions at rated voltage and max. permissible voltage.


SUB-SECTION – B-09

**MOTORS**

CLAUSE NO.	TECHNICAL REQUIREMENTS															
<p><b>1.00.00</b></p> <p>1.01.00</p> <p>1.02.00</p> <p>1.03.00</p> <p>1.04.00</p> <p>1.05.00</p> <p>1.06.00</p> <p>1.07.00</p> <p>1.08.00</p>	<p><b>GENERAL REQUIREMENTS</b></p> <p>For the purpose of design of equipment/systems, an ambient temperature of 50 deg. Centigrade and relative humidity of 95% (at 40 deg C) shall be considered. The equipment shall operate in a highly polluted environment.</p> <p>All equipments shall be suitable for rated frequency of 50 Hz with a variation of +3% &amp; -5%, and 10% combined variation of voltage and frequency unless specifically brought out in the specification.</p> <p>Contractor shall provide fully compatible electrical system, equipments, accessories and services.</p> <p>All the equipment, material and systems shall, in general, conform to the latest edition of relevant National and international Codes &amp; Standards, especially the Indian Statutory Regulations.</p> <p>The auxiliary AC voltage supply arrangement shall have 11kV, 3.3 kV and 415V systems. It shall be designed to limit voltage variations as given below under worst operating condition :</p> <table border="0" data-bbox="416 1010 957 1108"> <tr> <td>(a) 11kV, 3.3 kV</td> <td style="text-align: right;">+/- 6%</td> </tr> <tr> <td>(b) 415/240V</td> <td style="text-align: right;">+/- 10%</td> </tr> </table> <p>The voltage level for motors shall be as follows :-</p> <table border="0" data-bbox="416 1200 1382 1422"> <tr> <td>a) Upto 0.2KW</td> <td style="text-align: right;">: Single phase 240V AC / 3 phase 415V AC</td> </tr> <tr> <td>b) Above 0.2KW and upto 200KW</td> <td style="text-align: right;">: 3 phase 415V AC</td> </tr> <tr> <td>c) Above 200KW and upto 1500 KW</td> <td style="text-align: right;">: 3.3 kV</td> </tr> <tr> <td>d) Above 1500 KW</td> <td style="text-align: right;">: 11 kV</td> </tr> </table> <p>Voltage rating for special purpose motors viz. screw compressors and those with VFD shall be as per manufacturer standard.</p> <p>For CHP conveyor's motor above 160KW rating 3.3KV, three phase AC supply is to be used. However all the motors on the Stacker/ Reclaimer machine shall be on 415V AC only.</p> <p>Fault level shall be limited to 40kA RMS for 1 second for 11kV &amp; 3.3 kV system and 45 kA RMS 1 second for 415V system. 415V system shall be solidly grounded and 220 VDC system shall be isolated type.</p> <p>Paint shade shall be as per RAL 5012 (Blue) for indoor and outdoor equipment.</p>			(a) 11kV, 3.3 kV	+/- 6%	(b) 415/240V	+/- 10%	a) Upto 0.2KW	: Single phase 240V AC / 3 phase 415V AC	b) Above 0.2KW and upto 200KW	: 3 phase 415V AC	c) Above 200KW and upto 1500 KW	: 3.3 kV	d) Above 1500 KW	: 11 kV	
(a) 11kV, 3.3 kV	+/- 6%															
(b) 415/240V	+/- 10%															
a) Upto 0.2KW	: Single phase 240V AC / 3 phase 415V AC															
b) Above 0.2KW and upto 200KW	: 3 phase 415V AC															
c) Above 200KW and upto 1500 KW	: 3.3 kV															
d) Above 1500 KW	: 11 kV															
<p>SINGRAULI STPP STAGE-III (1X500 MW) EPC PACKAGE</p>	<p>TECHNICAL SPECIFICATION SECTION - VI PART-B</p>	<p>SUB-SECTION-B-09 MOTORS</p>	<p>PAGE 1 OF 9</p>													


CLAUSE NO.	TECHNICAL REQUIREMENTS			
1.09.00	The responsibility of coordination with electrical agencies and obtaining all necessary clearances shall be of the contractor.			
1.10.00	Degree of Protection  Degree of protection for various enclosures as per IS:4691, IEC60034-05 shall be as follows :-  i) Indoor motors - IP 54 ii) Outdoor motors - IP 55 iii) Cable box-indoor area - IP 54 iv) Cable box-Outdoor area - IP 55			
<b>2.00.00</b>	<b>CODES AND STANDARDS</b>  1) Three phase induction motors : IS:325, IEC:60034 2) Single phase AC motors : IS:996, IEC:60034 3) Crane duty motors : IS:3177, IEC:60034 4) DC motors/generators : IS:4722 5) Energy Efficient motors : IS:12615 or IEC:60034-30			
<b>3.00.00</b>	<b>TYPE</b>			
3.01.00	<b>AC Motors:</b>  a) Squirrel cage induction motor suitable for direct-on-line starting.  b) Continuous duty LT motors upto 160 KW Output rating (at 50 deg.C ambient temperature), shall be Energy Efficient motors, Efficiency class-Eff 1, conforming to IS 12615 or high efficiency (IE2) as per IEC:60034-30  c) Crane duty motors shall be slip ring/ squirrel cage Induction motor as per the requirement.			
3.02.00	DC Motors Shunt wound.			
<b>4.00.00</b>	<b>RATING</b>  (a) Continuously rated (S1). However, crane motors shall be rated for S4 duty, 40% cyclic duration factor.  (b) Whenever the basis for motor ratings are not specified in the corresponding mechanical specification sub-sections, maximum continuous motor ratings			
SINGRAULI STPP STAGE-III (1X500 MW) EPC PACKAGE	TECHNICAL SPECIFICATION SECTION - VI PART-B	SUB-SECTION-B-09 MOTORS	PAGE 2 OF 9	


CLAUSE NO.	TECHNICAL REQUIREMENTS			
<p><b>5.00.00</b></p>	<p>shall be at least 10% above the maximum load demand of the driven equipment under entire operating range including voltage and frequency variations.</p> <p>(c) For BFP motor the starting MVA shall be restricted to 58 MVA.</p> <p><b>TEMPERATURE RISE</b></p> <p><b>Air cooled motors</b></p> <p>70 deg. C by resistance method for both thermal class 130(B) &amp; 155(F) insulation.</p> <p><b>Water cooled</b></p> <p>80 deg. C over inlet cooling water temperature mentioned elsewhere, by resistance method for both thermal class 130(B) &amp; 155(F) insulation.</p> <p>41 deg.C over inlet cooling water maximum temperature of 39 deg.C for thermal class Y wet wound Boiler circulation pump motor.</p>			
<p><b>6.00.00</b></p>	<p><b>OPERATIONAL REQUIREMENTS</b></p>			
<p>6.01.00</p>	<p><b>Starting Time</b></p>			
<p>6.01.01</p>	<p>For motors with starting time upto 20 secs. at minimum permissible voltage during starting, the locked rotor withstand time under hot condition at highest voltage limit shall be at least 2.5 secs. more than starting time.</p>			
<p>6.01.02</p>	<p>For motors with starting time more than 20 secs. and upto 45 secs. at minimum permissible voltage during starting, the locked rotor withstand time under hot condition at highest voltage limit shall be at least 5 secs. more than starting time.</p>			
<p>6.01.03</p>	<p>For motors with starting time more than 45 secs. at minimum permissible voltage during starting, the locked rotor withstand time under hot condition at highest voltage limit shall be more than starting time by at least 10% of the starting time.</p>			
<p>6.01.04</p>	<p>Speed switches mounted on the motor shaft shall be provided in cases where above requirements are not met.</p>			
<p>6.02.00</p>	<p><b>Torque Requirements</b></p>			
<p>6.02.01</p>	<p>Accelerating torque at any speed with the lowest permissible starting voltage shall be at least 10% motor full load torque.</p>			
<p>6.02.02</p>	<p>Pull out torque at rated voltage shall not be less than 205% of full load torque. It shall be 275% for crane duty motors.</p>			
<p>SINGRAULI STPP STAGE-III (1X500 MW) EPC PACKAGE</p>	<p>TECHNICAL SPECIFICATION SECTION - VI PART-B</p>	<p>SUB-SECTION-B-09 MOTORS</p>	<p>PAGE 3 OF 9</p>	


CLAUSE NO.	TECHNICAL REQUIREMENTS			
6.03.00	<p><b>Starting voltage requirement</b></p> <p>a) 85% below 110 KW  b) 80% from 110 KW to 200 KW  c) 85% above 200 KW to 1000 KW  d) 80% from 1001 KW to 4000 KW  e) 75% &gt; 4000 KW</p>			
7.00.00	<p><b>DESIGN AND CONSTRUCTIONAL FEATURES</b></p>			
7.01.00	<p>Suitable single phase space heaters shall be provided on motors rated 30KW and above to maintain windings in dry condition when motor is standstill. Separate terminal box for space heaters &amp; RTDs shall be provided. However for flame proof motors , space heater terminals inside the main terminal box may be acceptable.</p>			
7.02.00	<p>All motors shall be either Totally enclosed fan cooled (TEFC) or totally enclosed tube ventilated (TETV) or Closed air circuit air cooled (CACA) type. However, motors rated 3000KW or above can be Closed air circuit water cooled (CACW). CW motors can be screen protected drip proof (SPDP) type. Motors located in hazardous areas shall have flame proof enclosures conforming to IS:2148 as detailed below</p> <p>(a) Fuel oil area : Group – IIB</p> <p>(b) Hydrogen generation plant area : Group - IIC (or Group-I, Div-II as per NEC)</p>			
7.03.00	<p>Winding and Insulation</p> <p>(a) Type : Non-hygroscopic, oil resistant, flame resistant</p> <p>(b) Starting duty : Two hot starts in succession, with motor initially at normal running temperature. However the conveyor motor shall be suitable for 3 consecutive hot starts.</p> <p>(c) 11kV &amp; 3.3 kV AC motors : Thermal class 155 (F) insulation. The winding insulation process shall be total Vacuum Pressure Impregnated i.e resin poor method. The lightning Impulse &amp; interturn insulation surge withstand level shall be as per IEC-60034 part-15</p> <p>(d) 240VAC, 415V AC &amp; 220V DC motors : Thermal Class( B ) or better</p>			
7.04.00	<p>Motors rated above 1000KW shall have insulated bearings to prevent flow of shaft currents.</p>			
<p>SINGRAULI STPP STAGE-III (1X500 MW) EPC PACKAGE</p>	<p>TECHNICAL SPECIFICATION SECTION - VI PART-B</p>	<p>SUB-SECTION-B-09 MOTORS</p>	<p>PAGE 4 OF 9</p>	

CLAUSE NO.	TECHNICAL REQUIREMENTS		
7.05.00	Motors with heat exchangers shall have dial type thermometer with adjustable alarm contacts to indicate inlet and outlet primary air temperature.		
7.06.00	Noise level for all the motors shall be limited to 85dB(A) except for BFP motor for which the maximum limit shall be 90dB(A). Vibration shall be limited within the limits prescribed in IS:12075 / IEC 60034-14 . Motors shall withstand vibrations produced by driven equipment. HT motor bearing housings shall have flat surfaces, in both X and Y directions, suitable for mounting 80mmX80mm vibration pads.		
7.07.00	In HT motors, at least four numbers simplex / two numbers duplex platinum resistance type temperature detectors shall be provided in each phase stator winding. Each bearing of HT motor shall be provided with dial type thermometer with adjustable alarm contact and preferably 2 numbers duplex platinum resistance type temperature detectors.		
7.08.00	Motor body shall have two earthing points on opposite sides.		
7.09.00	HT motors can be offered with either elastimould termination or dust tight phase separated double walled (metallic as well as insulated barrier) cable boxes. In case elastimould terminations are offered, then protective cover and trifurcating sleeves shall also be provided. In case cable box is offered, then Employer shall provide termination kit. Removable gland plates of thickness 3 mm (hot/cold rolled sheet steel) or 4 mm (non magnetic material for single core cables) shall be provided in case of cable boxes.		
7.10.00	The spacing between gland plate & centre of terminal stud shall be as per Table-I.		
7.11.00	All motors shall be so designed that maximum inrush currents and locked rotor and pullout torque developed by them at extreme voltage and frequency variations do not endanger the motor and driven equipment.		
7.12.00	The motors shall be suitable for bus transfer schemes provided on the 11kV, 3.3 kV /415V systems without any injurious effect on its life.		
7.13.00	For motors rated 2000 KW & above, neutral current transformers of PS class shall be provided on each phase in a separate neutral terminal box.		
7.14.00	11kV and 3.3 kV motor Terminal Box shall be suitable for fault level of 750MVA for 0.12 sec and 250 MVA for 0.12 sec respectively. Elastimould termination kit shall be suitable for fault level of 25 KA for 0.17 seconds.		
7.15.00	The size and number of cables (for HT and LT motors) to be intimated to the successful bidder during detailed engineering and the contractor shall provide terminal box suitable for the same.		
8.00.00	The ratio of locked rotor KVA at rated voltage to rated KW shall not exceed the following (without any further tolerance) except for BFP Motor.		
SINGRAULI STPP STAGE-III (1X500 MW) EPC PACKAGE	TECHNICAL SPECIFICATION SECTION - VI PART-B	SUB-SECTION-B-09 MOTORS	PAGE 5 OF 9



CLAUSE NO.	TECHNICAL REQUIREMENTS			
	(a) Upto 110KW : 11.0 (For AOP motor it shall be 8.0) (b) Above 110KW & upto 1500KW : 10.0 (c) Above 1500KW & upto 4000KW : 9.0 (d) Above 4000KW : 6 to 6.5			
9.00.00	CW Motor shall be designed with minimum power factor of 0.8 at design point.			
<b>10.00.00</b>	<b>TYPE TEST</b>			
10.01.00	<b>HT MOTORS</b>			
10.01.01	<p>The contractor shall carry out the type tests as listed in this specification on the equipment to be supplied under this contract. The bidder shall indicate the charges for each of these type tests separately in the relevant schedule of Section - VII- (BPS) and the same shall be considered for the evaluation of the bids. The type tests charges shall be paid only for the test(s) actually conducted successfully under this contract and upon certification by the employer's engineer.</p>			
10.01.02	<p>The type tests shall be carried out in presence of the employer's representative, for which minimum 15 days notice shall be given by the contractor. The contractor shall obtain the employer's approval for the type test procedure before conducting the type test. The type test procedure shall clearly specify the test set-up, instruments to be used, procedure, acceptance norms, recording of different parameters, interval of recording, precautions to be taken etc. for the type test(s) to be carried out.</p>			
10.01.03	<p>In case the contractor has conducted such specified type test(s) within last ten years as on the date of bid opening, he may submit during detailed engineering the type test reports to the owner for waiver of conductance of such test(s). These reports should be for the tests conducted on the equipment similar to those proposed to be supplied under this contract and test(s) should have been either conducted at an independent laboratory or should have been witnessed by a client. The owner reserves the right to waive conducting of any or all the specified type test(s) under this contract. In case type tests are waived, the type test charges shall not be payable to the contractor.</p>			
10.01.04	<p>Further the Contractor shall only submit the reports of the type tests as listed in "LIST OF TESTS FOR WHICH REPORTS HAVE TO BE SUBMITTED" and carried out within last ten years from the date of bid opening. These reports should be for the test conducted on the equipment similar to those proposed to be supplied under this contract and the test(s) should have been either conducted at an independent laboratory or should have been witnessed by a client. However if the contractor is not able to submit report of the type test(s) conducted within last ten years from the date of bid opening, or in the case of type test report(s) are not found to be meeting the specification requirements, the contractor shall conduct all such tests under this</p>			
<b>SINGRAULI STPP STAGE-III (1X500 MW) EPC PACKAGE</b>	<b>TECHNICAL SPECIFICATION SECTION - VI PART-B</b>	<b>SUB-SECTION-B-09 MOTORS</b>	<b>PAGE 6 OF 9</b>	

CLAUSE NO.	TECHNICAL REQUIREMENTS			
10.01.05	<p>contract at no additional cost to the owner either at third party lab or in presence of client/owners representative and submit the reports for approval.</p> <p><b>LIST OF TYPE TESTS TO BE CONDUCTED</b></p> <p><b>The following type tests shall be conducted on each type and rating of HT motor</b></p> <ul style="list-style-type: none"> <li>(a) No load saturation and loss curves upto approximately 115% of rated voltage</li> <li>(b) Measurement of noise at no load.</li> <li>(c) Momentary excess torque test (subject to test bed constraint).</li> <li>(d) Full load test(subject to test bed constraint)</li> <li>(e) Temperature rise test at rated conditions. During heat run test, bearing temp., winding temp., coolant flow and its temp. shall also be measured. In case the temperature rise test is carried at load other than rated load, specific approval for the test method and procedure is required to be obtained. Wherever ETD's are provided, the temperature shall be measured by ETD's also for the record purpose.</li> <li>(f) Lightning Impulse withstand test on the sample coil shall be as per IEC-60034, part-15</li> <li>(g) Surge-withstand test on interturn insulation shall be as per clause no. 5.1.2 of IEC 60034, part-15</li> </ul>			
10.01.06	<p><b>LIST OF TESTS FOR WHICH REPORTS HAVE TO BE SUBMITTED</b></p> <p>The following type test reports shall be submitted for each type and rating of HT motor</p> <ul style="list-style-type: none"> <li>(a) Degree of protection test for the enclosure followed by IR, HV and no load run test.</li> <li>(b) Terminal box-fault level withstand test for each type of terminal box of HT motors only.</li> </ul>			
10.02.00	<p><b>LT Motors</b></p>			
10.02.01	<p>LT Motors supplied shall be of type tested design. During detailed engineering, the contractor shall submit for Owner's approval the reports of all the type tests as listed in this specification and carried out within last <i>ten</i> years from the date of bid opening.</p>			
<p>SINGRAULI STPP STAGE-III (1X500 MW) EPC PACKAGE</p>	<p>TECHNICAL SPECIFICATION SECTION - VI PART-B</p>	<p>SUB-SECTION-B-09 MOTORS</p>	<p>PAGE 7 OF 9</p>	

CLAUSE NO.	TECHNICAL REQUIREMENTS			
<p>10.02.02</p> <p>10.02.03</p> <p>10.03.00</p> <p>10.04.00</p>	<p>These reports should be for the test conducted on the equipment similar to those proposed to be supplied under this contract and the test(s) should have been either conducted at an independent laboratory or should have been witnessed by a client.</p> <p>However if the contractor is not able to submit report of the type test(s) conducted within last ten years from the date of bid opening, or in the case of type test report(s) are not found to be meeting the specification requirements, the contractor shall conduct all such tests under this contract at no additional cost to the owner either at third party lab or in presence of client/owners representative and submit the reports for approval.</p> <p><b>LIST OF TESTS FOR WHICH REPORTS HAVE TO BE SUBMITTED</b></p> <p><b>The following type test reports shall be submitted for each type and rating of LT motor of above 50 KW only</b></p> <ol style="list-style-type: none"> <li>1. Measurement of resistance of windings of stator and wound rotor.</li> <li>2. No load test at rated voltage to determine input current power and speed</li> <li>3. Open circuit voltage ratio of wound rotor motors ( in case of Slip ring motors)</li> <li>4. Full load test to determine efficiency power factor and slip .</li> <li>5. Temperature rise test .</li> <li>6. Momentary excess torque test.</li> <li>7. High voltage test .</li> <li>8. Test for vibration severity of motor.</li> <li>9. Test for noise levels of motor(Shall be limited as per clause no 7.06.00 of this section)</li> <li>10. Test for degree of protection and</li> <li>11. Overspeed test.</li> </ol> <p>All acceptance and routine tests as per the specification and relevant standards shall be carried out. Charges for these shall be deemed to be included in the equipment price.</p> <p>The type test reports once approved for any projects shall be treated as reference. For subsequent projects of NTPC, an endorsement sheet will be furnished by the manufacturer confirming similarity and “No design Change”. Minor changes if any shall be highlighted on the endorsement sheet.</p>			
<p>SINGRAULI STPP STAGE-III (1X500 MW) EPC PACKAGE</p>	<p>TECHNICAL SPECIFICATION SECTION - VI PART-B</p>	<p>SUB-SECTION-B-09 MOTORS</p>	<p>PAGE 8 OF 9</p>	

**TABLE - I**

**DIMENSIONS OF TERMINAL BOXES FOR LV MOTORS**

<b>Motor MCR in KW</b>	<b>Minimum distance between centre of stud and gland plate in mm</b>
<b>UP to 3 KW</b>	<b>As per manufacturer's practice.</b>

Above 3 KW - upto 7 KW	85
Above 7 KW - upto 13 KW	115
Above 13 KW - upto 24 KW	167
Above 24 KW - upto 37 KW	196
Above 37 KW - upto 55 KW	249
Above 55 KW - upto 90 KW	277
Above 90 KW - upto 125 KW	331
Above 125 KW-upto 200 KW	203

For HT motors the distance between gland plate and the terminal studs shall not be less than 500 mm.

**PHASE TO PHASE/ PHASE TO EARTH AIR CLEARANCE:**

NOTE: Minimum inter-phase and phase-earth air clearances for LT motors with lugs installed shall be as follows:

<b>Motor MCR in KW</b>	<b>Clearance</b>
UP to 110 KW	10mm
Above 110 KW and upto 150 KW	12.5mm
Above 150 KW	19mm

		QUALITY PLAN		CUSTOMER :			PROJECT TITLE		SPECIFICATION : NUMBER :			
		SHEET 1 OF 9		BIDDER/ VENDOR :			QUALITY PLAN NUMBER PED-506-00-Q-007, REV-03		SPECIFICATION : TITLE			
				SYSTEM			ITEM: AC ELECT. MOTORS 55 KW & ABOVE (LV & MV)		SECTION VOLUME III			
SL. NO.	COMPONENT/OPERATION	CHARACTERISTIC CHECK	CAT.	TYPE/METHOD OF CHECK	EXTENT OF CHECK	REFERENCE DOCUMENT	ACCEPTANCE NORM	FORMAT OF RECORD	AGENCY			REMARKS
									P	W	V	
1	2	3	4	5	6	7	8	9	10			11
1.0	RAW MATERIAL & BOUGHT OUT CONTROL											
1.1	SHEET STEEL, PLATES, SECTION, EYEBOLTS	1.SURFACE CONDITION	MA	VISUAL	100%	-	FREE FROM BLINKS, CRACKS, WAVINESS ETC	LOG BOOK	3	-	-	
		2.DIMENSIONS	MA	MEASUREMENT	SAMPLE	MANFR'S DRG./SPEC	MANFR'S DRG./SPEC	-DO-	3	-	-	
		3.PROOF LOAD TEST (EYE BOLT)	MA	MECH. TEST	-DO-	-DO-	-DO-	INSPEC. REPORT	3	-	2	
1.2	HARDWARES	1.SURFACE CONDITION	MA	VISUAL	100%		FREE FROM CRACKS, UN-EVENNESS ETC.	-DO-	3	-	-	
		2.PROPERTY CLASS	MA	VISUAL	SAMPLES	MANFR'S DRG./SPEC BOOK	RELEVANT IS/SPEC.	SUPPLIERS TC & LOG	3	-	2	PROPERTY CLASS MARKING SHALL BE CHECKED BY THE VENDOR
1.3	CASTING	1.SURFACE CONDITION	MA	VISUAL	100%		FREE FROM CRACKS, BLOW HOLES ETC.	LOG BOOK	3	-	2	
		2.CHEM. & PHY. PROP.	MA	CHEM & MECH TEST	1/HEAT NO.	MANFR'S DRG./SPEC	RELEVANT IS/	SUPPLIER'S TC	3	-	2	HEAT NO. SHALL BE VERIFIED
		3.DIMENSIONS	MA	MEASUREMENT	100%	MANUFR'S DRG.	MANUFR'S DRG.	LOG BOOK	3	-	2	
1.4	PAINT & VARNISH	1.MAKE, SHADE, SHELF LIFE & TYPE	MA	VISUAL	100% CONTINUOUS	MANFR'S DRG./SPEC	MANFR'S DRG./SPEC	LOG BOOK	3	-	2	
BHEL			PARTICULARS			BIDDER/VENDOR						
			NAME									
			SIGNATURE									
			DATE						BIDDER'S/VENDORS COMPANY SEAL			



**QUALITY PLAN**

SHEET 2 OF 9

CUSTOMER :

PROJECT  
TITLE

SPECIFICATION :  
NUMBER :

BIDDER/  
VENDOR

QUALITY PLAN  
NUMBER PED-506-00-Q-007, REV-03

SPECIFICATION :  
TITLE

SYSTEM

ITEM: AC ELECT. MOTORS 55 KW & ABOVE (LV & MV)

SECTION

VOLUME III

SL. NO.	COMPONENT/OPERATION	CHARACTERISTIC CHECK	CAT.	TYPE/METHOD OF CHECK	EXTENT OF CHECK	REFERENCE DOCUMENT	ACCEPTANCE NORM	FORMAT OF RECORD	AGENCY			REMARKS
									P	W	V	
1	2	3	4	5	6	7	8	9	10			11
1.5	SHAFT (FORGED OR ROLLED)	1. SURFACE COND.	MA	VISUAL	100%	-	FREE FROM VISUAL DEFECTS	-DO-	3	-	-	VENDOR'S APPROVAL IDENTIFICATION SHALL BE MAINTAINED
		2. CHEM. & PHYSICAL PROPERTIES	MA	CHEM. & PHYSICAL TESTS	1/HEAT NO. OR HEAT TREATMENT BATCH NO	MFG. DRG. SPEC.	RELEVANT IS	SUPPLIER'S TC	3	-	2	
		3. DIMENSIONS	MA	MEASUREMENT	100%	-DO-	MANUFR'S DRG.	LOG BOOK	3	-	2	
		4. INTERNAL FLAWS	CR	UT	-DO-	ASTM-A388	MANUFR'S SPEC. BHEL SPEC.	-DO-	3	2	1	FOR DIA OF 55 MM & ABOVE
1.6	SPACE HEATERS, CONNECTORS, TERMINAL BLOCKS, CABLES, CABLE LUGS, CARBON BRUSH TEMP. DETECTORS, RTD, BTD'S	1. MAKE & RATING	MA	VISUAL	-DO-	MANUFR'S DRG. SPEC.	MANUFR'S DRG. SPEC.	-DO-	3	-	2	
		2. PHYSICAL COND.	MA	-DO-	-DO-	-	NO PHYS. DAMAGE, NO ELECTRICAL DISCONTINUITY	-DO-	3	-	2	
		3. DIMENSIONS (WHEREVER APPLICABLE)	MA	MEASUREMENT	SAMPLE	MANUFR'S DRG./ SPEC.	MANUFR'S DRG. / SPEC.	-DO-	3	-	2	
		4. PERFORMANCE/ CALIBRATION	MA	TEST	100%	-DO-	-DO-	INSP. REPORT	3	-	2	
<b>BHEL</b>			<b>PARTICULARS</b>		<b>BIDDER/VENDOR</b>							
			<b>NAME</b>									
			<b>SIGNATURE</b>									
			<b>DATE</b>					<b>BIDDER'S/VENDORS COMPANY SEAL</b>				



**QUALITY PLAN**

SHEET 3 OF 9

CUSTOMER :

BIDDER/ VENDOR :

SYSTEM

PROJECT

TITLE

QUALITY PLAN

NUMBER PED-506-00-Q-007, REV-03

ITEM: AC ELECT. MOTORS 55 KW & ABOVE (LV & MV)

SPECIFICATION :

NUMBER :

SPECIFICATION :

TITLE

SECTION

VOLUME III

SL. NO.	COMPONENT/OPERATION	CHARACTERISTIC CHECK	CAT.	TYPE/METHOD OF CHECK	EXTENT OF CHECK	REFERENCE DOCUMENT	ACCEPTANCE NORM	FORMAT OF RECORD	SECTION			REMARKS
									P	W	V	
1	2	3	4	5	6	7	8	9	10			11
1.7	OTHER INSULATING MATERIALS LIKE SLEEVES, BINDINGS CORDS, PAPERS, PRESS BOARDS ETC.	1. SURFACE COND. ETC.  2. OTHER CHARACTERISTICS	MA  MA	VISUAL  TEST	100%  SAMPLE	-  MANUF'S SPEC.	NO VISUAL DEFECTS  MANUF'S SPEC.	INSPT. REPORT  LOG BOOK AND OR SUPPLIER'S TC	3  3	-  -	2  2	
1.8	SHEET STAMPING (PUNCHED)	1. SURFACE COND.  2.DIMENSIONS INCLUDING BURS HEIGHT  3. ACCEPTANCE TESTS	MA  MA  MA	VISUAL  MEASUREMENT  ELECT. & MECH TESTS	100%  SAMPLE  -DO-	-  MANUFR'S DRG. .  MANUF'S SPEC./ RELEVANT IS	NO VISUAL DEFECTS (FREE FROM BURS)  MANUFR'S DRG.  RELEVANT IS	LOG BOOK  -DO-  SUPPLIER'S TC	3  3  3	-  -	-  2  2	FOR MV MOTOR INSULATION/VARNISH THICKNESS SHALL BE MORE THAN THE BURS HEIGHT
1.9	CONDUCTORS	1. SURFACE FINISH  2.ELECT. PROP, & MECH. PROP	MA  MA	VISUAL  ELECT. & MECH.TEST	100%  SAMPLES	-  RELEVANT IS/ BS OR OTHER STANDARDS	FREE FROM VISUAL DEFECTS  RELEVANT IS/ BS OR OTHER STANDARDS	LOG BOOK  SUPPLIERS TC & VENDOR'S INSPN. REPORTS	3*  3	-  -	2*  2	* MOTOR MANUFACTURER TO CONDUCT VISUAL CHECK FOR SURFACE FINISH ON RANDOM BASIS (10% SAMPLE) AT HIS WORKS AND MAINTAIN RECORD FOR VERIFICATION BY BHEL/CUSTOMER.
BHEL			PARTICULARS			BIDDER/VENDOR						
			NAME									
			SIGNATURE									
			DATE						BIDDER'S/VENDORS COMPANY SEAL			



**QUALITY PLAN**

SHEET 4 OF 9

CUSTOMER :

PROJECT

SPECIFICATION :

BIDDER/

TITLE

NUMBER :

VENDOR

QUALITY PLAN

SPECIFICATION :

NUMBER PED-506-00-Q-007, REV-03

TITLE

SYSTEM

ITEM: AC ELECT. MOTORS 55 KW & ABOVE (LV & MV)

SECTION

VOLUME III

SL. NO.	COMPONENT/OPERATION	CHARACTERISTIC CHECK	CAT.	TYPE/METHOD OF CHECK	EXTENT OF CHECK	REFERENCE DOCUMENT	ACCEPTANCE NORM	FORMAT OF RECORD	AGENCY			REMARKS
									P	W	V	
1	2	3	4	5	6	7	8	9	10			11
1.10	BEARINGS	3.DIMENSIONS	MA	MEASUREMENT	-DO-	-DO-	-DO-	Log Book	3	-	2	
		1.MAKE & TYPE	MA	VISUAL	100%	MANFR'S DRG./ APPROVED DATASHEET	MANFR'S DRG./ APPROVED DATASHEET	-DO-	3	-	2	
		2.DIMENSIONS	MA	MEASUREMENT	SAMPLE	BHEL DATA SHEET	BHEL DATA SHEET BEARING MANUF'S CATALOGUES	-DO-	3	-	2	
1.11	SLIP RING (WHEREVER APPLICABLE)	3.SURFACE FINISH	MA	VISUAL	100%	-	FREE FROM VISUAL DEFECTS	-DO-	3	-	2	
		1.SURFACE COND.	MA	VISUAL	100%	-	-DO-	-DO-	3	-	-	
		2.DIMENSIONS	MA	MEASUREMENT	SAMPLE	MANUF'S DRG	MANUF'S DRG	-DO-	3	-	-	
		3.TEMP.WITH-STAND CAPACITY	MA	ELECT.TEST	-DO-	MANUF'S SPEC./ BHEL SPEC.	MANUF'S SPEC./ BHEL SPEC.	-DO-	3	-	2	
1.12	OIL SEALS & GASKETS	4.HV/IR	MA	-DO-	100%	-DO-	-DO-	-DO-	3	-	2	
		1.MATERIAL OF GASKET	MA	VISUAL	100%	MANUF'S DRG/SPECS	MANUF'S DRG./ SPECS.	-DO-	3	-	-	
		2.SURFACE COND.	MA	VISUAL	100%	-	FREE FROM VISUAL DEFECTS	-DO-	3	-	-	
		3.DIMENSIONS	MA	MEASUREMENT	SAMPLE	MANUF'S DRG	MANUF'S DRG	-DO-	3	-	-	
<b>BHEL</b>			<b>PARTICULARS</b>			<b>BIDDER/VENDOR</b>						
			<b>NAME</b>									
			<b>SIGNATURE</b>									
			<b>DATE</b>						<b>BIDDER'S/VENDORS COMPANY SEAL</b>			



**QUALITY PLAN**

SHEET 5 OF 9

CUSTOMER :

PROJECT  
TITLE

SPECIFICATION :  
NUMBER :

BIDDER/  
VENDOR

QUALITY PLAN  
NUMBER PED-506-00-Q-007, REV-03

SPECIFICATION :  
TITLE

SYSTEM

ITEM: AC ELECT. MOTORS 55 KW & ABOVE (LV & MV)

SECTION VOLUME III

SL. NO.	COMPONENT/OPERATION	CHARACTERISTIC CHECK	CAT.	TYPE/METHOD OF CHECK	EXTENT OF CHECK	REFERENCE DOCUMENT	ACCEPTANCE NORM	FORMAT OF RECORD	AGENCY			REMARKS
									P	W	V	
1	2	3	4	5	6	7	8	9	10			11
2.0	IN PROCESS											
2.1	STATOR FRAME WELDING (IN CASE OF FABRICATED STATOR )	1.WORKMANSHIP & CLEANNESS	MA	VISUAL	100%	-DO-	GOOD FINISH	LOG BOOK	3/2	2	-	
		2.DIMENSIONS	MA	MEASUREMENT	-DO-	MANUF'S DRG	MANUF'S DRG	-DO-	2	-	-	
2.2	MACHINING	1.FINISH	MA	VISUAL	100%	-DO-	GOOD FINISH	LOG BOOK	2	-	-	
		2.DIMENSIONS	MA	MEASUREMENT	-DO-	MANUF'S DRG	MANUF'S DRG	-DO-	2	-	-	
		3.SHAFT SURFACE FLOWS	MA	PT	-DO-	RELEVENT SPEC./ ASTM-E165	MANUF'S SPEC./ BHEL SPEC./	-DO-	2	-	1	
2.3	PAINTING	1.SURFACE PREPARATION	MA	VISUAL	100%	MANFR'S SPEC/BHEL SPEC./ RELEVANT STAND	BHEL SPEC. SAME AS COL.7	LOG BOOK	2	-	-	
		2.PAINT THICKNESS (BOTH PRIMER & FINISH COAT)	MA	MEASUREMENT BY ELCOMETER	SAMPLE	-DO-	-DO-	-DO-	2	-	-	
		3.SHADE	MA	VISUAL	-DO-	-DO-	-DO-	Log Book	2	-	-	
		4.ADHESION	MA	CROSS CUTTING & TAPE TEST	-DO-	-DO-	-DO-	Log Book	2	-	-	
BHEL			PARTICULARS		BIDDER/VENDOR							
			NAME									
			SIGNATURE									
			DATE		BIDDER'S/VENDORS COMPANY SEAL							



**QUALITY PLAN**

SHEET 6 OF 9

CUSTOMER :

PROJECT  
TITLE

SPECIFICATION :  
NUMBER :

BIDDER/  
VENDOR

QUALITY PLAN  
NUMBER PED-506-00-Q-007, REV-03

SPECIFICATION :  
TITLE

SYSTEM

ITEM: AC ELECT. MOTORS 55 KW & ABOVE (LV & MV)

SECTION

VOLUME III

SL. NO.	COMPONENT/OPERATION	CHARACTERISTIC CHECK	CAT.	TYPE/METHOD OF CHECK	EXTENT OF CHECK	REFERENCE DOCUMENT	ACCEPTANCE NORM	FORMAT OF RECORD	AGENCY			REMARKS	
									P	W	V		
1	2	3	4	5	6	7	8	9	10			11	
2.4	SHEET STACKING	1.COMPLETENESS	MA	MEASUREMENT	SAMPLE	MANUFR'S SPEC.	MANUFR'S SPEC.	Log Book	2	-	-	(FOR MOTORS OF 2MW AND ABOVE) * ON 10% RANDOM SAMPLE	
		2.COMPRESSION & TIGHTENING	MA	MEASUREMENT	100%	-DO-	-DO-	Log Book	2	-	-		
		3.CORE LOSS & HOTSPOT	MA	ELECT.TEST	-DO-	-DO-	-DO-	Log Book	2	1*	1		
2.5	WINDING	1.COMPLETENESS	CR	VISUAL	100%	MANUFR'S SPEC./BHEL SPEC.	MANUFR'S SPEC./BHEL SPEC.	Log Book	2	-	-		FOR MV MOTOR
		2.CLEANLINESS	CR	-DO-	-DO-	-DO-	-DO-	Log Book	2	-	-		
		3.IR-HV-IR	CR	ELECT. TEST	-DO-	-DO-	-DO-	Log Book	2	-	1		
		4.RESISTANCE	CR	-DO-	-DO-	-DO-	-DO-	Log Book	2	-	1		
		5.INTERTURN INSULATION	CR	-DO-	-DO-	-DO-	-DO-	Log Book	2	-	-		
		6.SURGE WITH STAND AND TAN. DELTA TEST	CR	-DO-	-DO-	-DO-	-DO-	Log Book	2	-	1		
2.6	IMPREGNATION	1.VISCOSITY	MA	PHY. TEST	AT STARTING	-DO-	-DO-	Log Book	2	-	-	THREE DIPS TO BE GIVEN	
		2.TEMP. PRESSURE VACCUM	MA	PROCESS CHECK	CONTINUOUS	-DO-	-DO-	Log Book	2	-	-		
		3.NO. OF DIPS	MA	-DO-	-DO-	-DO-	-DO-	Log Book	2	-	1		
<b>BHEL</b>			<b>PARTICULARS</b>		<b>BIDDER/VENDOR</b>								
			<b>NAME</b>										
			<b>SIGNATURE</b>										
			<b>DATE</b>					<b>BIDDER'S/VENDORS COMPANY SEAL</b>					



**QUALITY PLAN**

SHEET 7 OF 9

CUSTOMER :

PROJECT

SPECIFICATION :

BIDDER/

TITLE

NUMBER :

VENDOR

QUALITY PLAN  
NUMBER PED-506-00-Q-007, REV-03

SPECIFICATION :


SYSTEM

ITEM: AC ELECT. MOTORS 55 KW & ABOVE (LV & MV)

SECTION

VOLUME III

SL. NO.	COMPONENT/OPERATION	CHARACTERISTIC CHECK	CAT.	TYPE/METHOD OF CHECK	EXTENT OF CHECK	REFERENCE DOCUMENT	ACCEPTANCE NORM	FORMAT OF RECORD	AGENCY			REMARKS
									P	W	V	
1	2	3	4	5	6	7	8	9	10			11
2.7	COMPLETE STATOR ASSEMBLY	4.DURATION 1.COMPACTNESS & CLEANLINESS	MA	-DO- VISUAL	-DO- 100%	-DO- -DO-	-DO- -DO-	Log Book Log Book	2	-	1	VERIFICATION FOR MV MOTOR ONLY
2.8	BRAZING/COMPRESSION JOINT	1.COMPLETENESS 2.SOUNDNESS	CR	-DO- MALLETT TEST & UT	-DO- -DO-	-DO- -DO-	-DO- -DO-	Log Book Log Book	2	-	-	
2.9	COMPLETE ROTOR ASSEMBLY	3.HV 1.RESIDUAL UNBALANCE	MA	ELECT. TEST	-DO-	-DO-	-DO-	Log Book	2		1	
		2.SOUNDNESS OF DIE CASTING	CR	ELECT. (GROWLER TEST)	-DO-	MFG SPEC./ ISO 1940	MFG. DWG.	Log Book	2		1	
2.10	ASSEMBLY	1.ALIGNMENT	MA	MEAS.	-DO-	-DO-	-DO-	Log Book	2	-	-	
		2.WORKMANSHIP	MA	VISUAL	-DO-	-DO-	-DO-	Log Book	2	-	-	
		3.AXIAL PLAY	MA	MEAS.	-DO-	-DO-	-DO-	Log Book	2	-	1	
		4.DIMENSIONS	MA	-DO-	-DO-	MFG.DRG./ MFG SPEC.	MFG. DRG/ RELEVANT IS	Log Book	2	-	-	
		5.CORRECTNESS, COMPLETENESS TERMINATIONS/ MARKING/ COLOUR CODE	MA	VISUAL	100%	MFG SPEC. RELEVANT IS	MFG SPEC. RELEVANT IS	Log Book	2	-	-	
		6. RTD, BTD & SPACE HEATER MOUNTING.	MA	VISUAL	100%	MFG SPEC. RELEVANT IS	MFG SPEC. RELEVANT IS	Log Book	2		1	
BHEL			PARTICULARS		BIDDER/VENDOR							
			NAME									
			SIGNATURE									
			DATE					BIDDER'S/VENDORS COMPANY SEAL				

		QUALITY PLAN	CUSTOMER :			PROJECT			SPECIFICATION :			
			BIDDER/ VENDOR :			TITLE			NUMBER :			
SHEET 8 OF 9		CHARACTERISTIC CHECK	CAT.	TYPE/ METHOD OF CHECK	EXTENT OF CHECK	REFERENCE DOCUMENT	ACCEPTANCE NORM	FORMAT OF RECORD	SPECIFICATION :			
SL. NO.	COMPONENT/OPERATION								SYSTEM	ITEM: AC ELECT. MOTORS 55 KW & ABOVE (LV & MV)	SECTION	VOLUME III
1	2	3	4	5	6	7	8	9	10			11
P	W	V										
3.0	TESTS	1.TYPE TESTS INCLUDING SPECIAL TESTS AS PER BHEL SPEC.	MA	ELECT.TEST	1/TYPE/SIZE	IS-325/ BHEL SPEC./ DATA SHEET	IS-325/ BHEL SPEC./ DATA SHEET	TEST REPORT	2	1*	1	* NOTE - 1
		2.ROUTINE TESTS INCLUDING SPECIAL TEST AS PER BHEL SPEC.	MA	-DO-	100%	-DO-	-DO-	-DO-	2	1 <sup>s</sup>	1	<sup>s</sup> NOTE - 2
		3.VIBRATION & NOISE LEVEL	MA	-DO-	100%	IS-12075 & IS-12065	IS-12075 & IS-12065	-DO-	2	1 <sup>s</sup>	1	<sup>s</sup> NOTE - 2
		4.OVERALL DIMENSIONS AND ORIENTATION	MA	MEASUREMENT & VISUAL	100%	APPROVED DRG/DATA SHEET	APPROVED DRG/DATA SHEET & RELEVANT IS	INSPC. REPORT	2	1	-	
		5.DEGREE OF PROTECTION	MA	ELECT. & MECH. TEST	1/TYPE/ SIZE	RELEVANT IS	BHEL SPEC. AND DATA SHEET	TC	2	-	1	TC FROM AN INDEPENDENT LABORATORY, REFER NOTE-3
		6. MEASUREMENT OF RESISTANCE OF RTD & BTD	MA	-DO-	100%	-DO-	-DO-	-DO-	2	1 <sup>s</sup>	1	<sup>s</sup> NOTE - 2
		7. MEASUREMENT OF RESISTANCE, IR OF SPACE HEATER	MA	-DO-	100%	-DO-	-DO-	-DO-	2	1 <sup>s</sup>	1	<sup>s</sup> NOTE - 2
		8. NAMEPLATE DETAILS	MA	VISUAL	100%	IS-325 & DATA SHEET	IS-325 & DATA SHEET	INSPC. REPORT	2	1 <sup>s</sup>	1	<sup>s</sup> NOTE - 2
		9.EXPLOSION FLAME PROOF NESS (IF SPECIFIED)	MA	EXPLOSION FLAME PROOF TEST	1/TYPE	IS-3682 IS-8239 IS-8240	IS-3682 IS-8239 IS-8240	TC	2	-	1	TC FROM AN INDEPENDENT LABORATORY, REFER NOTE-3
		10. PAINT SHADE, THICKNESS & FINISH	MA	VISUAL & MEASUREMENT BY ELKOMETER	SAMPLE	BHEL SPEC. & DATA SHEET	BHEL SPEC. & DATA SHEET	TC	2	1 <sup>s</sup>	1	SAMPLING PLAN TO BE DECIDED BY INSPECTION AGENCY <sup>s</sup> NOTE - 2
BHEL			PARTICULARS			BIDDER/VENDOR						
			NAME									
			SIGNATURE									
			DATE						BIDDER'S/VENDORS COMPANY SEAL			



**QUALITY PLAN**

SHEET 9 OF 9

CUSTOMER :

PROJECT  
TITLE

SPECIFICATION :  
NUMBER :

BIDDER/  
VENDOR

QUALITY PLAN  
NUMBER PED-506-00-Q-007, REV-03

SPECIFICATION :  
TITLE

SYSTEM

ITEM: AC ELECT. MOTORS 55 KW & ABOVE (LV & MV)

SECTION VOLUME III

SL. NO.	COMPONENT/OPERATION	CHARACTERISTIC CHECK	CAT.	TYPE/METHOD OF CHECK	EXTENT OF CHECK	REFERENCE DOCUMENT	ACCEPTANCE NORM	FORMAT OF RECORD	AGENCY			REMARKS
									P	W	V	
1	2	3	4	5	6	7	8	9	10			11

NOTES:

- 1 DEPENDING UPON THE SIZE AND CRITICALLY, WITNESSING BY BHEL SHALL BE DECIDED.
- 2 ROUTINE TESTS ON 100% MOTORS SHALL BE DONE BY THE VENDOR. HOWEVER, BHEL SHALL WITNESS ROUTINE TESTS ON RANDOM SAMPLES. THE SAMPLING PLAN SHALL BE MUTUALLY AGREED UPON.
- 3 IN CASE TEST CERTIFICATES FOR THESE TESTS ON SIMILAR TYPE, SIZE AND DESIGN OF MOTOR FROM INDEPENDENT LABORATORY ARE AVAILABLE, THESE TEST MAY NOT BE REPEATED.
- 4 WHEREVER CUSTOMER IS INVOLVED IN INSPECTION, AGENCY (1) SHALL MEAN BHEL AND CUSTOMERS BOTH TOGETHER.


Legends for Inspection agency

1. BHEL/CUSTOMER
2. VENDOR (MOTOR MANUFACTURER)
3. SUB-VENDOR (RAW MATERIAL/COMPONENTS SUPPLIER)

- P. PERFORM  
W. WITNESS  
V. VERIFY

<b>BHEL</b>	<b>PARTICULARS</b>	<b>BIDDER/VENDOR</b>	
	NAME		
	SIGNATURE		
	DATE		BIDDER'S/VENDORS COMPANY SEAL

		QUALITY PLAN		CUSTOMER :			PROJECT			SPECIFICATION :		
				BIDDER/ :			TITLE			NUMBER :		
				VENDOR			QUALITY PLAN			SPECIFICATION		
		SHEET 1 OF 2		SYSTEM			NUMBER PED-506-00-Q-006, REV-01			TITLE		
							ITEM AC ELECT. MOTORS BELOW 55KW (LV)			SECTION		VOLUME III
SL. NO.	COMPONENT/OPERATION	CHARACTERISTICS CHECK	CAT.	TYPE/METHOD OF CHECK	EXTENT OF CHECK	REFERENCE DOCUMENT	ACCEPTANCE NORM	FORMAT OF RECORD	AGENCY			REMARKS
									P	W	V	
1	2	3	4	5	6	7	8	9	10			11
1.0	ASSEMBLY	1.WORKMANSHIP	MA	VISUAL	100%	MANUF'S SPEC	MANUF'S SPEC	-DO-	2	-	-	
		2.DIMENSIONS	MA	-DO-	-DO-	MFG. DRG./ MFG. SPEC.	MFG. DRG./ MFG. SPEC.	-DO-	2	-	-	
		3.CORRECTNESS COMPLETENESS TERMINATIONS/ MARKING/COLOUR CODE	MA	VISUAL	100%	MFG.SPEC./ RELEVANT IS	MFG.SPEC. RELEVANT IS	-DO-	2	-	-	
2.0	PAINTING	1.SHADE	MA	VISUAL	SAMPLE	MANUFR'S SPEC/BHEL SPEC./RELEVANT STANDARD	BHEL SPEC. SAME AS COL.7	LOG BOOK	2	-	-	
3.0	TESTS	1.ROUTINE TEST INCLUDING SPECIAL TEST AS PER BHEL SPEC.	MA	-DO-	100%	IS-325/ BHEL SPEC./ DATA SHEET	SAME AS COL.7	TEST REPORT	2	1		NOTE -1 & NOTE-3
		2.OVERALL DIMENSIONS & ORIENTATION	MA	MEASUREMENT & VISUAL	100%	APPROVED DRG/DATA SHEET	APPROVED DRG/DATA SHEET & RELEVANT IS	INSPN. REPORT	2	1	-	NOTE -1 & NOTE-3
BHEL			PARTICULARS			BIDDER/VENDOR						
			NAME									
			SIGNATURE									

	<b>QUALITY PLAN</b>		CUSTOMER :			PROJECT			SPECIFICATION :			
			BIDDER/ :			TITLE			NUMBER :			
	SHEET 2 OF 2		VENDOR			QUALITY PLAN			SPECIFICATION :			
		SYSTEM			NUMBER PED-506-00-Q-006, REV-01			TITLE :				
					ITEM AC ELECT. MOTORS BELOW 55KW (LV)			SECTION		VOLUME III		
SL. NO.	COMPONENT/OPERATION	CHARACTERISTICS CHECK	CAT.	TYPE/METHOD OF CHECK	EXTENT OF CHECK	REFERENCE DOCUMENT	ACCEPTANCE NORM	FORMAT OF RECORD	AGENCY			REMARKS
									P	W	V	
1	2	3	4	5	6	7	8	9	10			11
		3.NAMEPLATE DETAILS	MA	VISUAL	100%	IS-325 & DATA SHEET	IS-325 & DATA SHEET	INSPN. REPORT	2	1	-	
<p>NOTES:</p> <p>1 ROUTINE TESTS ON 100% MOTORS SHALL BE DONE BY THE VENDOR. HOWEVER, BHEL SHALL WITNESS ROUTINE TESTS ON RANDOM SAMPLES. THE SAMPLING PLAN SHALL BE MUTUALLY AGREED UPON</p> <p>2 WHERE EVER CUSTOMER IS INVOLVED IN INSPECTION, (1) SHALL MEAN BHEL AND CUSTOMERS BOTH TOGETHER.</p> <p>3 FOR EXHAUST/VENTILATION FAN MOTORS OF RATING UPTO 1.5KW , ONLY ROUTINE TEST CERTIFICATES SHALL BE FURNISHED FOR SCRUTINY.</p> <p><u>Legends for Inspection agency</u></p> <p>1. BHEL/CUSTOMER  2. VENDOR (MOTOR MANUFACTURER)  3. SUB-VENDOR (RAW MATERIAL/COMPONENTS SUPPLIER)</p> <p>P. PERFORM  W. WITNESS  V. VERIFY</p>												
BHEL			PARTICULARS			BIDDER/VENDOR						
			NAME									
			SIGNATURE									
			DATE						BIDDER'S/VENDORS COMPANY SEAL			



TITLE : TECHNICAL SPECIFICATION  
FOR  
SELF CLEANING STRAINERS (SCS)

SPEC. NO. PE-TS-401-165-N003

VOLUME : IIB

SECTION : D

REV. NO. 0

DATE : 16.06.14


SHEET 1 of 1

### SECTION D3

## STANDARD TECHNICAL SPECIFICATION FOR C&I SYSTEMS


**SUB-SECTION**  
**CONTROL SYSTEM**

# DCS INTERFACE FOR BIDIRECTIONAL DRIVE(WITH INTEGRAL STARTER)




**NOTE:**

1. DISTURBED= Loss of Power supply (1 Phase/3 Phase),  
Loss of control supply, Motor thermostat trip,  
Thermal over load relay trip,  
Local/Off/Remote Sel. switch in local or off mode.  
Stop PB optd.

	NTPC LIMITED	DRG.NO. PE-DM-401-145-1002
	FEROZ GANDHI UNCHAHAR THERMAL POWER PLANT(1 X 500 MW)	DATE 05.03.2014
TITLE DCS INTERFACE FOR BIDIRECTIONAL DRIVE	REV.NO. 00	SHT 7 OF 13


# DCS INTERFACE FOR UNIDIRECTIONAL LT DRIVE ( CONTACTOR CONTROLLED )



NTPC LIMITED  
 FERDZ GANDHI UNCHAHAR THERMAL POWER PLANT(1 X 500 MW)  
 TITLE DCS INTERFACE FOR UNIDIRECTIONAL LT DRIVE

DRG.NO.	PE-DM-401-145-1002
DATE	05.03.2014
REV.NO.	00
SHT	8 OF 13

# DCS INTERFACE FOR SOLENOID DRIVE (24V DC/240V AC)




**NOTES:**

- \* TWO INDEPENDENT OUTPUTS FROM CONTROL SYSTEM SHALL BE PROVIDED TO PUSH-PULL TYPE VALVES, WITH DUAL COIL SOLENOIDS.
- \*\* MCB SHALL BE PROVIDED FOR EACH SOLENOID
- # FOR ON/OFF TYPE, SOLENOID ACTUATED CONTROL VALVE.



FERDZ GANDHI UNCHAHR THERMAL POWER PLANT(1 X 500 MW)	NTPC LIMITED	DRG.NO. PE-DM-401-145-1002
TITLE	DCS INTERFACE FOR SOLENOID DRIVE	DATE 05.03.2014
REV.NO.	00	SHT 9 OF 13

# DCS INTERFACE FOR UNIDIRECTIONAL HT DRIVE/ LT DRIVE (BREAKER CONTROLLED) HT SWGR (NBPPL SCOPE)



# APPLICABLE FOR FD FANS & PA FANS ONLY

\$ DATA CONCENTRATOR & SERIAL LINK TO MAX STATION SHALL BE COMMON FOR HT/LT DRIVES(BREAKER CONTROLLED)

© APPLICABLE TO SELECTED DRIVES ONLY.

\* REDUNDANCY SHALL BE PROVIDED AS PER CLAUSE 1.01.00, NOTE 12, CONTRACT QUANTITIES FOR DDCMIS, APPENDIX-I TO PART-A OF TECHNICAL SPECIFICATION.

NOTE: 1. EXACT NO. OF PORTS/ LINKS BETWEEN NUMERICAL RELAYS & MAX LINK STATION SHALL BE AS PER THE APPROVED SWGR & DATA CONCENTRATOR DRAWINGS.

2. OVER LOAD ALARM, RELAY FAULT, SWGR AVAILABLE & SWGR DISTURBED SIGNALS ALONG WITH OTHER INFORMATION SHALL FLOW THROUGH SOFT LINK




NTPC LIMITED  
FEROZ GANDHI UNCHAHR THERMAL POWER PLANT(1 X 500 MW)  
TITLE DCS INTERFACE FOR UNIDIRECTIONAL HT DRIVE

DRG.NO.	PE-DM-401-145-1002	DATE	05.03.2014
REV.NO.	00	SHT	10 OF 13

SUB-SECTION


**MEASURING INSTRUMENTS**


CLAUSE NO.	TECHNICAL REQUIREMENTS								
1.00.00	<b>MEASURING INSTRUMENTS (PRIMARY AND SECONDARY)</b>								
1.01.00	Measuring instruments/equipment and subsystems offered by the Bidder shall be from reputed experienced manufacturers of specified type and range of equipment, whose guaranteed and trouble free operation has been proven. Refer Sub-section Basic Design Criteria. Further, all instruments shall be of proven reliability, accuracy, and repeatability requiring a minimum of maintenance and shall comply with the acceptable international standards and shall be subject to Employer's approval.								
1.02.00	Every panel-mounted instrument requiring power supply shall be provided with a pair of easily replaceable glass cartridge fuses of suitable rating. Every instrument shall be provided with a grounding terminal and shall be suitably connected to the panel grounding bus.								
1.03.00	All transmitters, sensors, and switches for parameters like pressure, temperature, level, flow etc. as required for the safe and efficient operation and maintenance as well as for operator and management information (including all computation) of equipment in the system under the scope of specification shall be provided as <del>indicated in the APPENDIX I TO PART A OF TECHNICAL SPECIFICATIONS/</del> tender drawings. Estimated system parameters & instrument ranges etc. are indicated in the I & C device list. The exact value shall be provided by Employer during detailed engineering. The Contractor shall furnish all Instrumentation / Control equipment & accessories under this specification as per technical specification, ranges, makes & model as approved by the Employer during detailed engineering.								
1.04.00	The necessary root valves, impulse piping, drain cocks, gauge-zeroing cocks, valve manifolds and all the other accessories required for mounting/erection of these local instruments shall be furnished, even if not specifically asked for, on as required basis. The contacts of equipment mounted instruments, sensors, switches etc. for external connection including spare contacts shall be wired out in flexible/rigid conduits, independently to suitably located common junction boxes. The proposal shall include the necessary cables, flexible conduits, junction boxes and accessories for the above purpose. Double root valves shall be provided for all pressure tapping where the pressure exceeds 40 Kg./sq.cm.								
1.05.00	<del>The quantity of secondary instruments etc. to be provided by Contractor is listed in Appendix I to Part A of Technical Specifications.</del>								
2.00.00	<b>SPECIFICATION FOR ELECTRONIC TRANSMITTER FOR PRESSURE, D.P., FLOW AND LEVEL</b>  <b>ELECTRONIC TRANSMITTERS</b>  <table border="1" data-bbox="430 1564 1323 1690"> <thead> <tr> <th>Sl.No.</th> <th>Features</th> <th>Essential/Minimum Requirements</th> </tr> </thead> <tbody> <tr> <td>1.</td> <td>Type of Transmitter</td> <td>Microprocessor based 2 wire type, Hart protocol compatible.</td> </tr> </tbody> </table>			Sl.No.	Features	Essential/Minimum Requirements	1.	Type of Transmitter	Microprocessor based 2 wire type, Hart protocol compatible.
Sl.No.	Features	Essential/Minimum Requirements							
1.	Type of Transmitter	Microprocessor based 2 wire type, Hart protocol compatible.							
SINGRAULI STPP STAGE-III (1X500 MW) EPC PACKAGE	TECHNICAL SPECIFICATION SECTION - VI PART-B	SUB-SECTION-C-03(A) MEASURING INSTRUMENTS (PRIMARY & SECONDARY)	PAGE 1 OF 45						




104


08470

CLAUSE NO.	TECHNICAL REQUIREMENTS			
	2.	Accuracy	± 0.1% of calibrated span (minimum) (upto turn down ratio of 10:1)	
	3.	Output signal range	4-20 mA DC (Analog) along with superimposed digital signal (based on HART protocol)	
	4.	Turn down ratio	10:1 for vacuum/very low pressure applications. 5:1 for very high pressure application. 30:1 for other applications.	
	5.	Stability	± 0.1% of calibrated span for six months for Ranges up to and including 70 Kg/cm <sup>2</sup> . ± 0.25% of calibrated span for six months for Ranges more than 70 Kg/cm <sup>2</sup> (g).	
	6.	Zero and span drift	+/- 0.015% per deg.C at max span. +/-0.11% per deg.C at min. Span.	
	7.	Load impedance	500 ohm (min.)	
	8.	Housing	Weather proof as per IP-55 with durable corrosion resistant coating.	
	9.	Over Pressure	150% of max. Operating pressure	
	10.	Connection (Electrical)	Plug and socket type	
	11.	Process connection	1/2 inch NPT (F)	
	12.	Span and Zero	Continuous, tamper proof, Remote as well as adjustability manual from instrument with zero suppression and elevation facility.	
	13.	Accessories	-Diaphragm seal, pulsation dampeners, syphon etc. as required by service and operating condition.  -2 valve manifold for absolute & Gauge pressure transmitters, 3-valve manifold for vacuum pressure transmitters & where DP transmitters are being used for pressure measurement and 5 valve manifold for DP/Level/Flow applicable.  -For hazardous area, explosions proof enclosure as described in NEC article 500.	
SINGRAULI STPP STAGE-III (1X500 MW) EPC PACKAGE	TECHNICAL SPECIFICATION SECTION - VI PART-B	SUB-SECTION-C-03(A) MEASURING INSTRUMENTS (PRIMARY & SECONDARY)	PAGE 2 OF 45	





08471

CLAUSE NO.	TECHNICAL REQUIREMENTS			
2.01.00	14. Diagnostics 15. Power supply 16. Adjustment/calibration/maintenance	Self Indicating feature 24V DC ± 10%. From hand held calibrator/centralized PC based system (as applicable).	<p>Notes</p> <p>For air/flue gas applications, DP type transmitters shall be provided for pressure measurement.</p> <p>LVDT type is not acceptable.</p> <p>Where the process fluids are corrosive, viscous, solid bearing or slurry type, diaphragm seals shall be provided. Parts below the diaphragm shall be removable for cleaning. The entire volume above the diaphragm shall be completely filled with an inert liquid suitable for the application.</p>	
	<p><b>GUIDED WAVE RADAR TYPE LEVEL TRANSMITTER</b></p>			<p>Guided wave radar type level transmitters shall be provided for level measurements of the vessel under vacuum or low pressure applications.</p> <p>Type: Guided wave Radar</p> <p>Principle: TDR (Time domain reflectometry)</p> <p>Probe Type&amp; Material: Coaxial, SS316/316L. If required, probe shall be suitable for overflow prevention.</p> <p>Signal o/p: 4-20mA with HART signal suitable for overflow prevention.</p> <p>Display: Integral</p> <p>Power supply: 24 VDC</p> <p>Accuracy: 5mm</p> <p>Electromagnetic compatibility: Shall meet EN 61326-1 (1997) and AmdtA1, class A equipment/EN 50081-2 &amp; EN 5008 1-2 &amp; EN 50082-2.</p> <p>Mounting: External cage mounting</p> <p>The transmitters shall be provided with IP-55 protection class with durable corrosion resistant coating.</p>
<p>SINGRAULI STPP STAGE-III (1X500 MW) EPC PACKAGE</p>	<p>TECHNICAL SPECIFICATION SECTION - VI PART-B</p>	<p>SUB-SECTION-C-03(A) MEASURING INSTRUMENTS (PRIMARY &amp; SECONDARY)</p>	<p>PAGE 3 OF 45</p>	





08501

<p>CLAUSE NO.</p>	<p>MEASURING INSTRUMENTS (C-03)</p>			
<p>15.00.00</p>	<p>The transmitter shall provide suitable 4-20mA dc output signal for control and indication/recording. Converters if necessary shall be provided to generate the 4-20mA signal.</p> <p>A local indicator of fuel oil flow shall also be provided. The instrument shall be calibrated in Tons/hr.</p> <p>Suitable strainer shall be provided before the transmitter for the protection of oval wheel meters against foreign matter contained in the fuel oil.</p> <p>The exact model no. and type of material being used, etc., shall be subject to Employer's approval during detailed engineering without any price repercussion to Employer.</p>			
<p>15.00.00</p>	<p><b>PROCESS ACTUATED SWITCHES</b></p>			
	<p><b>FEATURES</b></p>	<p><b>ESSENTIAL / MINIMUM REQUIREMENTS</b></p>		
		<p>Pressure/ Draft Switches/ Switches</p>	<p>Temperature DP switches</p>	<p>Level switches</p>
	<p>Sensing Element</p>	<p>Piston actuated for high pressure and diaphragm or bellows for low pr./ vacuum</p>	<p>Vapor pressure sensing, liquid filled bellow type with SS bulb and capillary (10 m minimum)</p>	<p>Capacitance types for oil and dirty medium, water, condensate application. Float type switches for applications as decided by Employer during detailed engineering. Capacitance/ Conductivity/ Ultrasonic type for acid and alkali application. Radio-frequency/ Ultrasonic type for ash hopper, ash slurry application.</p>
	<p>Material</p>	<p>316 SS</p>	<p>Bulb 316 SS/ capillary 304 SS</p>	<p>316 SS</p>
	<p>End connection</p>	<p>½ inch NPT (F)</p>	<p>½ inch NPT (F)</p>	<p>Manufacturer standard</p>
	<p>Over range proof pressure</p>	<p>150% of max. design pr.</p>	<p>-</p>	<p>150% of max. design pressure</p>
<p>SINGRAULI STPP STAGE-III (1X500 MW) EPC PACKAGE</p>	<p>TECHNICAL SPECIFICATION SECTION - VI PART-B</p>	<p>SUB-SECTION-C-03(A) MEASURING INSTRUMENTS (PRIMARY &amp; SECONDARY)</p>	<p>PAGE 33 OF 45</p>	





*Handwritten signature*



08502

CLAUSE NO.	MEASURING INSTRUMENTS (C-03)		
	<p>Repeatability <math>\pm 0.5\%</math> of full range</p> <p>No. of contacts of 2 No.+2NC. SPDT snap action dry contact</p> <p>Rating of contacts 60 V DC, 6 VA (or more if required by DDCMIS)</p> <p>Elect. Connection Plug in socket.</p> <p>Set point/dead band adjustment Provided over full range.</p> <p>Enclosure Weather and dust proof as per IP-55</p> <p>Accessories Siphon, snubber, chemical seal, pulsation dampeners as required by process</p> <p>Mounting Suitable for enclosure/ rack mounting or direct mounting</p> <p>Power Supply 24 V DC, to be arranged by Contractor except for Ash Level Switches, where the same shall be as per Contractor's Standard practice. (wherever required)</p> <p>Where the process fluids are corrosive, viscous, solid bearing or slurry type, diaphragm seals shall be provided. Parts below the diaphragm shall be removable for cleaning. The entire volume above the diaphragm shall be completely filled with an inert liquid suitable for the application.</p>	<p>Thermo well of 316 SS and packing glands</p> <p>All mounting accessories</p> <p>Suitable for rack mounting or direct mounting</p>	
	<p>TECHNICAL SPECIFICATION SECTION - VI PART-B</p>	<p>SUB-SECTION-C-03(A) MEASURING INSTRUMENTS (PRIMARY &amp; SECONDARY)</p>	<p>PAGE 34 OF 45</p>

08503


CLAUSE NO.	MEASURING INSTRUMENTS (C-03)				
16.00.00	SPECIFICATIONS FOR PR. GAUGE, D.P. GAUGE, TEMP. GAUGE AND LEVEL GAUGE.				
	SI. No	FEATURES	ESSENTIAL/MINIMUM REQUIREMENTS		
			Pr. Gauge/ DP Gauge/ Draught gauges	Temperature Gauge	Level Gauge
	1	Sensing Element and material	Bourdon for high pressure, Diaphragm/Bellow for low pr. Of 316 SS	Mercury in steel for below 450°C and inert gas actuated for above 450°C of SS bulb and capillary.	Tempered * toughened Borosilicate gauge glass steel armoured reflex or transparent type.
	2	Body material	Die-cast aluminium	Die-cast aluminium	Forged carbon steel/304 SS
	3	Dial size	150mm	150 mm	Tubular covering entire range
	4	End connection	1/2 inch NPT (M)	3/4" NPT (M)	Process connection as per ASME PTC and drain/vent 15 NB
	5	Accuracy	±1% of span	± 1% of span	± 2%
	6	Scale	Linear, 270° arc graduated in metric units	Linear, 270° arc graduated in °C	Linear vertical
	7	Range selection	Cover 125% of max. of scale	Cover 125% of max. of scale	Cover 125% of max. of scale
	8	Over range test	Test pr. for the assembly shall be 1.5 to the max. Design pr. at 38°C.		
	9	Housing	Weather and dust proof as per IP-55	Weather and dust proof as per IP-55	CS/304 SS leak proof
	10	Zero/span adjustment	Provided	Provided	--
	11	Identification	Engraved with service legend or laminated phenolic name plate		
SINGRAULI STPP STAGE-III (1X500 MW) EPC PACKAGE	TECHNICAL SPECIFICATION SECTION - VI PART-B	SUB-SECTION-C-03(A) MEASURING INSTRUMENTS (PRIMARY & SECONDARY)	PAGE 35 OF 45		



CLAUSE NO.	MEASURING INSTRUMENTS (C-03)		
	12 Accessories  13 Material of Bourdon/ movement	Blow out disc, SS Thermowell siphon, snubber, pulsation dampener, chemical seal (if required by process) gauge isolation valve  of 316 SS / 304 SS / 304 SS	Gasket for all KEL-F shield *for transparent type vent and drain valves of Steel/SS as per CS/Alloy process Requirement.  Notes:-  *Bicolour type level gauges will be provided for applications involving steam and water except for condensate and feed water services.  Length of gauge glass shall not be more than 1400 mm. If the vessel is higher, multiple gauge glasses with 50 mm overlapping shall be provided.  Where the process fluids are corrosive, viscous, solid bearing or slurry type, diaphragm seals shall be provided. Parts below the diaphragm shall be removable for cleaning. The entire volume above the diaphragm shall be completely filled with an inert liquid suitable for the application.
17.00.00	<b>G Related Special Measuring Instrument</b>		
17.01.00	<b>ANALYSER INSTRUMENTS:</b>  Common Requirements  1 Output signals Analog 4-20 mA DC Binary 2 NO + 2 NC for high alarm  2. Zero & span Adjustment Available  3. Ambient temp. 50°C  4. Indication Digital  5. Enclosure Type/Material Weather & Dust proof (IP 55) Die cast Aluminium/SS  6. Type of Electronics Microprocessor based		
 SINGRAULI STPP STAGE-III (1X500 MW) EPC PACKAGE	TECHNICAL SPECIFICATION SECTION - VI PART-B	SUB-SECTION-C-03(A) MEASURING INSTRUMENTS (PRIMARY & SECONDARY)	PAGE 36 OF 45


08565

CLAUSE NO.	TECHNICAL REQUIREMENTS	एनटीपीसी NTPC	
	<p>instrumentation cable shields at same potential. This shall be completed prior to system tests. All the cables etc. required for grounding of all equipments supplied under this package are to be supplied by the Bidder.</p>		
9.07.00	<p>The Contractor shall take full care while laying / installing cables as recommended by cable manufacturers regarding pulling tensions and cable bends. Cables damaged in any way during installation shall be replaced at the expense of the Contractor.</p>		
10.00.00	<p><b>FIELD MOUNTED LOCAL JUNCTION BOXES</b></p> <p>(i) No. of ways 12/24/36/48/64/72/96/128 with 20% spares terminals.</p> <p>(ii) Material and Thickness 4mm thick Fiberglass Reinforced Polyester (FRP).</p> <p>(iii) Type Screwed at all four corners for door. Door gasket shall be of synthetic rubber.</p> <p>(iv) Mounting clamps and accessories Suitable for mounting on walls, columns, structures etc. The brackets, bolts, nuts, screws, glands required for erection shall be of SS, included in Bidders scope of supply.</p> <p>(v) Type of terminal blocks Rail mounted cage-clamp type suitable for conductor size upto 2.5 mm<sup>2</sup>. A M6 earthing stud shall be provided.</p> <p>(vi) Protection Class IP: 55 minimum for indoor &amp; IP-65 minimum for outdoor applications.</p> <p>(vii) Grounding To be provided.</p> <p>(viii) Color To be decided during detailed engineering &amp; subject to Employer's approval.</p>		
11.00.00	<p><b>CONDUITS</b></p>		
11.01.00	<p>Conduits shall be generally used for interconnecting cables from field instruments to Local JB's. All rigid conduits, couplings and elbows shall be hot dipped galvanised rigid mild steel in accordance with IS: 9537 Part-I (1980) and Part-II (1981). The conduit interior and exterior surfaces shall have continuous zinc coating with an overcoat of transparent enamel lacker or zinc chromate. Flexible conduit shall be heat resistant lead coated steel, water leak, fire and rust proof for the following areas:-</p> <p>(i) Mills,</p> <p>(ii) Drum,</p> <p>(iii) Main Steam, RH steam</p>		
SINGRAULI STPP STAGE-III (1X500 MW) EPC PACKAGE	TECHNICAL SPECIFICATION SECTION - VI PART-B	SUB-SECTION-C-06 INSTRUMENTATION POWER SUPPLY CABLE	PAGE 15 OF 17



09944

PRESS. MEASUREMENT




This document is the property of NATIONAL THERMAL POWER CORPORATION LTD. No part of this document will be reproduced by any means without the written permission.

NOTES:-

1. THIS TYPE OF PRESSURE CONNECTION SHALL BE PROVIDED FOR PRESSURE MEASUREMENTS IN AIR AND FLUE GAS DUCT/FURNACE.
2. DIMENSIONS ARE INDICATIVE ONLY.

FOR TENDER PURPOSE ONLY




 एन टी पी सी लिमिटेड <b>NTPC LIMITED</b> <small>( A GOVERNMENT OF INDIA ENTERPRISE )</small> ENGINEERING DIVISION			
PROJECT		TYPICAL THERMAL POWER PROJECT (STATION C&I PACKAGE)	
TITLE		INSTRUMENT SOURCE CONNECTION DETAILS	
REV. NO.	DESCRIPTION	DATE	BY
A	FIRST ISSUE		
SIZE		SCALE	DRG. NO.
A4		N.T.S.	0000-405-POI-A-035
Cleared by		REV. NO.	A
		SH-3 of 14	




This document is the property of NATIONAL THERMAL POWER CORPORATION LTD. No part of this document will be reproduced by any means without the written permission.

**PRESS. MEASUREMENT**




**ELEVATION  
LIQUID SERVICE**



**ELEVATION  
STEAM SERVICE**


**PRESSURE CONNECTION ON HORIZONTAL PIPE**



**ELEVATION  
LIQUID OR STEAM SERVICE**


**PRESSURE CONNECTIONS ON VERTICAL PIPES**

• USE DOUBLE ISOLATION VALVES FOR PRESSURE EQUAL TO OR EXCEEDING 40 Kg/Cm<sup>2</sup> AND TEMP. MORE THAN 280°C.



**FOR TENDER PURPOSE ONLY**

										<p>एन टी पी सी लिमिटेड <b>NTPC LIMITED</b> (A GOVERNMENT OF INDIA ENTERPRISE) ENGINEERING DIVISION</p>				
PROJECT										TYPICAL THERMAL POWER PROJECT (STATION C&I PACKAGE)				
TITLE										INSTRUMENT SOURCE CONNECTION DETAILS				
A FIRST ISSUE										SIZE	A4			
NO.	DESCRIPTION	DRAWN	DESIGN	CHKD.	M	E	C	C&I	PRCH.	APPD.	DATE	SCALE	DWG. NO.	REV. NO.
												N.T.S.	0000-405-POI-A-035	A
Cleared by										Sh-1 of 14				



**LIST OF MATERIALS**

ITEM NO.	DESCRIPTION
1.	4242 TO 3/4" SW REDUCING INSERT.
2.	3/4" SW GLOBE VALVE.
3.	1/2" SW GLOBE VALVE FOR LIQUID APPLICATION & 3/4" 1/2" IN GAS/AIR APPLICATION (AS PER PROCESS REQUIREMENT)
4.	CS/ALLOY/STEEL PIPE
5.	1/2" SW EQUAL TEE
6.	1/2" NPS SW x 1/2" NPT (M) CS NIPPLE.
7.	1/2" NPT (F) CS CAP.
8.	1/2" PIPE x 1/2" PIPE UNION.
9.	5 VALVE MANIFOLD (FOR DETAIL REFER DRAWING NO.0000-405-POI-A-026)
10.	3/4" SCH 80 CARBON/ALLOY STEEL PIPE.
11.	3/4" 1/2" SW EQUAL TEE.
12.	3/4" 1/2" TUBE UNION.
13.	1/2" SCREWED GLOBE VALVE.
14.	1/2" NPT (M) PLUG.
15.	3/4" SW GATE VALVE.
16.	3/4" SW EQUAL CROSS.
17.	WAFER ELEMENT FOR USE WITH 3" ANSI R.F. VALVE.
18.	3" BLIND 300 LB. R.F. WELD NECK FLANGE DRILLED FOR 1" SCH. 40/80 PIPE.
19.	1" BLIND FLANGE.
20.	1" NPS SCH. 40/80 (AS PER PROCESS REQUIREMENT) CS PIPE.
21.	1" SW EQUAL TEE.
22.	3/4" x 1/2" SW REDUCING INSERT.
23.	3/4" SW x 3/4" NPT (M) CS/AS NIPPLE
24.	3/4" NPT (F) CS/AS CAP.
25.	1/4" NPS ALLOY STEEL PIPE.
26.	1" x 3/4" SW REDUCING INSERT.
27.	3/4" SW x 1/2" PSW BRANCH TEE.
28.	3/4" PIPE UNION
29.	1/2" CLAMP UNION (THREADED) SUITABLE FOR FLEXIBLE CONNECTION OF NYLON REINFORCED PVC TUBE.
30.	SS TUBE
31.	3/4" SW 4 WAY VALVE.
32.	QUICK DISCONNECT FITTINGS.
33.	1/4" SW ISOLATION VALVE 316SS
34.	1/2" x 1/2" SS PIPE UNION.

**FOR TENDER PURPOSE ONLY**

NOTES:-  
 1. SAME NOTES AS UNDER DRG. NO. 0000-405-POI-A-023

**NTPC**  
 (A GOVERNMENT OF INDIA ENTERPRISE)  
 ENGINEERING DIVISION

**एन टी सी लिमिटेड**  
**NTPC LIMITED**  
 (A GOVERNMENT OF INDIA ENTERPRISE)  
 ENGINEERING DIVISION


PROJECT: TYPICAL THERMAL POWER PROJECT (STATION C&I PACKAGE)

TITLE: INSTRUMENT INSTALLATION DIAGRAM  
 DIFF. PRESS. MEASUREMENT (LIQUID, OIL, AIR/GAS SERVICE)

SCALE: N.T.S.  
 SIZE: A3  
 DRG. NO.: 0000-405-POI-A-030  
 REV. NO.: A

REV/NO	DESCRIPTION	DATE	APPD	ARCH.	C&I	E	C	CHND.	DESIGN	CHKD.	DATE
A	FIRST ISSUE	28.04.05									

CLEAR BY: \_\_\_\_\_




No part of this document will be reproduced by any means without the written permission.  
 This document is the property of NATIONAL THERMAL POWER CORPORATION LTD.


00931

**LIST OF MATERIALS**


ITEM NO.	DESCRIPTION
1.	1/2" NPS SCH. 80/160 SW 1/2" NPT NIPPLE OF MATERIAL SAME AS THAT OF MAIN PIPE.
2.	3/4" 1" SW GLOBE VALVE.
3.	3/4" 1" TO 1/2" REDUCING INSERT
4.	1/2" NPS PIPE
5.	1/2" SW EQUAL TEE
6.	1/2" SW GLOBE VALVE
7.	1/2" NPS SCH. 80/160 SW 1/2" CS/AS COUPLER
8.	1/2" PIPE UNION
9.	3/8" VALVE W/ADAPTER (FOR DETAIL SEE DRAWING NO. 0000-405-POI-A-023)
10.	SUITABLE ADAPTER
11.	SS. TUBE
12.	1/2" PIPE x 1/2" TUBE UNION
13.	1/2" NPS SCH. 80/160 SW 1/2" NPT(M) CS/AS NIPPLE




**ELEVATION  
TRANSMITTER MOUNTED ABOVE INSTRUMENT SOURCE POINT  
LIQUID PRESSURE MEASUREMENT**




**ELEVATION  
TRANSMITTER MOUNTED ABOVE INSTRUMENT SOURCE POINT  
VACUUM PRESSURE MEASUREMENT**



**ELEVATION  
TRANSMITTER MOUNTED BELOW INSTRUMENT SOURCE POINT  
STEAM PRESSURE MEASUREMENT**



**ELEVATION  
TRANSMITTER MOUNTED BELOW INSTRUMENT SOURCE POINT  
LIQUID PRESSURE MEASUREMENT**




**ELEVATION  
VACUUM PRESSURE MEASUREMENT**

**NOTES:-**

1. SAME NOTES UNDER DRG. NO. 0000-405-POI-A-023.
2. FOR VACUUM APPLICATION OTHER PORT OF TRANSMITTER SHALL BE KEPT OPEN TO ATMOSPHERE.

**FOR TENDER PURPOSE ONLY**



**एन टी पी सी लिमिटेड**  
**NTPC LIMITED**  
 ( A GOVERNMENT OF INDIA ENTERPRISE )  
 ENGINEERING DIVISION

**PROJECT**  
 TYPICAL THERMAL POWER PROJECT  
 (STATION C&I PACKAGE)

**TITLE**  
 INSTRUMENT INSTALLATION DIAGRAM  
 (PRESSURE MEASUREMENT USING PRESS /DP  
 TRANSMITTERS STEAM/LIQUID VACUUM)

SIZE	A3	SCALE	M.T.S.	DRG. NO.	0000-405-POI-A-025	REV. NO.	A
------	----	-------	--------	----------	--------------------	----------	---

REV. NO.	DESCRIPTION	CLEARED BY				DATE	APFD
		M	E	C	ARCH.		
A	FIRST ISSUE					20/04/08	




This document is the property of NATIONAL THERMAL POWER CORPORATION LTD. No part of this document will be reproduced by any means without the written permission.

09930

**LIST OF MATERIALS**

ITEM NO.	DESCRIPTION
1.	1" NPS SCH 40/80 (AS PER PROCESS REQUIREMENT) NIPPLE OF MATERIAL SAME AS THAT OF MAIN PIPE
2.	1" SW GLOBE VALVE
3.	1" x 1/2" SW REDUCING INSERT
4.	1" NPS SCH 40/80 CS PIPE
5.	1" SW EQUAL TEE
6.	1/2" SW GLOBE VALVE
7.	1/2" NPS SCH 40/80 SW x 1/2"NPT (M) CS NIPPLE
8.	1/2" NPT (F) CS CAP.
9.	-
10.	-
11.	1/2" PIPE UNION
12.	-
13.	2/2" BLIND 300# RF ANSI FLANGE DRILLED & TAPPED FOR 1" NPT PIPE
14.	2/2" MATCHING BLIND FLANGE
15.	WAFER ELEMENT FOR USE WITH 2 1/2" ANSI RF FLANGE
16.	SPECIAL LIQUID FILLED 300 SS POLYTHENE JACKETED CAPILLARY TUBE OF PRESSURE TRANSMITTER.
17.	1/4" CHROME MOLY STEEL PIPE.
18.	1/2" NPS SCH. 40/80 CS PIPE.
19.	-
20.	-
21.	-
22.	1/4" SW 316 SS ISOLATION VALVE.





**HEAVY FUEL PRESS. MEASUREMENT USING WAFER TYPE TRANSMITTER WITH REMOTE SEAL**

**NOTES:-**

1. SAME NOTES AS UNDER DRG. NO.0000-405-POI-A-023.
1. FOR LFO STEAM TRACING NOT APPLICABLE.

**FOR TENDER PURPOSE ONLY**

 <b>एन टी पी लिमिटेड</b> <b>NTPC LIMITED</b> (A GOVERNMENT OF INDIA ENTERPRISE) ENGINEERING DIVISION	
<b>PROJECT</b> TYPICAL THERMAL POWER PROJECT (STATION C&I PACKAGE)	
<b>TITLE</b> INSTRUMENT INSTALLATION DIAGRAM (PRESSURE TRANSMITTER FUEL OIL)	
<b>DATE</b> 26/04/08	<b>SCALE</b> N.T.S.
<b>APPD</b> M E C	<b>DRG. NO.</b> 0000-405-POI-A-024
<b>DESIGN</b> CHKO.	<b>REV. NO.</b> A




No part of this document will be reproduced by any means without the written permission of NATIONAL THERMAL POWER CORPORATION LTD.

REV. NO.	DESCRIPTION	DATE	BY	CHKD.	APPD.	DATE
A	FIRST ISSUE					

CLEARED BY

**LIST OF MATERIALS**

ITEM NO.	DESCRIPTION
1.	42 X 405 MM M.S. BLACK PIPE
2.	M222(F) 3/4" REDUCING INSERT
3.	M222(F) M.S. CAP
4.	3/4" SW GLOBE VALVE/GATE VALVE
5.	3/4" NPS PIPE
6.	3/4" NPS SW 3/4" NPT(M) CS/AS NIPPLE
7.	3/4" SW EQUAL TEE
8.	3/4" NPS SCH 80 CARBON/ALLOY STEEL NIPPLE
9.	3/4" NPT(F) CS/AS CAP
10.	3/4" SW CS/AS EQUAL CROSS
11.	1/2" TUBE ADAPTER
12.	3 VALVE MANIFOLD
13.	3/4" PIPE UNION
14.	2 VALVE MANIFOLD
15.	3/4" SW 2 WAY VALVE
16.	QUICK DISCONNECT FITTING
17.	3/4" SW 1/2 SW BRANCH TEE
18.	1/2" NB SEAMLESS GI PIPE
19.	1/2" NPT (F) O FITTING
20.	SS TUBE
21.	FLEXIBLE HOSE WITH ONE END SOCKET WELDED (PIPE SIDE) & OTHER END WITH SUITABLE FITTINGS
22.	3/4" x 1/2" S.S. TUBE UNION



**NOTES:-**

- SEE NOTES UNDER DRG. NO.0000-405-POI-A-022.
- IMPULSE LINE DRAIN CONNECTIONS SHALL BE DONE AS PER TECHNICAL SPECIFICATIONS
- THE SLOPE IN THE HORIZONTAL OF THE IMPULSE PIPE SHALL BE APPROX. 50 mm/mtr.
- THE ORIENTATION OF THE TRANSMITTERS WITH RESPECT TO VALVE MANIFOLDS SHALL BE REVISITED DURING DETAILED ENGINEERING KEEPING IN VIEW THE MANUFACTURER'S RECOMMENDATIONS.
- COMMON INSTRUMENT AIR HEADER (1"NB) USING REDUNDANT AIR FILTER REGULATORS WILL BE MADE IN EACH TRANSMITTER ENCLOSURE. PURGE AIR, PURGE AIR FOR EACH INSTRUMENT LINE SHALL BE TAPPED FROM THIS HEADER. USE OF INDIVIDUAL PURGE ROTAMETERS AS SHOWN IN DRG. NO. 0000-405-POI-A-034 TYPICALLY.

**FOR TENDER PURPOSE ONLY**

**एन टी पी सी लिमिटेड**  
**NTPC LIMITED**  
 (A GOVERNMENT OF INDIA ENTERPRISE)  
 ENGINEERING DIVISION

**PROJECT**  
 TYPICAL THERMAL POWER PROJECT  
 (STATION C&I PACKAGE)

**TITLE**  
 INSTRUMENT INSTALLATION DIAGRAM  
 (PRESSURE MEASUREMENT USING PRESS / DP TRANSMITTERS  
 (INST./SERVICE, DIRTY AIR/FLUE GAS))

**REV. NO.**  
 A

**DRG. NO.**  
 0000-405-POI-A-023

**SCALE**  
 N.T.S.

**SIZE**  
 A3

**DATE**  
 26/04/06

**APPD**  
 [Signature]

**CHKD.**  
 [Signature]

**DESIGN**  
 [Signature]


**ARCH.**  
 [Signature]

**C&I**  
 [Signature]

**E**  
 [Signature]

**M**  
 [Signature]





**CLEARED BY**  
 [Signature]



No part of this document will be reproduced by any means without the written permission. This document is the property of NATIONAL THERMAL POWER CORPORATION LTD.

**LIST OF MATERIALS**

ITEM NO.	DESCRIPTION
1.	1/2" / 3/4" / 1" NPS SCH 40/80/160 XXS/P01 (AS PER PROCESS REQUIREMENT) NIPPLE OF MATERIAL SAME AS THAT OF MAIN PIPE.
2.	1/2" / 3/4" / 1" SW GLOBE VALVE/GATE VALVE
3.	3/4" / 1" x 1/2" SW REDUCING INSERT
4.	1/2" / 3/4" PIPE
5.	1/2" / 3/4" SW EQUAL TEE
6.	1/2" / 3/4" SW GLOBE VALVE.
7.	1/2" / 3/4" NPS SW x 1/2" / 3/4" NPT(M) CARBON/ALLOY STEEL NIPPLE.
8.	1/2" / 3/4" NPT(F) CS CAP.
9.	1/2" / 3/4" PIPE UNION.
10.	6" SS SIPHON
11.	1/2" BLIND 3000# BF ANSI FLANGE DRILLED AND TAPED FOR 1" NPT PIPE.
12.	SUITABLE ADAPTER.
13.	1/4" CHROME MOLY STEEL TUBE.
14.	
15.	1" / 3/4" SW EQUAL TEE.
16.	DAMPFRAG(WATER ELEMENT)
17.	ISOLATION VALVE 316 SS 1/4" SW



**NOTES:-**

- THE MATERIAL SPECIFICATION AND SCHEDULE NO. OF IMPULSE PIPE & NIPPLE AS LISTED HEREIN SHALL BE AS PER TECHNICAL SPECIFICATIONS.
- THE MATERIAL SPECIFICATION AND RATING OF FITTINGS AS LISTED SHALL BE AS PER SPECIFICATIONS. WELDED/FORGED FITTINGS SHALL CONFORM TO ANSI-B.16-11.
- TECHNICAL SPECIFICATIONS OF STEEL MATERIAL AND PRESSURE CLASS SHALL BE AS PER FOR BOILER AIR/FUELS/GAS SERVICES. SOURCE CONNECTIONS IMPULSE PIPING AND ALL FITTINGS SHALL BE OF 3/4" NB SIZE.
- GAUGES SHALL NOT BE MOUNTED ON THE PIPE. IT WILL BE MOUNTED ON A CHANNEL OR FRAME OR A RACK.
- \* SLOPE APPROX. 4D MM / METRE.

**FOR TENDER PURPOSE ONLY**

**एन टी पी सी लिमिटेड**  
**N.T.P.C. LIMITED**  
( A GOVERNMENT OF INDIA ENTERPRISE )  
ENGINEERING DIVISION

**एन टी पी सी लिमिटेड**  
**N.T.P.C. LIMITED**  
( A GOVERNMENT OF INDIA ENTERPRISE )  
ENGINEERING DIVISION

**PROJECT**  
TYPICAL THERMAL POWER PROJECT  
(STATION C&I PACKAGE)

**TITLE**  
INSTRUMENT INSTALLATION DIAGRAM  
(FOR PRESSURE GAUGE)

**SCALE**  
AS

**SIZE**  
A5

**DRG. NO.**  
0000-405-POI-A-022

**REV. NO.**  
A




No part of this document is the property of NATIONAL THERMAL POWER CORPORATION LTD. This document is the property of NATIONAL THERMAL POWER CORPORATION LTD. No part of this document will be reproduced by any means without the written permission.


REV. NO.	DESCRIPTION	DATE	APPD	ARCH.	C&I	ARCH.	CLEARED BY
A	FIRST ISSUE	26.04.06					

**SUB-SECTION**

**CABLING PHILOSOPHY**


08559


CLAUSE NO.	TECHNICAL REQUIREMENTS																																										
5.00.00	<p><del>SPECIFICATION OF POWER SUPPLY CABLES</del></p> <p>Refer Annexure to this Sub-section.</p>																																										
5.00.00	<p><b>INSTRUMENTATION CABLE INTERCONNECTION AND TERMINATION PHILOSOPHY</b></p> <p>The cable interconnection philosophy to be adopted shall be such that extensive grouping of signals by large scale use of field mounted Group Junction Boxes (JBs) at strategic locations (where large concentration of signals are available, e.g. valves limit &amp; torque switches, switchgear) is done and consequently cable with higher number of pairs are extensively used. The details of termination to be followed are mentioned in the given Table A.</p> <p style="text-align: center;"><b>TABLE A: CABLE TERMINATION TO BE FOLLOWED</b></p> <table border="1" data-bbox="451 772 1343 1675"> <thead> <tr> <th colspan="2" data-bbox="451 772 906 829">Application</th> <th colspan="2" data-bbox="906 772 1237 829">Type Of Termination</th> <th data-bbox="1237 772 1343 886" rowspan="2">Type Of Cable</th> </tr> <tr> <th data-bbox="451 829 673 886">FROM (A)</th> <th data-bbox="673 829 906 886">TO (B)</th> <th data-bbox="906 829 1091 886">END A</th> <th data-bbox="1091 829 1237 886">END B</th> </tr> </thead> <tbody> <tr> <td data-bbox="451 886 673 1045">Valves/dampers drives (Integral Junction box)</td> <td data-bbox="673 886 906 1045">Marshalling / Marshalling – cum Termination Cubicle / local group JB</td> <td data-bbox="906 886 1091 1045">Plug in connector</td> <td data-bbox="1091 886 1237 1045">Post mount cage clamp type.</td> <td data-bbox="1237 886 1343 1045">G</td> </tr> <tr> <td data-bbox="451 1045 673 1180">Transmitters, Process Actuated switches mounted in LIE/LIR</td> <td data-bbox="673 1045 906 1180">Integral Junction box of LIE/LIR</td> <td data-bbox="906 1045 1091 1180">Plug in connector</td> <td data-bbox="1091 1045 1237 1180">Cage clamp (Rail mount) type.</td> <td data-bbox="1237 1045 1343 1180">F,G</td> </tr> <tr> <td data-bbox="451 1180 673 1314">RTD heads</td> <td data-bbox="673 1180 906 1314">Local junction box</td> <td data-bbox="906 1180 1091 1314">Plug in connector</td> <td data-bbox="1091 1180 1237 1314">Cage clamp (Rail mount) type.</td> <td data-bbox="1237 1180 1343 1314">F</td> </tr> <tr> <td data-bbox="451 1314 673 1444">Thermocouple</td> <td data-bbox="673 1314 906 1444">Local junction box / CJC box (if applicable)</td> <td data-bbox="906 1314 1091 1444">Plug in connector</td> <td data-bbox="1091 1314 1237 1444">Cage clamp (Rail mount) type.</td> <td data-bbox="1237 1314 1343 1444">A, B, C*</td> </tr> <tr> <td data-bbox="451 1444 673 1575">Other Field mounted Instrument</td> <td data-bbox="673 1444 906 1575">Local JB / Group JB</td> <td data-bbox="906 1444 1091 1575">Plug in connector</td> <td data-bbox="1091 1444 1237 1575">Cage clamp (Rail mount) type.</td> <td data-bbox="1237 1444 1343 1575">F,G</td> </tr> <tr> <td data-bbox="451 1575 673 1675">RTD</td> <td data-bbox="673 1575 906 1675">Temperature transmitter</td> <td data-bbox="906 1575 1091 1675">Plug in connector</td> <td data-bbox="1091 1575 1237 1675">Screwed, Cage clamp type</td> <td data-bbox="1237 1575 1343 1675">F</td> </tr> </tbody> </table>				Application		Type Of Termination		Type Of Cable	FROM (A)	TO (B)	END A	END B	Valves/dampers drives (Integral Junction box)	Marshalling / Marshalling – cum Termination Cubicle / local group JB	Plug in connector	Post mount cage clamp type.	G	Transmitters, Process Actuated switches mounted in LIE/LIR	Integral Junction box of LIE/LIR	Plug in connector	Cage clamp (Rail mount) type.	F,G	RTD heads	Local junction box	Plug in connector	Cage clamp (Rail mount) type.	F	Thermocouple	Local junction box / CJC box (if applicable)	Plug in connector	Cage clamp (Rail mount) type.	A, B, C*	Other Field mounted Instrument	Local JB / Group JB	Plug in connector	Cage clamp (Rail mount) type.	F,G	RTD	Temperature transmitter	Plug in connector	Screwed, Cage clamp type	F
Application		Type Of Termination		Type Of Cable																																							
FROM (A)	TO (B)	END A	END B																																								
Valves/dampers drives (Integral Junction box)	Marshalling / Marshalling – cum Termination Cubicle / local group JB	Plug in connector	Post mount cage clamp type.	G																																							
Transmitters, Process Actuated switches mounted in LIE/LIR	Integral Junction box of LIE/LIR	Plug in connector	Cage clamp (Rail mount) type.	F,G																																							
RTD heads	Local junction box	Plug in connector	Cage clamp (Rail mount) type.	F																																							
Thermocouple	Local junction box / CJC box (if applicable)	Plug in connector	Cage clamp (Rail mount) type.	A, B, C*																																							
Other Field mounted Instrument	Local JB / Group JB	Plug in connector	Cage clamp (Rail mount) type.	F,G																																							
RTD	Temperature transmitter	Plug in connector	Screwed, Cage clamp type	F																																							
SINGRAULI STPP STAGE-III (1X500 MW) EPC PACKAGE	TECHNICAL SPECIFICATION SECTION - VI PART-B	SUB-SECTION-C-06 INSTRUMENTATION POWER SUPPLY CABLE	PAGE 9 OF 17																																								




*Handwritten signature*


08560

CLAUSE NO.	TECHNICAL REQUIREMENTS				
	Application		Type Of Termination		
	FROM (A)	TO (B)	END A	END B	
	Thermocouple	Temperature transmitter	Plug in connector	Screwed, Cage clamp type	A, B, C*
	Local Junction box, Temperature Transmitter, Int. Junction box of LIE/ LIR/ MCC/SWGR	Group JB	Cage clamp (Rail mount) type.	Cage clamp (Rail mount) type.	F,G
	Local Junction box, Temperature Transmitter, Int. Junction box of LIE/ LIR/ Group JB / MCC/SWGR	Marshalling / Marshalling – cum Termination Cubicle	Cage clamp (Rail mount) type.	Cage clamp (Post mounted) type.	F,G
	Marshalling cubicle/ Termination Cabinet	Electronic system cabinet	Cage clamp (Post mounted) type.	Plug-in connector / other system as per Mfr.'s Standard	Internal wiring
	Marshalling/ Termination System Cabinets	UCD mounted equipments	Cage clamp (Post mounted) type.	Plug in connector / Cage clamp type (rail mounted).	F,G (with plug-in connect or at one end)
	DDCMIS/PLC cabinets	PC, Printers etc.	Plug in connector	Plug in connector	Mfr.'s Standard
<p>Notes</p> <ol style="list-style-type: none"> <li>Normally 10% spare cores shall be provided when the numbers of pairs of cables are more than four pairs, except for pre-fabricated cables which shall be as per manufacturer's standard.</li> <li>For analog signals, individual pair shielding &amp; overall shielding &amp; for Binary signals, only overall shielding of instrumentation cables shall be provided.</li> <li>Also refer drg. X-405-POI-A-021.</li> <li>*For high temperature applications only.</li> </ol>					
SINGRAULI STPP STAGE-III (1X500 MW) EPC PACKAGE		TECHNICAL SPECIFICATION SECTION - VI PART-B		SUB-SECTION-C-06 INSTRUMENTATION POWER SUPPLY CABLE	PAGE 10 OF 17



08561

CLAUSE NO.	TECHNICAL REQUIREMENTS			
6.00.00	<b>TERMINAL BLOCKS</b>			
6.01.00	<p>All terminal blocks shall be rail mounted/post mounted, cage clamp type with high quality non-flammable insulating material of melamine suitable for working temperature of 105 deg. C. The terminal blocks in field mounted junction boxes, temperature transmitters, instrument enclosures/racks, etc., shall be suitable for cage clamp connections. The terminal blocks in Control Equipment Room logic/termination/marshalling cubicles shall be suitable for post mounted cage clamp connection at the field input end. The terminal blocks for DDCMIS input/output connections from/to SWGR/MCC, Actuators with Integral Starter (for coupling relays and check back signals of 11 kV and 3.3 kV auxiliaries, LT drives/valves &amp; dampers/solenoids, CT &amp; VT, etc.) shall be provided with built in test and disconnect facilities complete with plug, slide clamp, test socket etc. The exact type of terminal blocks to be provided by the Bidder and the technical details of the same including width etc. shall be subject to Employer's approval.</p>			
6.02.00	<p>All the terminal blocks shall be provided complete with all required accessories including assembly rail, locking pin and section, end brackets, partitions, small partitions, test plug bolts and test plug (as specified above for SWGR connections) transparent covers, support brackets, distance sleeves, warning label, marking, etc.</p>			
6.03.00	<p>The marking on terminal strips shall correspond to the terminal numbering on wiring diagrams. At least 20% spare unused terminals shall be provided everywhere including local junction boxes, instrument racks/enclosures, termination/marshalling cabinets, etc. All terminal blocks shall be numbered for identification and grouped according to the function. Engraved labels shall be provided on the terminal blocks.</p>			
6.04.00	<p>For terminating each process actuated switches, drive actuators, control valves, Thermocouple,RTD, etc. in Local Junction Boxes, etc, refer Drg no. 0000-999-POI-A-065.</p>			
6.05.00	<p>The terminal blocks shall be arranged with at least 100 mm clearance between two sets of terminal blocks and between terminal blocks and junction box walls.</p>			
6.06.00	<p>For ensuring proper connections, Bidder shall provide suitable accessories, along with insulation sleeves. The exact connecting accessory shall be finalised as per application during detail engineering stage subject to Employer's approval without any cost repercussions.</p>			
6.07.00	<p>Internal wiring in factory pre-wired electronic equipment cabinets may be installed according to the Bidder's standard as to wire size and method of termination or internal equipment. Terminal blocks for connection of external circuits into factory prewired electronic equipment cabinets shall meet all the requirements as specified above.</p>			
7.00.00	<b>INTERNAL PANELS/ SYSTEM CABINETS WIRING</b>			
7.01.00	<p>Internal panel/cabinet wiring shall be of <del>multi-stranded</del> copper conductor with FRLS PVC insulation <del>without shield</del> and outer sheath meeting the requirements of VDE 0815.</p>			
<p>SINGRAULI STPP STAGE-III (1X500 MW) EPC PACKAGE</p>	<p>TECHNICAL SPECIFICATION SECTION - VI PART-B</p>	<p>SUB-SECTION-C-06 INSTRUMENTATION POWER SUPPLY CABLE</p>	<p>PAGE 11 OF 17</p>	





-08269



## **SUB-SECTION**

# **ELECTRICAL ACTUATORS WITH INTEGRAL STARTERS**



CLAUSE NO.	TECHNICAL REQUIREMENTS		
1.00.00	ELECTRIC ACTUATORS WITH INTEGRAL STARTERS		08270
1.01.00	<b>TYPE:</b>		
1.01.01	The actuators shall have integral starters along with over load relays with built in SPP (Single Phasing Preventer). A 415, 3 phase 3 wire power supply shall be given to the actuator from vendor's/employer's switch board as applicable through a switch fuse unit. Control voltage of the motor starter shall be 110 V AC / 24 V DC, derived suitably from 415V power supply.		
1.01.02	In case supplier's standard control voltage for Open/Close contactors is 110V AC, the same is acceptable if suitable Opto Isolation circuit is provided with coupling relays for 24 V DC command inputs.		
1.02.00	<b>INTERFACES:</b>		
1.02.01	<p>Open/Close command termination logic with position &amp; torque Limit Switches, positioner circuit shall be suitably built in the PCB inside the actuator.</p> <p>(a) For Binary Drive (both ON-OFF and INCHING type) :- Open/Close command &amp; status thereof and disturbance monitoring signal (common contact for Overload, Thermostat, control supply failure, L/R selector switch at local &amp; other protections operated) shall be provided.</p> <p>Interface with the control system shall be through hardware signal only. Inter posing relays provided (with coil burden 2.5 VA) in the actuator shall be energized to initiate opening and closing, by 24V DC signal from the external control system.</p> <p>(b) For Modulating Drive:- the command to actuator shall be in form of 4-20mA signal. The necessary positioning circuit and motor protection shall be provided</p> <p>(c) Open/close command termination logic shall be suitably built inside actuator.</p>		
1.03.00	<p><b>RATING :</b></p> <p>(a) Supply Voltage &amp; frequency: 415V +/- 10%, 3 Phase, 3 Wire 50HZ +/-5%.</p> <p>(b) Sizing:-</p> <p>For Open/Close at rated speed against designed differential pressure at 90% of rated voltage.</p> <p>For isolating service:- three successive open-close operations or 15 mins, whichever is higher. For regulating service 150 starts per hour or required cycles, whichever is higher.</p>		
SINGRAULI STPP STAGE-III (1X500 MW) EPC PACKAGE	TECHNICAL SPECIFICATION SECTION - VI PART-B	SUB-SECTION-B-30 ELECTRICAL ACTUATORS WITH INTEGRAL STATORS	


CLAUSE NO.	TECHNICAL REQUIREMENTS		
1.04.00	<p style="text-align: right;"><b>08271</b></p> <p><b>CONSTRUCTION:</b></p> <p>(a) Enclosure: Totally enclosed weatherproof minimum IP-55 degree of protection.</p> <p>(b) Gear Train : Metal (Fibre gears are not acceptable) self-locking to prevent drift under torque switch (where ever applicable) spring pressure when motor is de-energised.</p> <p>(c) Manual Wheel: Shall disengage automatically during motor operation.</p>		
1.05.00	<p><b>MOTOR :</b></p> <p>(a) Type : Squirrel cage induction motor suitable for Direct On Line ( DOL ) starting.</p> <p>(b) Enclosure: Totally enclosed, self ventilated IP-55 degree of protection.</p> <p>(c) Insulation Class B or better. Temperature rise 70 Deg C. over 50 Deg C ambient</p> <p>(d) Bearings: Double shielded, grease lubricated antifriction.</p> <p>(e) Earth Terminals: Two</p> <p>(f) Protection: Single Phasing Protection, Over heating protection through Thermostat and wrong phase sequence protection shall be provided over and above other protection features standard to bidder's design Suitable means shall be provided to diagnose the type of fault locally.</p>		
1.06.00	<p><b>POSITION/TORQUE SWITCHES:</b></p>		
1.06.01	<p>Four nos. (2 each in open and close position) position limit switches and two nos. (one in open and other in close direction) torque switches each having two nos. NO</p>		
<p>SINGRAULI STPP STAGE-III (1X500 MW) EPC PACKAGE</p>	<p>TECHNICAL SPECIFICATION SECTION - VI PART-B</p>	<p>SUB-SECTION-B-30 ELECTRICAL ACTUATORS WITH INTEGRAL STATERS</p>	<p>PAGE 2 OF 4</p>




Handwritten signature or initials.



	<p>and two nos. NC contacts shall be provided. A single shaft shall actuate all contacts of limit switches at each position.</p> <p>Limit switch and disturbance signals shall be available to DCS even when the power supply to the actuators is not available.</p> <p>Torque switches shall be bypassed in both the end positions with the other end Limit switches.</p> <p><b>Limit switches</b></p> <p>Limit switches shall be Silver plated with high conductivity and non-corrosive type. Contact rating shall be sufficient to meet the requirement of Control System subject to a minimum of 60 V, 6 VA rating. Protection class shall be IP-55.</p>
1.07.00	<b>LOCAL OPERATION:</b>
1.07.01	It shall be possible to operate the actuator locally also. Lockable local/remote selection shall be provided on the actuator.
1.08.00	<b>POSITION INDICATOR :</b>
1.08.01	To be provided for 0 to 100% travel.
1.09.00	<b>POSITION TRANSMITTER (FOR MODULATING/INCHING TYPE) :</b>
1.09.01	As required. Suitable for stabilized 4-20 mA signal, 2 wire inductive type, 24 volts DC operated.
1.10.00	<b>WIRING :</b>
1.10.01	Suitable voltage grade copper wire.
1.11.00	<b>TERMINAL BOX :</b>
	<ul style="list-style-type: none"> <li>(i) 9 pin plug and socket (1 no. per actuator to suit 4 pair 0.5 sq.mm. copper overall shielded (16 mm OD), instrumentation cable) suitably mounted in the starter box itself to terminate open/close command and status feedback signals with external control systems.</li> <li>(ii) Additional one number 9 pin plug and socket (to suit 4 pair 0.5 sq.mm copper (16 mm OD) individual and overall shielded instrumentation cable) suitably mounted in the starter box itself for actuators with 4-20 mA position transmitters.</li> <li>(iii) Necessary glands for power cables shall be provided.</li> </ul>



CLAUSE NO.	08273 TECHNICAL REQUIREMENTS			एनटीपीसी NTPC
1.12.00	<b>TERMINAL BLOCK :</b>			
1.12.01	650V grade. For power cables.			
1.13.00	<b>SPACE HEATER :</b>			
1.13.01	Space heater of suitable rating. The supply shall be derived from the main power supply available in the actuator.			
<del>1.14.00</del>	<del><b>TYPICAL WIRING DIAGRAM :</b></del>			
<del>1.14.01</del>	<del>Refer Tender Drawing No. 0000-999-POI-A-063.</del>			
SINGRAULI STPP STAGE-III (1X500 MW) EPC PACKAGE	TECHNICAL SPECIFICATION SECTION -VI PART-B	SUB-SECTION-B-30 ELECTRICAL ACTUATORS WITH INTEGRAL STATERS	PAGE 4 OF 4	



101

<b>SPECIFICATION FOR MOTORISED VALVE ACTUATOR</b>	SPECIFICATION NO.: PE-ID-401-145-1902		
	VOLUME	II B	
	SECTION	D	
	REV. NO.	00	DATE: 25.03.14
	SHEET	2	OF 5

### Data Sheet A & B

DATA SHEET-A (TO BE FILLED BY PURCHASER)	DATA SHEET-B (TO BE FILLED-UP BY BIDDER)
---	---

<b>GENERAL*</b>	* PROJECT	1 X 500 MW FGUTPP	
	OFFER REFERENCE		
	* TAG NO. SERVICE		
	* DUTY	<input type="checkbox"/> ON / OFF	<input type="checkbox"/> INCHING
	* LINE SIZE (inlet/outlet): MATERIAL		
	* VALVE TYPE	<input type="checkbox"/> GLOBE <input type="checkbox"/> GATE <input type="checkbox"/> REG. GLOBE <input type="checkbox"/> BUTTERFLY	
	* OPENING / CLOSING TIME		
	* WORKING PRESSURE		
	AMBIENT CONDITION	SHALL BE SUITABLE FOR CONTINUOUS OPERATION UNDER AN AMBIENT TEMP. OF 0-55 DEG C AND RELATIVE HUMIDITY OF 0-95%	
	VALVE SEAT TEST PRESS	BIDDER TO SPECIFY	
	REQUIRED VALVE TORQUE	BIDDER TO SPECIFY	
	ACTUATOR RATED TORQUE	BIDDER TO SPECIFY	
<b>CONSTRUCTION AND SIZING</b>	CONSTRUCTION	TOTALLY ENCLOSED, WEATHER PROOF, IP:55	
	MECHANICAL POSITION INDICATOR	TO BE PROVIDED FOR 0-100% TRAVEL	
	BEARINGS	DOUBLE SHIELDED, GREASE LUBRICATED ANTI-FRICTION.	
	GEAR TRAIN FOR LIMIT SWITCH/TORQUE SWITCH OPERATION	METAL (NOT FIBRE GEARS). SELF-LOCKING TO PREVENT DRIFT UNDER TORQUE SWITCH SPRING PRESSURE WHEN MOTOR IS DE-ENERGIZED.	
	SIZING	OPEN/CLOSE AT RATED SPEED AGAINST DESIGNED DIFFERENTIAL PRESSURE AT 85% OF RATED VOLTAGE. FOR ISOLATING SERVICE THREE SUCCESSIVE OPEN-CLOSE OPERATIONS OR 15 MINS. WHICHEVER IS HIGHER. <b>FOR INCHING SERVICE - 150 STARTS/HR MINIMUM &amp; FOR REGULATING SERVICE - 600 STARTS/HR MINIMUM.</b>	
<b>HANDWHEEL</b>	* REQUIRED	<input checked="" type="checkbox"/> YES <input type="checkbox"/> NO	
	* ORIENTATION	<input type="checkbox"/> TOP MOUNTED <input type="checkbox"/> SIDE MOUNTED	
	*TO DISENGAGE AUTOMATICALLY DURING MOTOR OPERATION.		
<b>ELECTRIC ACTUATOR</b>	ACTUATOR MAKE/MODEL	BIDDER TO SPECIFY	
	MOTOR MAKE / MODEL / TYPE / RATING (KW)	BIDDER TO SPECIFY	
	@ MOTOR TYPE	SQUIRREL CAGE INDUCTION MOTOR SUITABLE FOR DOL STARTING	
	ACTUATOR APPLICABLE WIRING DIAGRAM	<input checked="" type="checkbox"/> ENCLOSED (BIDDER TO CONFIRM) A: <input type="checkbox"/> DRG. NO. 3-V-MISC-24227 R00 B: <input type="checkbox"/> DRG. NO. 3-V-MISC-24550 R00 C: <input checked="" type="checkbox"/> DRG. NO. 3-V-MISC-24283 R00 D: <input type="checkbox"/> DRG. NO. 4-V-MISC-90271 R11 E: <input type="checkbox"/> For Thyristor based Integral starter, Bidder/Vendor to furnish wiring diagram	
	COLOUR SHADE	<input checked="" type="checkbox"/> BLUE (RAL 5012) <input type="checkbox"/> .....	
	<b>PAINT TYPE (## Refer Notes)</b>	<input checked="" type="checkbox"/> ENAMEL <input type="checkbox"/> EPOXY <input type="checkbox"/> .....	
	SHAFT RPM	BIDDER TO SPECIFY	
	OLR SET VALUE	BIDDER TO SPECIFY	
	@ STARTING / FULL LOAD CURRENT	BIDDER TO SPECIFY	
	NO. OF REV FOR FULL TRAVEL	BIDDER TO SPECIFY	
	@ PWR SUPP TO MTR / STARTER	415V, 3PH, AC	
	@ CONTROL VOLTAGE REQUIREMENT	110V AC/ 24VDC TO BE DERIVED SUITABLY FROM 415V POWER SUPPLY	

<b>SPECIFICATION FOR MOTORISED VALVE ACTUATOR</b>	SPECIFICATION NO.: PE-ID-401-145-1902		
	VOLUME	II B	
	SECTION	D	
	REV. NO.	00	DATE: 25.03.14
	SHEET	3	OF 5

### Data Sheet A & B

DATA SHEET-A (TO BE FILLED BY PURCHASER)	DATA SHEET-B (TO BE FILLED-UP BY BIDDER)
---	---

	@ ENCLOSURE CLASS OF MOTOR	TOTALLY ENCLOSED, SELF VENTILATED IP-55 DOP	
	@ INSULATION CLASS	CLASS B OR BETTER, TEMPERATURE RISE 70 DEG C OVER 50 DEG C AMBIENT	
	@ WINDING TEMP PROTECTION	■ THERMOSTAT (3 Nos., 1 IN EACH PHASE)	
	SINGLE PHASE / WRONG PHASE SEQUENCE PROTECTION	REQUIRED	
<b>INTEGRAL STARTER</b>	INTEGRAL STARTER	■ REQUIRED      □ NOT REQUIRED	
	TYPE OF SWITCHING DEVICE	■ CONTACTORS      □ THYRISTORS	
	TYPE	■ CONVENTIONAL      □ SMART (NON-INTRUSIVE)	
	<b>IF SMART</b>		
	a) SERIAL LINK INTERFACE	□ INTEGRAL      □ FIELD MOUNTED	
	b) SERIAL LINK PROTOCOL	□ FOUNDATION FIELD-BUS      □ PROFI-BUS □ DEVICE NET      □ .....	
	c) SERIAL LINK MEDIA	□ TWISTED PAIR Cu-CBL      □ CO-AXIAL Cu-CBL □ OFC	
	d) HAND HELD PROGRAMMER	□ REQUIRED      □ NOT REQUIRED	
	e) TYPE OF HAND HELD PROGRAMMER	□ BLUETOOTH      □ INFRARED      □ .....	
	f) MASTER STATION	□ REQUIRED      □ NOT REQUIRED	
	g) MASTER STN INTRFACE WITH DCS	□ MODBUS      □ TCP/IP	
	h) DETAILS OF SPECIAL CABLE	□ ENCLOSED      □ NOT REQUIRED	
	STEP DOWN CONT. TRANSFORMER	■ REQUIRED	
	OPEN / CLOSE PB	■ REQUIRED      □ NOT REQUIRED	
	STOP PB	■ REQUIRED      □ NOT REQUIRED	
	INDICATING LAMPS	■ REQUIRED      □ NOT REQUIRED	
	LOCAL REMOTE S/S	■ REQUIRED      □ NOT REQUIRED	
STATUS CONTACTS FOR MONITORING	■ REQUIRED      □ NOT REQUIRED		
INTEGRAL STARTER DISTURBED SIGNAL	REQUIRED (O/L RELAY OPERATED, CONT./POWER SUPPLY FAILED, S/S IN LOCAL, TORQUE SWITCH OPTD. MID WAY)		
<b>INTERPOSING RELAY/OPTO COUPLER</b> (Applicable for integral Starter)	TYPE OF ISOLATING DEVICE	■ INTERPOSING RELAY      □ OPTO COUPLER □ EITHER	
	QUANTITY	■ 2 NOs.      □ 3 NOs.	
	DRIVING VOLTAGE	■ 20.5 – 24V DC      □ _____ V DC	
	DRIVING CURRENT	■ 125mA MAX      □ _____ mA MAX	
	LOAD RESISTANCE	■ > 192 ohms - <25 k ohms □ > _____ ohms - < _____ ohms	
<b>TORQUE SWITCH</b> (Not Applicable for Smart Actuator) <b>(\$\$ Refer Notes)</b>	MFR & MODEL NO.	BIDDER TO SPECIFY	
	OPEN / CLOSE	■ 1 No.      □ 2Nos. /      ■ 1 No.      □ 2Nos	
	CONTACT TYPE	2 NO + 2 NC	
	RATING	5A 240V AC AND 0.5A 220V DC	
	CALIBRATED KNOBS(OPEN&CLOSE TS)	REQUIRED FOR SETTING DESIRED TORQUE	
	ACCURACY	+3% OF SET VALUE	
<b>LIMIT SWITCH</b> (Not Applicable for Smart Actuator) <b>(\$\$ Refer Notes)</b>	MFR & MODEL NO.	BIDDER TO SPECIFY	
	OPEN : INT : CLOSE	□ 1 No.      2 Nos. (ADJ.)      □ 1 No. ■ 2 Nos.      ■ 2Nos.	
	CONTACT TYPE	2 NO + 2 NC	
	RATING (AC / DC)	5A 240V AC AND 0.5A 220V DC	

<b>SPECIFICATION FOR MOTORISED VALVE ACTUATOR</b>	SPECIFICATION NO.: PE-ID-401-145-1902	
	VOLUME	II B
	SECTION	D
	REV. NO.	00
	DATE:	25.03.14
SHEET	4 OF 5	

### Data Sheet A & B

DATA SHEET-A (TO BE FILLED BY PURCHASER)	DATA SHEET-B (TO BE FILLED-UP BY BIDDER)
---	---

<b>POSITION TRANSMITTER</b>	POSITION TRANSMITTER (For inching duty & other specific applications)	<input checked="" type="checkbox"/> REQUIRED <input type="checkbox"/> NOT REQUIRED	
	MFR & MODEL NO.	BIDDER TO SPECIFY	
	TYPE	<input type="checkbox"/> ELECTRONIC (2 WIRE) R/I CONVERTER <input checked="" type="checkbox"/> ELECTRONIC (2 WIRE) CONTACTLESS	
	SUPPLY	<input checked="" type="checkbox"/> 24V DC <input type="checkbox"/> .....	
	OUTPUT	<input checked="" type="checkbox"/> 4-20mA	
	ACCURACY	± 1% FS	
<b>SPACE HEATER</b>	@SPACE HEATER	REQUIRED	
	@ POWER SUPPLY (NON INTEGRAL)	N.A	
	@ POWER SUPPLY (INTEGRAL)	BIDDER TO SPECIFY	
	@ RATING		
<b>TERMINAL BOX</b>	ACTUATOR/MOTOR TERMINAL BOX	REQUIRED	
	ENCL CLASS ACTUATOR/MOTOR T.B.	@ <input type="checkbox"/> IP 68                      @ <input checked="" type="checkbox"/> IP 55	
	@ EARTHING TERMINAL	REQUIRED TWO	
	PLUG & SOCKET(9 PIN) (FOR COMMD, LS/TS FEED BACK, PoT)	<input checked="" type="checkbox"/> REQUIRED <input type="checkbox"/> NOT REQUIRED <input checked="" type="checkbox"/> 2 NOS. <input type="checkbox"/> .....	
<b>CABLE GLANDS</b>	@ POWER CABLE GLAND	SIZE:--TO BE PROVIDED DURING DETAILED ENGINEERING	
	@ SPACE HEATER CABLE GLAND	SIZE:----- TO BE PROVIDED DURING DETAILED ENGINEERING	
	OTHER CONTROL CABLE GLANDS-1	<input type="checkbox"/> 1No. for BFV of CW PUMP	
	OTHER CONTROL CABLE GLANDS-2	QUANTITY & SIZE : TO BE PROVIDED DURING DETAILED ENGINEERING	
<b>WEIGHT</b>	TOTAL WEIGHT (ACTUATOR + ACCESSORIES)	BIDDER TO SPECIFY	_____ Kg.

**NOTES:**

- SCOPE:** DESIGN, MANUFACTURE, INSPECTION, TESTING AND DELIVERY TO SITE OF ELECTRIC ACTUATOR FOR INCHING OR OPEN / CLOSE DUTY.
  - CODES & STANDARDS:** DESIGN AND MATERIALS USED SHALL COMPLY WITH THE RELEVANT LATEST NATIONAL AND INTERNATIONAL STANDARD. AS A MINIMUM, THE FOLLOWING STANDARDS SHALL BE COMPLIED WITH:  
IS-9334, IS-2147, IS-2148, IS-325, IS-2959, IS-4691 AND IS-4722
  - TEMPERATURE RISE SHALL BE RESTRICTED TO 70 DEG. C FOR AMBIENT TEMPERATURE OF 50 DEG C.
  - CABLE GLANDS OF DOUBLE COMPRESSION TYPE, BRASS MATERIAL SHALL BE PROVIDED.
  - THE TORQUE SWITCHES SHALL BE PROVIDED WITH MECHANICAL LATCHING DEVICE TO PREVENT OPERATION WHEN UNSEATING FROM THE END POSITIONS. THE LATCHING DEVICE SHALL UNLATCH AS SOON AS THE VALVE LEAVES THE END POSITION. IF SUCH PROVISION IS NOT POSSIBLE, THE TORQUE SWITCHES SHALL BE BYPASSED BY END-POSITION LIMIT SWITCHES WHICH OPENS ON VALVE LEAVING END POSITION. THESE LIMIT SWITCHES ARE ADDITIONAL TO THE NUMBER OF LIMIT SWITCHES SPECIFIED ELSEWHERE.
  - THE MOTOR SHALL OPERATE SATISFACTORILY UNDER THE +/- 10% SUPPLY VOLTAGE VARIATION AT RATED FREQUENCY, -5% TO +3% VARIATION IN FREQUENCY AT RATED SUPPLY VOLTAGE, SIMULTANEOUS VARIATION IN VOLTAGE & FREQUENCY THE SUM OF ABSOLUTE PERCENTAGE NOT EXCEEDING 10%.
  - THE MOTOR SHALL BE SUITABLE FOR DIRECT ON LINE STARTING.
- \$\$ TORQUE SWITCH & LIMIT SWITCH SHALL ACT INDEPENDENT OF EACH OTHER. TANDEM OPERATION IS NOT ACCEPTABLE.**
- ## EPOXY PAINT IS RECOMMENDED FOR COASTAL AREAS.**

<b>NAME SIGNATURE DATE</b>	<b>PREPARED BY</b>	<b>CHECKED BY</b>	<b>APPROVED BY</b>	<b>VENDOR COMPANY SEAL</b>
	ANUJ WADHWA	AMIT TYAGI	BHARAT SINGH	NAME
				SIGNATURE
	25.03.2014	25.03.2014	25.03.2014	DATE

NOTES\* = TO BE FILLED BY MPL (LEAD AGENCY).    @= TO BE FILLED BY ES

ALL DIMENSIONS ARE IN MILLIMETRES. FOR TOLERANCES OF UNTOLERANCED DIMENSIONS DURING MANUFACTURE REFER RELEVANT QCP / QP.


DRAWING NO. 58272-031W1-A-5

### CONTACT DEVELOPMENT DIAGRAM

OTS	1-2	OPEN AT OVER TORQUE DURING OPENING TRAVEL
	3-4	CLOSE AT OVER TORQUE DURING OPENING TRAVEL
CTS	5-6	OPEN AT OVER TORQUE DURING CLOSING TRAVEL
	7-8	CLOSE AT OVER TORQUE DURING CLOSING TRAVEL
OLS-1	9-10	
	11-12	
CLS-1	13-14	
	15-16	
OLS-2	17-18	
	19-20	
CLS-2	21-22	
	23-24	
SWITCH NO.		
	TERMINAL OPEN	d
	INTERMEDIATE	b
	FULL CLOSE	a

--- INDICATES CONTACT CLOSED  
 - - - - - INDICATES CONTACT OPEN

CONTACT RATING: 5A AT 250V AC & 0.5A AT 220V DC



### SETTING PROCEDURE OF POSITION LIMIT AND TORQUE SWITCH

VALVES	OPEN			CLOSE		
	MAIN	BACK UP	MAIN	BACK UP	MAIN	BACK UP
GATE VALVE OF 100 mm AND ABOVE IN 1500 CL. AND ABOVE RATINGS	OLS	OTS *	CLS	CLS	CTS	CTS
ALL OTHER GATE & GLOBE VALVES	OLS	OTS *	CTS	CTS	CTS	#

# - CLS NOT TO BE CONNECTED IN TRIP CIRCUIT  
 \* - BYPASS OTS FOR INITIAL 5% OF TRAVEL (FOR GATE VALVES ONLY)

**TYPE OF PRODUCT** ELECTRICAL VALVE ACTUATORS (AC) WITH INTEGRAL STARTERS FOR NTPC PROJECTS

**OR NAME OF CUSTOMER/PROJECT** (DRAWN FOR INTERMEDIATE POSITION OF VALVES)

	DRN	N.P.ESWAR	SIGN	N.P.	DATE	NO. OF VAL.
	CHD	D.DINAKARAN		D.D	17.03.05	
	APPD	K.ARUNACHALAM		K.A	17.03.05	

UNIT: HIGH PRESSURE BOILER PLANT, TRUCHIRAPALLI-620014.

DEPT	VL	SCALE	WEIGHT (KG)	REFERENCE INFORMATION
		NIS		

REV DATE ALTERED CHD & APPD

CARD CODE	DRAWING NO.	REV
U 01	3-V-MISC-24283	0

WIRING DIAGRAM (TERMINAL PLAN)  
 FOR ACTUATOR WITH INTEGRAL STARTER WITH PLUG & SOCKET FOR NTPC PROJECTS

- NOTE:-**
- ALL TORQUE AND LIMIT SWITCHES (OTS,CTS,OLS1&2, CLS1&2) ARE WITH 2NO+2NC CONTACTS '1NO+1NC' IS TERMINATED IN TBS 1-24, REMAINING CONTACTS ARE FOR INTERNAL USE. ANY SPARE CONTACTS WHICH ARE NOT USED INTERNALLY ARE TO BE TERMINATED IN TBS 25-32
  - CTS - TORQUE SWITCHES FOR CW ROTATION (CLOSE)
  - OTS - TORQUE SWITCHES FOR CCW ROTATION (OPEN)
  - OLS-1, OLS-2 - LIMITSWITCHES FOR POSITION OPEN
  - CLS-1, CLS-2 - LIMITSWITCHES FOR POSITION CLOSE
  - EPT - ELECTRONIC POSITION TRANSMITTER (CONTACTLESS TYPE, FOR INCHING DUTY)
  - R1-R2-POTENTIOMETER 2 x 100 OHMS (FOR ON-OFF DUTY)
  - FOR COMMANDS & EPT EITHER INTERNALLY GENERATED 24 VDC OR EXTERNAL SUPPLY OF 24VDC CAN BE USED
  - M - MOTOR 3ø 415V 50 Hz AC SUPPLY
  - TORQUE SWITCH BYPASS WITH LIMITSWITCH BOTH ON OPEN & CLOSE DIRECTION TO BE DONE INTERNALLY.

CLAUSE NO.


TECHNICAL REQUIREMENTS





**Annexure C&I-1 to S.No. 04 of Amendment**



**.12430**


**SUB-SECTION  
TYPE TESTS REQUIRMENTS**



*Handwritten mark*

CLAUSE NO.	TECHNICAL REQUIREMENTS			
	<b>TYPE TEST REQUIREMENTS</b>			
1.00.00	<b>TYPE TEST REQUIREMENTS</b>	<b>12431</b>		
1.01.00	<b>General Requirements</b>			
1.01.01	<p>The Contractor shall furnish the type test reports of all type tests as per relevant standards and codes as well as other specific tests indicated in this specification. A list of such tests are given for various equipment in table titled 'TYPE TEST REQUIREMENT FOR C&amp;I SYSTEMS' at the end of this chapter and under the item Special Requirement for Solid State Equipments/Systems. For the balance equipment instrument, type tests may be conducted as per manufactures standard or if required by relevant standard.</p> <p>(a) Out of the tests listed, the Bidder/ sub-vendor/ manufacturer is required to conduct certain type tests specifically for this contract (and witnessed by Employer or his authorized representative) even if the same had been conducted earlier, as clearly indicated subsequently against such tests.</p> <p>(b) For the rest, submission of type test results and certificate shall be acceptable provided.</p> <p style="margin-left: 40px;">i. The same has been carried out by the Bidder/ sub-vendor on exactly the same model /rating of equipment. ( For control valves, this shall be same size, type &amp; design).</p> <p style="margin-left: 40px;">ii. There has been no change in the components from the offered equipment &amp; tested equipment.</p> <p style="margin-left: 40px;">iii. The test has been carried out as per the latest standards alongwith amendments as on the date of Bid opening.</p> <p>(c) In case the approved equipment is different from the one on which the type test had been conducted earlier or any of the above grounds, then the tests have to be repeated and the cost of such tests shall be borne by the Bidder/ sub-vendor within the quoted price and no extra cost will be payable by the Employer on this account.</p>			
1.01.02	As mentioned against certain items, the test certificates for some of the items shall be reviewed and approved by the main Bidder or his authorized representative and the balance have to be approved by the Employer.			
1.01.03	The schedule of conduction of type tests/ submission of reports shall be submitted and finalized during pre-award discussion.			
1.01.04	For the type tests to be conducted, Contractor shall submit detailed test procedure for approval by Employer. This shall clearly specify test setup, instruments to be			
FGUTPP-IV (1 x 500MW) EPC PACKAGE		 TECHNICAL SPECIFICATIONS SECTION-VI PART-B	SUB SECTION C-07 TYPE TEST REQUIREMENTS	PAGE 2 OF 9


CLAUSE NO.	TECHNICAL REQUIREMENTS			
1.01.05	<p>used, procedure, acceptance norms (wherever applicable), recording of different parameters, interval of recording precautions to be taken etc. for the tests to be carried out.</p> <p style="text-align: right; font-size: 24px;"><b>12432</b></p> <p>The Bidder shall indicate in the relevant BPS schedule, the cost of the type test for each item only for which type tests are to be conducted specifically for this project. The cost shall only be payable after conduction of the respective type test in presence of authorize representative of Employer. If a test is waived off, then the cost shall not be payable.</p>			
2.00.00	<b>SPECIAL REQUIREMENT FOR SOLID STATE EQUIPMENTS/ SYSTEMS</b>			
2.01.00	<p>The minimum type test reports, over and above the requirements of above clause, which are to be submitted for each of the major C&amp;I systems shall be as indicated below:</p> <p>i) Surge Withstand Capability (SWC) for Solid State Equipments/ Systems</p> <p>All solid state systems/ equipments shall be able to withstand the electrical noise and surges as encountered in actual service conditions and inherent in a power plant. All the solid state systems/ equipments shall be provided with all required protections that needs the surge withstand capability as defined in ANSI 37.90.1/ IEEE-472. Hence, all front end cards which receive external signals like Analog input &amp; output modules, Binary input &amp; output modules etc. including power supply, data highway, data links shall be provided with protections that meets the surge withstand capability as defined in ANSI 37.90.1/ IEEE-472. Complete details of the features incorporated in electronics systems to meet this requirement, the relevant tests carried out, the test certificates etc. shall be submitted along with the proposal. As an alternative to above, suitable class of EN 61000-4-12 which is equivalent to ANSI 37.90.1/ IEEE-472 may also be adopted for SWC test.</p> <p>ii) Dry Heat test as per IEC-68-2-2 or equivalent.</p> <p>iii) Damp Heat test as per IEC-68-2-3 or equivalent.</p> <p>iv) Vibration test as per IEC-68-2-6 or equivalent.</p> <p>v) Electrostatic discharge tests as per EN 61000-4-2 or equivalent.</p> <p>vi) Radio frequency immunity test as per EN 61000-4-6 or equivalent.</p> <p>vii) Electromagnetic Field immunity as per EN 61000-4-3 or equivalent.</p> <p>Test listed at item no. v, vi, vii, above are applicable for electronic cards only as defined under item (i) above.</p>			
FGUTPP-IV (1 x 500MW) EPC PACKAGE	 <p>TECHNICAL SPECIFICATIONS SECTION-VI PART-B</p>	SUB SECTION C-07 TYPE TEST REQUIREMENTS	PAGE 3 OF 9	




109



6W

08580

CLAUSE NO.	TECHNICAL REQUIREMENTS					
3.00.00	<b>TYPE TEST REQUIREMENT FOR C&amp;I SYSTEMS</b>					
Sl. No	Item	Test Requirement	Standard	Test To Be Specifically Conducted	NTPC's Approval Req. On Test Certificate	
Col 1	Col 2	Col 3	Col 4	Col 5	Col 6	
1	Elect. Metering instruments	As per standard (col 4)	IS-1248	No	Yes	
2	Transducers	As per standard (col 4)	IEC-60688, IS12784	No	Yes	
3	Thermocouple	Degree of protection test	IS-13947	No	No	
4	RTD	As per standard (col 4)	IEC-60751	No	No	
5	Electronic transmitter	As per standard (col 4)	BS-6447 / IEC-60770	No	Yes	
6	E/P converter	As per standard (col 4)	Mfr. standard	No	Yes	
7	Dust emission monitor	Degree of protection test	IS-13947	No	Yes	
8	<b>Instrumentation Cables Twisted &amp; Shielded*</b>					
	-Conductor	Resistance test	VDE-0815	No	Yes	
		Diameter test	IS-10810	No	Yes	
		Tin Coating test (Persulphate test)	IS-8130	No	Yes	
	-Insulation	Loss of mass	VDE 0472	No	Yes	
		Ageing in air ovens**	VDE 0472	No	Yes	
SINGRAULI STPP STAGE-III (1X500 MW) EPC PACKAGE		TECHNICAL SPECIFICATION SECTION - VI PART-B		SUB-SECTION-C-07 TYPE TEST REQUIREMENTS		PAGE 3 OF 10




08583


CLAUSE NO.	TECHNICAL REQUIREMENTS																																							
	<p>* 1.0 All cables to be supplied shall be of type tested quality. The Contractor shall submit for Owner's approval the reports of all the type tests as listed in this specification and carried out within last five years from the date of bid opening. These reports should be for the tests conducted on the equipment similar to those proposed to be supplied under this contract and the test(s) should have been either conducted at an independent laboratory or should have been witnessed by a client.</p> <p>2.0 In case the Contractor is not able to submit report of the type test(s) conducted within last five years from the date of bid opening, or in case the type test report(s) are not found to be meeting the specification requirements, the Contractor shall conduct all such tests under this contract free of cost to the Owner and submit the reports for approval.</p> <p>**These tests shall be carried out as per VDE0207 Part 6 &amp; ASTM-D-2116 for TEFLON insulated &amp; outer sheathed cables</p> <p>***Applicable for armoured cables only</p>																																							
9	DC Power Supply System (Applicable for each model and rating)	<table border="1"> <tr> <td>Degree of protection test</td> <td>IS-13947</td> <td>Yes</td> <td>Yes</td> </tr> <tr> <td>Short circuit current capability</td> <td>Approved procedure</td> <td>Yes</td> <td>Yes</td> </tr> <tr> <td>Voltage Proof Test</td> <td>UL 950, IEC950</td> <td>Yes</td> <td>Yes</td> </tr> <tr> <td>Burn In test</td> <td>Approved procedure</td> <td>Yes</td> <td>Yes</td> </tr> <tr> <td>Efficiency</td> <td>Approved procedure</td> <td>Yes</td> <td>Yes</td> </tr> <tr> <td>Audible Noise Test</td> <td>Approved procedure</td> <td>Yes</td> <td>Yes</td> </tr> <tr> <td>Fuse Clearing Capability</td> <td>Approved procedure</td> <td>Yes</td> <td>Yes</td> </tr> <tr> <td>Total harmonic content</td> <td>Approved procedure/CIGRE's</td> <td>Yes</td> <td>Yes</td> </tr> <tr> <td>Radio Frequency interference</td> <td>IEC-CISPR22, IEC-61000-</td> <td>Yes</td> <td>Yes</td> </tr> </table>	Degree of protection test	IS-13947	Yes	Yes	Short circuit current capability	Approved procedure	Yes	Yes	Voltage Proof Test	UL 950, IEC950	Yes	Yes	Burn In test	Approved procedure	Yes	Yes	Efficiency	Approved procedure	Yes	Yes	Audible Noise Test	Approved procedure	Yes	Yes	Fuse Clearing Capability	Approved procedure	Yes	Yes	Total harmonic content	Approved procedure/CIGRE's	Yes	Yes	Radio Frequency interference	IEC-CISPR22, IEC-61000-	Yes	Yes		
Degree of protection test	IS-13947	Yes	Yes																																					
Short circuit current capability	Approved procedure	Yes	Yes																																					
Voltage Proof Test	UL 950, IEC950	Yes	Yes																																					
Burn In test	Approved procedure	Yes	Yes																																					
Efficiency	Approved procedure	Yes	Yes																																					
Audible Noise Test	Approved procedure	Yes	Yes																																					
Fuse Clearing Capability	Approved procedure	Yes	Yes																																					
Total harmonic content	Approved procedure/CIGRE's	Yes	Yes																																					
Radio Frequency interference	IEC-CISPR22, IEC-61000-	Yes	Yes																																					
 <p>SINGRAULI STPP STAGE-III (1X500 MW) EPC PACKAGE</p>		<p>TECHNICAL SPECIFICATION SECTION - VI PART-B</p>	<p>SUB-SECTION-C-07 TYPE TEST REQUIREMENTS</p>	<p>PAGE 6 OF 10</p>																																				



Handwritten signature or initials at the bottom left of the page.

08587

CLAUSE NO.	TECHNICAL REQUIREMENTS					
				approved procedure		
18	CJC Box	Degree Of protection test	IS-13947	No	Yes	
19	Junction Box	Degree Of protection Test	IS-13947	No	Yes	
20	OPC Access Server, Data Exchange Server & Historical Data Access Server	OPC Compliance Testing		No	Yes (Self certification is also acceptable)	
	Conductivity Type Switch	Degree of protection test	IS-2147	No	No	
	Local Gauges	Degree of protection test	IS-2147	No	No	
	Process actuated Switches	Degree of protection test	IS-2147	No	No	
	Control Valves	CV test	ISA 75.02	No	Yes	
	PLCs	As per standard (Col 4)	IEC 1131	No	No	
	Flow Nozzle Orifice plates	Calibration	ASME PTC BS 1042	Yes	Yes	
<p>## The contractor shall submit for Employers approval the reports of all the type test as per latest IS-10918 carried out within last five years from the date of Bid opening and the test(s) should have been either conducted at an independent laboratory or should have been witnessed by a client. The complete type test reports shall be for any rating of Battery in a particular group based on plate dimensions being manufactured by supplier.</p> <p><b>Note:</b></p> <p>Type Tests are to be conducted only for the items, which are being supplied as a part of this Package.</p>						
SINGRAULI STPP STAGE-III (1X500 MW) EPC PACKAGE			TECHNICAL SPECIFICATION SECTION - VI PART-B		SUB-SECTION-C-07 TYPE TEST REQUIREMENTS	PAGE 10 OF 10



6  
97

~

**SUB-SECTION**

**QUALITY ASSURANCE**



09104


CLAUSE NO.		QUALITY ASSURANCE & TESTING										एनटीपीसी NTPC
TESTS	ITEMS											
		Dimensions (R)	Make, Model, Type, Rating (R)	Process / Electrical connection	Calibration (R)	Requirement as per standard (R)	WPS approval (A)	Non-destructive testing (R)	Calculation for accuracy (R)	Insulation Resistance (R)	IBR Certification as applicable (R)	Hydro test (R)
15.	Cold junction compensation box	Y	Y	Y	Y					Y		
16.	Orifice plate (BS-1042)	Y	Y	Y	Y *	Y	Y **	Y **			Y	Y *
17.	Flow nozzle (BS-1042)	Y	Y	Y	Y *	Y	Y	Y			Y	Y
18.	Impact head type element	Y	Y	Y					Y			Y
19.	Level transmitter/float type switch	Y	Y	Y	Y					Y	Y	Y
20.	Flue Gas analyser	Y	Y	Y	Y							
21.	Dust emission monitors	Y	Y	Y	Y							
*Calibration to be carried out on one flow element of each type and size if calibration carried out as type test same shall not be repeated.												
** If applicable												
R-Routine Test      A- Acceptance Test      Y – Test applicable												
Note: 1) Detailed procedure of Environmental stress screening test shall be as per Quality Assurance Programme in General Technical Conditions												
2) This is an indicative list of tests/checks. The manufacturer is to furnish a detailed quality plan indicating the Practices and Procedure adopted alongwith relevant supporting documents.												

SINGRAULI STPP STAGE-III  
(1X500 MW)  
EPC PACKAGE

TECHNICAL SPECIFICATION  
SECTION-VI  
PART-B

SUB-SECTION-E-51  
MEASURING  
INSTRUMENTS (PRIMARY  
& SECONARY)  
(CW SYSTEM)


PAGE  
2 OF 2



09105

**SUB-SECTION - E-52**

**PROCESS CONNECTION AND  
PIPING**



09106



## Process Control & Piping

ITEMS	Visual	GA, BOM, Layout of component & construction feature	Dimension	Paint Shade/thickness	Flattening,flaring,hydrotest,hardness check as per ASTM standard (A)	Component Ratings	Wiring	Make, Model, Type, Rating	IR & HV	Review of TC for instrument/devices (R)	Accessibility of TBs/Devices	Illumination,grounding	Tubing	Leak/hydro test(A)	Chemical/physical properties of material (A)	Proof pressure test,Dismantling & reassembly test,Hydraulic impulse and Vibration test (R)	Tests as per standards & specification
Local Instrument enclosure	Y	Y	Y	Y		Y	Y	Y	Y	Y	Y	Y	Y				
Local instruments racks	Y	Y	Y	Y		Y	Y	Y	Y	Y	Y	Y	Y				
Junction Box	Y	Y	Y	Y*		Y	Y	Y	Y	Y							
Gauge Board	Y	Y	Y	Y		Y	Y	Y	Y	Y			Y				
Impulse pipes and tubes	Y	Y	Y	Y	Y			Y	Y					Y			
Socket weld fittings ANSI B-16.11	Y		Y					Y	Y					Y			Y
Compression fittings	Y		Y					Y						Y			
Instrument valves & Valve manifolds	Y		Y					Y						Y			
Copper tubings ASTM B75	Y							Y									Y

\*-applicable for painted junction boxes.  
 Note: R-Routine Test      A- Acceptance Test  
 Note: This is an indicative list of tests/checks. The manufacturer is to furnish a detailed quality plan, indicating the Practices and Procedure adopted along with relevant supporting documents.

Y - Test applicable


SINGRAULI STPP STAGE-III (1X500 MW) EPC PACKAGE	TECHNICAL SPECIFICATION SECTION VI PART-B	SUB-SECTION-E-52 PROCESS CONNECTION & PIPING (CW SYSTEM)	PAGE 1 OF 1
---	---	--	-------------



09117


**SUB-SECTION - E-57**

**ELECTRICAL ACTUATORS WITH  
INTEGRAL STARTERS**



09118

CLAUSE NO.	QUALITY ASSURANCE													एनटीपीसी NTPC	
<b>ELECTRICAL ACTUATOR WITH INTEGRAL STARTER</b>															
Test/Attributes  Characteristics           ITEM/ COPONENT/ SUB SYSTEM ASSEMBLY/ TESTING	RPM @	No Load Current @	IR & HV Test@	Mounting Dimension@	All routine Test as per Standard & Specification@	Correct Phase Sequence@	Operation & Setting of limit Switch/Torque Switch@	Stall Torque/Current (A)	Hand Wheel operation/ Auto de clutch function (A)	Function of Aux. like Potentiometer, space heater, position indicator @	EPT output @	Grease leakage @	Local/ Remote ( Open-Stop-Close) Operation@ Safety check (Single phasing, Phase correction, Tripping etc.) (A)		
	<b>ELECTRICAL ACTUATOR WITH INTEGRAL STARTER(IS 9334)</b>														
	Motor	Y	Y	Y	Y	Y									
	Final Testing	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	
	Note: 1) Detailed procedure of Environmental Stress Screening test shall be as per Quality Assurance Programme in General Technical Conditions 2) This is an indicative list of tests/checks. The manufacturer is to furnish a detailed quality plan indicating the practices and procedure adopted along with relevant supporting documents.														
	@ - Routine Test                      (A) - Acceptance Test                      Y - Test applicable														
	SINGRAULI STPP STAGE-III (1X500 MW) EPC PACKAGE	TECHNICAL SPECIFICATION SECTION - VI PART-B	SUB-SECTION-E-57 ELECTRICAL ACTUATORS (CW SYSTEM)	PAGE 1 OF 1											



# **SUB-SECTION**

**DOCUMENTS TO BE SUBMITTED  
AFTER AWARD OF CONTRACT**

**LIST OF DELIVERABLES OF PEM - C&I DEPARTMENT FOR Self Cleaning Strainer system  
(1 X 500 MW FGUTPP)**

**DOCUMENT NUMBER PE-GL-401-165-I100 SHEET 1 of 1**

<b>SI.No.</b>	<b>DRAWING NO.</b>	<b>DRAWING/DOCUMENT TITLE</b>	<b>CATEGORY</b>
1	PE-V0-401-165-I912	CONTROL & OPERATIONAL WRITE-UP FOR THE SYSTEM	A
2	PE-V0-401-165-I913	CONTROL SCHEME/LOGIC DIAGRAM(TO BE IMPLEMENTED IN DDCMIS)	A
3	PE-V0-401-165-I914	HMI PICTURES/PLANT SCHEMATICS	A
4	PE-V0-401-165-I915	INSTRUMENT SCHEDULE	A
5	PE-V0-401-165-I916	I/O LIST (ANALOG & BINARY)	A
6	PE-V0-401-165-I917	DRIVE LIST/SOLENOID/ACTUATOR VALVE LIST WITH LOCATION DATA	A
7	PE-V0-401-165-I918	FIELD JB TERMINATIONS	A
8	PE-V0-401-165-I919	DATASHEETS FOR INSTRUMENTS, JBs, etc.	A
9	PE-V0-401-165-I920	QUALITY PLANS ( INSTRUMENTS)	A
13	PE-V0-401-165-I921	CABLE SCHEDULE & INTERCONNECTION	A
14	PE-V0-401-165-I922	ANNUNCIATION & SOE LIST	A

**NOTES:**

1. ANY OTHER DOCUMENT DECIDED DURING DETAILED ENGINEERING SHALL BE PROVIDED BY BIDDER WITHOUT ANY COMMERCIAL/TECHNICAL IMPLICATION.

2. CONTRACTOR TO SUBMIT REUSABLE DATABASE FORMATS IN BHEL/NTPC APPROVED FORMATS LIKE MS EXCEL,MS ACCESS OF DOCUMENTS LIKE INSTRUMENT SCHEDULE, I/O LIST, DRIVE LIST,FIELD JB TERMINATIONS, CABLE SCHEDULE & INTERCONNECTION, etc.  
SOFT COPY OF FORMATS SHALL BE PROVIDED TO SUCCESSFUL BIDDERS.