

Bharat Heavy Electricals Limited
Ramachandrapuram Hyderabad 502 032
Township Administration
PRICE BID - PART - B

OT-06 ITEM 02

Name of work: Providing vitrified tile to all Type-V quarters in NH-VI area.

SL.NO	Description	Total Qty	Unit	Rate	Amount
PART-A (CIVIL WORKS)					
1	Laying of vitrified Floor Tiles laid with cement based high polymer modified quick-set tile adhesive (water based) conforming to IS:15477 using not less than 5 kg. adhesive per Sq.M of tile area, in average 3 mm to 10 mm thickness and hacking the existing surface, cleaning the surface with water, grouting the joints with pigment in wet condition, including, loading, unloading and conveyance to site all as directed by Engineer-in-charge. (Tiles & adhesive, color grout will be issued free of cost from BHEL store).	4785.00	One Sqm	97.87	468298.33
2	Removing dry or oil bound distemper water proofing cement paint and the like by scrapping sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete	7250.00	Sqm	4.25	30812.50
3.a	Distemping with 1st quality acrylic washable distemper (ready mixed) of approved manufacturer and of required shade and colour complete as per manufacturer's specification to give an even shade old work (two or more coats)	5033.04	One Sqm	23.55	118528.02
3.b	Distemping with oil bound washable distemper of approved brand and manufacturer and of required shade and colour complete as per manufacturer's specification to give an even shade old work (one or more coats)	11743.75	One Sqm	14.90	174981.92
4	Dismantling the existing plastering in walls and ceilings and disposal up to a distance of 2 kms. Lead, the following including the cost of labour, tools, transport etc. all complete all as directed by Engineer-in-charge.	580.00	One Sqm	8.74	5070.10
5	Plastering in cement mortar 1:6, 20 mm thick including curing, cost of all materials etc, complete all as directed by Engineer-in-charge. (Cement will be free issue free of cost from BHEL store)	435.00	One Sqm	65.87	28652.58
6	Plastering in cement mortar 1:3, 6 mm thick including curing, cost of all materials etc, complete all as directed by Engineer-in-charge. (Cement will be free issue free of cost from BHEL store)	290.00	One Sqm	42.99	12467.85
Total					838811.31

Tender %	In words	Figures
Excess		
Less		
Estimate		

Notes	
1	A penalty of 0.5% of the gross value of work will be levied for every week's delay of work subject to a maximum penalty of 10% of the gross value of work.
2	The tender % age quoted by the contractor shall be inclusive of all taxes and duties other than service tax as applicable from time to time.
3	Service tax if paid by the contractor with respect to this work will be reimbursed by BHEL on production of documentary evidence for having paid the service tax by the contractor.
4	All the bills of the contractors will be cleared subject to the production of clearance certificate by the contractors in respect of compliance of all statutory requirement, issued by IR section of HR department BHEL.
5	The agency shall submit the I.R. clearance certificate for the above work and arrange to get the final bill sent to Finance within one month from the actual date of completion of work.
6	The maintenance period of the work is 12 months. The security deposit will be released after satisfactory completion of the work and after getting I.R clearance and payment of final bill.

Signature of the Contractor

Issuing Authority