

TENDER SPECIFICATION

NO: BHE/PW/PUR/DHJRI-ENB/1322

FENCING OF OPEN STORAGE YARD (10,000 SQM) WITH GATE, CLOSED STORAGE SHED FOUNDATION UPTO FFL (15X60M) ETC. INCLUDING ITS INTERNAL/EXTERNAL ELECTRIFICATION, ASSOCIATED CIVIL WORK OF PORTA CABIN COMPLEX.

FOR

3 X 90.3 MW STG PACKAGE OF RUPPL DMD DAHEJ CCPP PROJECT

AT

TALUKA : VAGRA,

RELIANCE UTILITIES AND POWER PVT. LTD

DIST- Bharuch

GUJARAT

VOLUME:II – PRICE BID-1322



BHARAT HEAVY ELECTRICALS LIMITED

(A GOVERNMENT OF INDIA UNDERTAKING)

POWER SECTOR - WESTERN REGION

SHREEMOHINI COMPLEX

345, KINGSWAY - NAGPUR 440 001

BHARAT HEAVY ELECTRICALS LIMITED

(A GOVERNMENT OF INDIA UNDERTAKING)

POWER SECTOR - WESTERN REGION

SHREEMOHINI COMPLEX

345, KINGSWAY - NAGPUR 440 001

TENDER SPECIFICATION

NO: BHE/PW/PUR/DHJRI-ENB/1322

FENCING OF OPEN STORAGE YARD (10,000 SQM) WITH GATE, CLOSED STORAGE SHED FOUNDATION UPTO FFL (15X60M) ETC. INCLUDING ITS INTERNAL/EXTERNAL ELECTRIFICATION, ASSOCIATED CIVIL WORK OF PORTA CABIN COMPLEX.

FOR

3 X 90.3 MW STG PACKAGE OF RUPPL DMD DAHEJ CCPP PROJECT

AT

TALUKA : VAGRA,

RELIANCE UTILITIES AND POWER PVT. LTD

DIST- Bharuch

GUJARAT

EARNEST MONEY DEPOSIT: Please see Notice Inviting Tender.

LAST DATE FOR: Please see Notice Inviting Tender.

TENDER SUBMISSION:

THESE TENDER SPECIFICATION DOCUMENTS CONTAINING **VOLUME-I-Tech Bid**, **VOLUME- II-Price Bid** AND **VOLIME-IBCD Rev-03** ARE ISSUED TO:

M/s.

PLEASE NOTE:

THESE TENDER SPECS DOCUMENTS ARE NOT TRANSFERABLE.

For Bharat Heavy Electricals Limited

AGM (Purchase)

Place: Nagpur

Date:

PRICE BID FOR ENABLING WORKS : FENCING OF OPEN STORAGE YARD WITH GATES, CONSTRUCTION OF CLOSED STORAGE SHED AND ITS INTERNAL ELECTRIFICATIONS ETC. ALL COMPLETE AT DAHEJ							
SECTION	SL.NO	DESCRIPTION OF WORK	UNIT	QTY	RATE IN FIGURES (In Rs)	RATE IN WORDS (In Rs)	TOTAL AMOUNT (In Rs)
SECTION - A: NAME OF WORK: FENCING OF OPEN STORAGE YARD OF AREA 10,000 SQM WITH GATE							
Sec. A	1	PROVIDING AND FIXING BARBED WIRE FENCING AROUND OPEN STORAGE YARD AS PER BHEL DRAWING. POSTS SHALL BE SPACED AT 3M CENTRES AND STRUTS AT 30M CENTRES AND AT ALL TURNINGS WITH FOUNDATIONS, SUPPLYING AND FIXING GI BARBED WIRES, 10 HORIZONTAL LINES, TWO DIAGONALS BETWEEN POSTS BY MEANS OF GI STAPLES AS PER STANDARD PRACTICE. THE BARBED WIRE SHALL CONFORM TO IS 278 AND BE MADE OF TWO STRANDS OF GALVANISED TWISTED 2.5MM DIA (12.5 GAUGE) STEEL WIRE WITH FOUR POINT BARS. RATE QUOTED SHALL BE INCLUSIVE OF EXCAVATION, DISPOSAL OF SURPLUS EARTH, CONCRETE (1:3:6), FORM WORK AND ALL MATERIALS, COST OF POSTS, BARBED WIRES, TRANSPORTING, FIXING IN POSITION ETC. INCLUDING COST OF ALL LABOUR AND TWO COATS OF ENAMEL PAINT OF APPROVED SHADE WITH A SHOP COAT OF PRIMER IN ALL STRUCTURAL MEMBERS ETC COMPLETE.	RM	400			
Sec. A	2	SUPPLY FABRICATION, AND FIXING IN POSITION OF MS GATES WITH STRUCTURAL/TUBULAR STEEL FRAMES AS PER BHEL DRAWING INCLUDING COST OF FOUNDATION & POSTS, PAINTING TWO COATS BY SYNTHETIC ENAMEL PAINT OF APPROVED COLOUR AND QUALITY OVER ONE COAT OF RED OXIDE PRIMER, COST OF ALL MATERIALS, LABOUR, TRANSPORT ETC. COMPLETE.	MT	1			
Sec. A		TOTAL VALUE OF SECTION-A IN Rs.					
SECTION B:-ASSOCIATED CIVIL WORK OF PORTA CABIN							
Sec. B		SANITATION OF PORTA CABIN COMPLEX					
Sec. B	1(A)	EARTH WORK EXCAVATION FROM 0 (ZERO) TO 2 M DEPTH IN ALL KINDS OF SOIL (EXCEPT SOFT ROCK AND HARD ROCK) FOR SEPTIC TANK, SOAK PIT, FOUNDATION, BRICK KERB WALL AND WHEREVER REQUIRED ETC., AS DIRECTED BY BHEL ENGINEER INCLUDING REMOVING THE EXCAVATED MATERIALS UP TO A DISTANCE OF 50M. DEWATERING (BOTH GROUND WATER AS WELL AS RAIN WATER) AND KEEP THE AREA DRY TILL COMPLETION OF ALL THE WORKS, LABOURS, MATERIALS AND REQUIRED T&Ps ETC. COMPLETE.	M3	10			
Sec. B	1(E)	SUB GRADE PREPARATION: CUTTING LEVELLING, FILLING WITH EXCAVATED EARTH, WATERING AND CONSOLIDATION WITH 8-10 MT POWER ROLLER TO ACHIVE REQUIRED DENSITY (90% OF PROCTOR DENSITY) FOR OFFICE OFFICE COMPLEX AREA, BEFORE LAYING THE PCC WITH ALL T&P, LABOURS, MATERIALS ETC. COMPLETE.	M2	140			
Sec. B	2	DISPOSAL OF EXCAVATED EARTH/ROCK (NOT SUITABLE FOR BACK FILLING) BEYOND INITIAL LEAD OF 50M AND UPTO A MAXIMUM LEAD OF 2 KM OR PART THEREOF INCLUDING LOADING, UNLOADING , TRANSPORTING AND SPREADING AS PER DIRECTION OF BHEL ENGINEER .	M3	7			
Sec. B	3	BACKFILLING OF RAISED PLATFORM FOR PLACEMENT OF OFFICE , PANTRY AND TOILET BLOCK ETC AND WHEREVER REQUIRED IN REQUIRED THICKNESS (LAYERS NOT EXCEEDING 150MM THICK). INCLUDING WATERING AND CONSOLIDATING WITH 8-10 MT POWER ROLLER ETC. COMPLETE AS PER STANDARD SPECIFICATION AND INSTRUCTED BY BHEL ENGINEER.					
Sec. B	A	WITH GOOD EXCAVATED SOIL AVAILABLE FROM THE EARTH WORK AND LEAD UP TO 200 M.	M3	3			

PRICE BID FOR ENABLING WORKS : FENCING OF OPEN STORAGE YARD WITH GATES, CONSTRUCTION OF CLOSED STORAGE SHED AND ITS INTERNAL ELECTRIFICATIONS ETC. ALL COMPLETE AT DAHEJ							
SECTION	SL.NO	DESCRIPTION OF WORK	UNIT	QTY	RATE IN FIGURES (In Rs)	RATE IN WORDS (In Rs)	TOTAL AMOUNT (In Rs)
Sec. B	4	PROVIDING & FILLING IN SOAK PIT WITH BRICK BATS 40-80MM INCLUDING SAND PACKING ETC. COMPLETE, AS PER STANDARD SPECIFICATION AND INSTRUCTED BY BHEL ENGINEER.	M3	3.00			
Sec. B	5	PROVIDING AND LAYING OF PLAIN CEMENT CONCRETE OF MIX 1:4:8 USING OPC GRADE 43/53, 20 MM DOWN SIZE HARD BROKEN GRANITE STONE JELLY WITH TROWEL FINISH FOR RAISED PLATFORM, WALK WAY / FOOT PATH OF OFFICE AND WHEREVER REQUIRED ETC. INCLUDING SHUTTERING, FINISHING, CURING, CONSOLIDATION ETC. COMPLETE AS PER STANDARD SPECIFICATIONS AND AS DIRECTED BY BHEL ENGINEER.	M3	2			
Sec. B	6	PROVIDING AND LAYING OF RCC MIX 1:2:4 USING OPC GRADE 43/53, 20MM DOWN SIZE HARD BROKEN GRANITE STONE AGGREGATE FOR ROOF SLAB OF PANTRY AND TOILET BLOCK, SLAB OF SEPTIC TANK ETC AND WHEREVER REQUIRED AS PER DRAWING AND SPECIFICATION AND DIRECTED BY BHEL ENGINEER INCLUDING MECHANICAL MIXING, VIBRATION, CURING, FORM WORK & CENTERING BUT EXCLUDING COST OF REINFORCEMENTS.	M3	2			
Sec. B	7	PROVIDING, CUTTING, BENDING AND FIXING IN POSITION REINFORCEMENT OF VARIOUS DIA. USING HIGH TENSILE TOR STEEL (Fe - 415/500) FOR ROOF SLAB OF PANTRY AND TOILET BLOCK, SLAB OF SEPTIC TANK ETC AND FOR WHEREVER REQUIRED AS PER DRAWING AND SPECIFICATION AND AS DIRECTED BY BHEL ENGINEER INCLUDING COST OF ALL MATERIALS, LEADS, LIFT, LABOURS, MS BINDING WIRE 18/20 GAUGE, TACK WELDING AND SUPPORTING IF REQUIRED COMPLETE.	MT	0.34			
Sec. B	8 (A)	PROVIDING BRICK WORK IN CM 1:6 (1 CEMENT & 6 COARSE SAND) USING OPC GRADE 43/53 AND FLY ASH LIME BRICKS (FAL - MIN STRENGTH 35 KG/CM ²) AS PER DRAWING AND SPECIFICATION FOR FOUNDATION, WALL ETC. INCLUDING COST OF ALL MATERIALS, LABOUR, SCAFFOLDING, CURING, AT ALL ELEVATIONS AND LEVELS, RAKING OUT JOINTS ETC. COMPLETE AND AS DIRECTED BY ENGINEER. EXCLUDING PLASTERING & PAINTING.	M3	8			
Sec. B	9	PROVIDING PLASTERING WITH CEMENT MORTAR -1:6 (1 CEMENT & 6 COARSE SAND) USING OPC GRADE 43/53 OVER BOTH INTERNAL AND EXTERNAL FACES OF BRICKWORK AND CONCRETE SURFACES, PARTITION WALLS ETC. AT ALL LEVELS INCLUDING PREPARING THE SURFACE, RAKING JOINTS, SCAFFOLDING, CURING, COST OF ALL MATERIALS, LABOUR ETC. COMPLETE.					
Sec. B	B	INTERNAL PLASTERING -12MM THICK	M2	24			
Sec. B	10	PROVIDING AND FIXING OVER HEAD HYDRAULIC DOOR CLOSER (HEAVY DUTY) OF APPROVED BRAND AND SIZE ON NECESSARY DOORS AS DIRECTED BY BHEL ENGINEER.	NO.	1			
Sec. B	11	PROVIDING AND FIXING WHITE GLAZED VITREOUS CHINA WASH HAND BASIN OF 55 CM X 40 CM SIZE INCLUDING COLD WATER PILLER TAP, BRACKETS, STOP TAP, CHROMIUM PLATED BOTTLE TRAP AND NECESSARY PIPE CONNECTIONS INCLUDING UPVC WASTE PIPE AND TRAP UPTO THE OUT SIDE FACE OF THE WALL, MAKING GOOD THE DAMAGED SURFACE, TESTING ETC. COMPLETE. PRIOR APPROVAL OF SAMPLE AND BRAND BY BHEL ENGINEER IS NECESSARY BEFORE USE.	NO	1			

PRICE BID FOR ENABLING WORKS : FENCING OF OPEN STORAGE YARD WITH GATES, CONSTRUCTION OF CLOSED STORAGE SHED AND ITS INTERNAL ELECTRIFICATIONS ETC. ALL COMPLETE AT DAHEJ							
SECTION	SL.NO	DESCRIPTION OF WORK	UNIT	QTY	RATE IN FIGURES (In Rs)	RATE IN WORDS (In Rs)	TOTAL AMOUNT (In Rs)
Sec. B	12	PROVIDING AND FIXING IN POSITION OF WHITE GLAZED EARTHENWARE FLAT BACK/CORNER TYPE LIPPED FRONT URINALS OF 430MM X 260MM X 350MM / 340X460X265 MM OF APPROVED MAKE AND QUALITY WITHOUT FLUSHING CISTERN, GI FLUSH PIPE AND SPREADERS WITH BRASS UNIONS, GI CLAMPS, CUTTING OF WALLS AND MAKING GOOD OF ALL DAMAGES AND FINISHING TO MATCH THE EXISTING WORK ETC. COMPLETE. RATE QUOTED SHALL INCLUDE COST OF ALL MATERIALS AND LABOUR FOR CARRYING, LAYING & FIXING AND ALL OTHER INCIDENTAL CHARGES ETC. COMPLETE.	NO	1			
Sec. B	13	PROVIDING AND FIXING IN POSITION OF HIGH CLASS BELGIUM OR SUPERIOR MAKE BEVELLED EDGE MIRROR OF SIZE 450MM X 550MM X 6MM WITH 16 MM DIA & 550MM LENGTH NICKEL PLATED TOWEL ROD MOUNTED ON 6 MM THICK PLYWOOD OR PLASTIC FOLDER SHEET. RATE TO INCLUDE COST OF ALL MATERIALS, LABOUR FOR FIXING THE WOODEN PLUGS WITH CP BRASS SCREWS AND WASHERS ETC. COMPLETE.	NO	1			
Sec. B	14	PROVIDING AND FIXING IN POSITION OF 15 MM DIA CONCUSSION PUSH BUTTON TYPE BRASS/ GUN MATEL SELF CLOSING TAP INCLUDING NECESSARY SOCKET,TESTING ETC COMPLETE FOR URINALS AS DIRECTION OF BHEL ENGINEER.	NO	2			
Sec. B	15	PROVIDING AND FIXING IN POSITION OF 15 MM DIA NOMINAL SIZE SCREW DOWN TYPE CHROMIUM PLATES BRASS BIB COCKS OF STANDARD TYPE OF APPROVED MAKE AND QUALITY (LEADER MAKE OR EQUIVALENT) AS PER STANDARD SPECIFICATION. RATE INCLUDES JOINTING MATERIALS, SOCKETS, UNION NUT, TESTING, LABOURS FOR CARRYING AND FIXING ETC. COMPLETE.	NO	3			
Sec. B	16	PROVIDING AND FIXING IN POSITION OF 25 MM DIA GATE VALVE INCLUDING ALL NECESSARY FITTING & FIXTURE ETC. COMPLETE AS PER STANDARD SPECIFICATION.	NO	1			
Sec. B	17	PROVIDING AND FIXING IN POSITION OF 40 MM DIA GATE VALVE INCLUDING ALL NECESSARY FITTING & FIXTURE ETC. COMPLETE AS PER STANDARD SPECIFICATION.	NO	1			
Sec. B	18	PROVIDING AND FIXING IN POSITION OF 100MM X 50MM HCI "NAHANI" TRAP WITH HCI GRATINGS, BENDS, CONNECTING PIECES OF CI PIPE UPTO OUTSIDE FACE OF THE WALL. MAKING GOOD THE DAMAGED SURFACE, TESTING ETC COMPLETE AS PER STANDARD SPECIFICATIONS. RATE TO BE ALL INCLUSIVES.	NO	1			
Sec. B	19	PROVIDING AND FIXING IN POSITION OF 150MM SALT GLAZED STONE WARE GULLY TRAP WITH HCI GRATINGS AND CI COVER OF SIZE 300X300 MM OF APPROVED MAKE (WEIGHT NOT LESS THAN 2 KG) AND QUALITY AS PER STANDARD SPECIFICATIONS. RATE TO BE ALL INCLUSIVE.	NO	2			
Sec. B	20	PROVIDING AND LAYING WITH REQUIRED GRADING & LEVELING IN TRENCHES MEDIUM GRADE (TYPE) GALVANISED IRON (GI) PIPE HAVING EMBOSSED ISI MARK ON IT, OF REQUIRED DIAMETER WITH SCREWED, SOCKETS, JOINTS, NECESSARY GALVANISED IRON FITTINGS SUCH AS SOCKETS, BACK NUTS, ELBOWS, BENDS, TEES, REDUCERS, ENLARGERS, PLUGS, CLAMPS ETC. INCLUDING ALL NECESSARY EXCAVATION, BACK FILLING, FIXING WITH CLAMPS, TESTING ETC. COMPLETE. (PRIOR APPROVAL OF SAMPLE AND BRAND BY BHEL ENGINEER IS NECESSARY BEFORE USE.)					

PRICE BID FOR ENABLING WORKS : FENCING OF OPEN STORAGE YARD WITH GATES, CONSTRUCTION OF CLOSED STORAGE SHED AND ITS INTERNAL ELECTRIFICATIONS ETC. ALL COMPLETE AT DAHEJ							
SECTION	SL.NO	DESCRIPTION OF WORK	UNIT	QTY	RATE IN FIGURES (In Rs)	RATE IN WORDS (In Rs)	TOTAL AMOUNT (In Rs)
Sec. B	A	40MM DIA	RM	40			
Sec. B	B	25MM DIA	RM	40			
Sec. B	C	20MM DIA	RM	40			
Sec. B	D	15MM DIA	RM	40			
Sec. B	21	PROVIDING AT WORKING SITE, CARRYING AND LOWERING INTO TRENCHES, LAYING TO PROPER ALIGNMENT, LEVEL AND GRADE, JOINTING WITH CM (1:1) AND TESTING OF JOINTS ETC. OF THE FOLLOWING SIZE OF SALT GLAZED STONEWARE PIPE INCLUSIVE OF ALL NECESSARY SPECIALS TARRED HEMP YARN AND ALL JOINTING MATERIALS COMPLETE AS PER STANDARD SPECIFICATIONS INCLUDING ALL NECESSARY EXCAVATION, BACKFILLING, DISPOSAL OF SURPLUS EARTH ,LEAD AND LIFT AS PER SITE CONDITIONS. RATE SHALL INCLUDE COST OF ALL MATERIALS, LABOUR CHARGES AND INCIDENTAL CHARGES ETC. COMPLETE.					
Sec. B	A	100MM DIA STONEWARE PIPELINE INCLUDING ALL SPECIALS COMPLETE.	RM	50			
Sec. B	22	PROVIDING AND FIXING IN POSITION OF PVC OVERHEAD WATER TANK OF SYNTEX OR ANY APPROVED MAKE OF FOLLOWING LITRE CAPACITY WITH PROVISION FOR OVERFLOW ARRANGEMENT VALVES, INLET AND OUTLET ETC. COMPLETE.					
Sec. B	A	1000 LITRE CAPACITY	NO	1			
Sec. B	23	CONSTRUCTION OF 230MM THICK BURNT CLAY / FLY ASH LIME BRICK CHAMBER (USING OPC GRADE 43/53) OF THE FOLLOWING DIMENSIONS (INNER DIMENSION) WITH 20MM THICK INTERNAL & EXTERNAL CEMENT PLASTER OF MIX CM 1:5 (1 CEMENT & 5 COARSE SAND) , NEAT CEMENT FINISH , TOP CI – COVER AND CONNECTORS FOR SEWER LINES. RATE SHALL BE INCLUSIVE OF ALL NECESSARY EXCAVATION & FILLING, PCC-100 MM THICK OF 1:3:6 FOR BEDDING ON 100MM THICK OVERSIZER SOLING WITH 80 MM METALET. COMPLETE.					
Sec. B	A	600X450X450 WITH C.I COVER	NO	2			
Sec. B	B	900X600X450 WITH C.I. COVER	NO	3			
Sec. B	24	PROVIDING AND FIXING OF PRECAST 80 MM THICK RCC COVER OF MIX 1:1.5:3 FOR MAN HOLES OF VARIOUS SIZES WITH REINFORCEMENT OF 10 MM DIA BOTH WAY TIED WITH TACK WELDING @ 150 MM C/C WITH 2 HOOKS OF 12 MM DIA BARS ETC.COMPLETE.					
Sec. B	A	1050MM x 750MM	Nos.	1			
Sec. B	25	PROVIDING AND FIXING CHROMIUM PLATED TOWEL ROD 16 MM DIA. AND 75CM. IN LENGTH INCLUDING ALL ACCESSORIES COMPLETE. (PRIOR APPROVAL OF SAMPLE AND BRAND BY BHEL ENGINEER IS NECESSARY BEFORE USE).	NO.	1			
Sec. B	26	PROVIDING & FIXING OF LIQUID SOAP DISPENSER AT ALL WASH BASIN LOCATION.	NO.	1			

PRICE BID FOR ENABLING WORKS : FENCING OF OPEN STORAGE YARD WITH GATES, CONSTRUCTION OF CLOSED STORAGE SHED AND ITS INTERNAL ELECTRIFICATIONS ETC. ALL COMPLETE AT DAHEJ								
SECTION	SL.NO	DESCRIPTION OF WORK	UNIT	QTY	RATE IN FIGURES (In Rs)	RATE IN WORDS (In Rs)	TOTAL AMOUNT (In Rs)	
Sec. B	27	PROVIDING & FIXING IN POSITION OF CI VENT PIPE OF DIA. 100MM (APPROX. HT. 3M) IN SEPTIC TANK. RATE TO INCLUDE ALL NECESSARY FITTING & FIXTURE, LABOUR ETC.	RM	4				
Sec. B		TOTAL VALUE OF SECTION B--ASSOCIATED CIVIL WORK OF PORTA CABIN (IN Rs.)						
Sec. B		ELECTRIFICATION OF PORTA CABIN COMPLEX						
Sec. B	SL.NO	DESCRIPTION OF WORK	UNIT	QTY	RATE	AMOUNT	REMARK	
Sec. B	1	SUPPLY OF 415 VOLT AC , 3 PHASE /FOUR WIRE POWER FEEDER PILLAR BOARD , BOARD SHALL BE COMPRISES OF THREE NUMBER AND ONE NUMBER ALUMINIUM BUS BAR FOR PHASE & NEUTRAL RESPECTIVELY. BUS BAR RATING SHALL BE 200 AMPS AND SHALL BE MOUNTED ON EPOXY INSULATOR OF 1.1 KV GRADE, EACH BUS BAR SHALL HAVE DRILLED HOLE FOR CONNECTING INCOMING / OUT GOING CABLES, PROVISION FOR EARTHING THE PANEL ENCLOSURE. PANEL ENCLOSURE SHALL BE MADE OF SHEET METAL THICHNNES NOT LESS THAN 1.6 MM AND SUITABLE FOR OUT DOOR INSTALLATION, HINGED DOOR WITH LOCKING ARRAGEMENT , BASE FRAME , SHOULD HAVE SLOPPED CANOPY, DULY PAINTED WITH FIRST COAT WITH PRIMER AND TWO COATS OF SYNTHETIC ENAMEL PAINT (INTERIOR WITH WHITE PAINT AND EXTERIOR WITH SMOKE GREY AS PER IS), SUITABLE STOOL MADE OUT OF MS STRUCTURE OF 1.2 METER HIGH FOR MOUNTING OF PANEL WITH ANCHORING ARRAGEMENT AT FOUNDATION .	Set	1				
Sec. B	2	SUPPLY AND ERECTING STEEL TUBULAR SWAGED POLES, 9 MTR LONG MADE OF SHEET STEEL HAVING ULTIMATE TENSILE STRENGTH 42 KG F/SQ.MM CONFIRMING TO BIS :2713 (RPART-II) COMPLETE WITH 300X300X6 MM THICK M. S. BASE PLATE FOR WELDING AT SITE AND SIZE AS PER CONFIGURATION GIVEN IN BIS FOR 410 SP-28 (113 KG- POLE WEIGHT) WITH 1.5 MTR. DEEP EXACAVATION, CONCRETING IN 1:4:8 RATIO SIZE 45 CMS X 45 CMS X 150 CMS AND POLE PLINTH IN 1:3:6 CEMENT CONCRETING HAVING 300 MM HEIGHT AND 300 MM DIA .INCLUDING DOUBLE EARTHING OF POLE WITH SUITABLE ARRANGEMENT, DULY PAINTED WITH TWO COATS OF RED OXIDE PAINT AND ONE COAT OF ALUMINIUM PAINT TO BE APPLIED AFTER ERECTION; THE LENGTH OF POLE BELOW GROUND TO BE PAINTED WITH TWO COATS OF BLACK BITUMINUS PAINT. THE POLE SHALL BE COMPLETE WITH JB, FUSE AND MINOR FABRICATION AS BELOW : I) DRILING 20 MM DIA HOLE AT ABOUT 2.5 MTR FROM GROUND LEVEL FOR WIRE LEADS FROM JUNCTION BOX TO LIGHT FIXTURE . II) DRILING 15MM DIA HOLES AT ABOUT 0.7 AND AT 2.5 MTR FROOM GROUND LEVEL AND WELDING 12 MM NUTS FOR USING A 12 MM G.I BOLT FOR FASTENING EARTH CONDUCTERS. III) WELDING REQUIORED HOLES FOR FIXING POLE CAP OF STREET LIGHT BRACKET. IV) WELDING DIAMETRALLY 10 MM M.S. ROUND 30 MM BELOW POLE TOP EDGE FOR CLIPPING WIRE LEADS .	NOS.	1				
Sec. B	3	SUPPLYING, INSTALLATION & COMMISSIONING OF SODIUM VAPOUR LAMP STREET LIGHT FITTING 150 WATT SSG-2315 IH OF CROMPTON OR SIMILAR PHILIPS MAKE, COMPLETE WITH ONE PIECE CANOPY, INTEGRAL CONTROLGEAR COMPRISING OF COPPER WOUND CHOKE ,IGNITOR , HPF CAPACITOR, HPSV LAMP AND SUITABLE FOR DIRECTLY SLIPPING OVER LIGHT MOUNTING BRACKET MADE OUT OF 40 MM OD PIPE AND SUITABLE FOR LAMPS, CONTROL GEAR BOX CABLING & TERMINATION OF ITEMS SUPPLIED (TO BE MOUNTED ON 9 MTR POLE - ITEM NO. 2).	NOS.	2				
Sec. B	4	PROVIDING AND INSTALLING WIRING USING 2.5 SQ.MM COPPER CONDUCTOR THROUGH PVC CONDUIT OF REQUIRED SIZE WITH ACCESSORIES AND FIXTURES . WIRING SHALL BE CONCEALED TYPE FOR WHRERVER REQUIRED AS PER INSTRUCTED BY BHEL ENGINEER IN PVC CONDUIT OF REQUIRED SIZE.	PER POINT	5				

PRICE BID FOR ENABLING WORKS : FENCING OF OPEN STORAGE YARD WITH GATES, CONSTRUCTION OF CLOSED STORAGE SHED AND ITS INTERNAL ELECTRIFICATIONS ETC. ALL COMPLETE AT DAHEJ							
SECTION	SL.NO	DESCRIPTION OF WORK	UNIT	QTY	RATE IN FIGURES (In Rs)	RATE IN WORDS (In Rs)	TOTAL AMOUNT (In Rs)
Sec. B	5	PROVIDING AND INSTALLING WIRING FOR USING 4.0 SQ.MM COPPER CONDUCTOR THROUGH PVC CONDUIT OF REQUIRED SIZE WITH ACCESSORIES AND FIXTURES .WIRING SHALL BE CONCEALED TYPE FOR WHRERVER REQUIRED AS PER INSTRUCTED BY BHEL ENGINEER IN PVC CONDUIT OF REQUIRED SIZE.	PER POINT	5			
Sec. B	6	PROVIDING AND INSTALLING WIRING FOR USING 6.0 SQ.MM COPPER CONDUCTOR THROUGH PVC CONDUIT OF REQUIRED SIZE WITH ACCESSORIES AND FIXTURES .WIRING SHALL BE CONCEALED TYPE FOR WHRERVER REQUIRED AS PER INSTRUCTED BY BHEL ENGINEER IN PVC CONDUIT OF REQUIRED SIZE.	PER POINT	4			
Sec. B	7	PROVIDING AND INSTALLING WIRING FOR USING 16.0 SQ.MM COPPER CONDUCTOR THROUGH PVC CONDUIT OF REQUIRED SIZE WITH ACCESSORIES AND FIXTURES .WIRING SHALL BE CONCEALED TYPE FOR WHRERVER REQUIRED AS PER INSTRUCTED BY BHEL ENGINEER IN PVC CONDUIT OF REQUIRED SIZE.	PER POINT	4			
Sec. B	8	POVIDING AND INSTALLATION OF PLUG POINT OF 5A SOCKET (ANCHOR OR EQUIV.) OUTLET FOR WHRERVER REQUIRED AS PER INSTRUCTED BY BHEL ENGINEER INCLUDING WIRING TERMINATION.	NO	4			
Sec. B	9	POVIDING AND INSTALLATION OF PLUG POINT OF 15A SOCKET (ANCHOR OR EQUIV.) OUTLET FOR WHRERVER REQUIRED AS PER INSTRUCTED BY BHEL ENGINEER INCLUDING WIRING TERMINATION.	NO	4			
Sec. B	10	PROVIDING AND FIXING ORDINARY TUBELIGHT WITH FRAME OF STANDARD MANUFACTURER LIKE PHILIPS/BAJAJ OR EQUIVALENT AS APPROVED BY BHEL. THIS INCLUDES TUBE LIGHT FITTINGS , ALL NECESSARY ELECTRICAL FITTINGS (STARTER AND CHOCK ETC) ETC. COMPLETE.	NO.	7			
Sec. B	11	PROVIDING AND FIXING EXHAUST FANS 12" DIAMETER WITH FRAME OF STANDARD MANUFACTURER LIKE CROMPTAN GREEVES OR EQUIVALENT AS APPROVED BY BHEL.	NO.	2			
Sec. B	12	SUPPLY OF CABLES 3 -1/2 COREX 35 SQMM ALUMINIUM ARMoured PVC INSULATED CABLE (THREE AND HALF CORE) CONFIRMING TO IS 1554 (PART -I)	RM	150			
Sec. B	13	INSTALLATION OF CABLES 3 -1/2 COREX 35 SQMM ALUMINIUM ARMoured PVC INSULATED CABLE CONFIRMING TO IS 1554 (PART -I) INCLUDING LAYING OF CABLE BELOW GROUND , EXCAVATION OF TRENCH OF 600 MM DEPTH IN ALL KIND OF SOIL, TERMINATION OF CABLES CORES WITH CRIMP TYPE LUGGS, PROVIDING SAND LAYER BELOW/ ABOVE THE CABLE, BRICK LAYING BOTH SIDE /ABOVE THE ABOVE THE CABLE AND BACK FILLING ETC. CABLES ARE TO BE LAID FROM TRANSFORMER SUB STATION TO 415 VOLT AC DISTRIBUTION BOARD	RM	150			
		TOTAL value of Section B: ELECTRIFICATION OF PORTA CABIN COMPLEX (In Rs)					
Section B		GRAND TOTAL OF SECTION B (ELECTRIFICATION OF PORTA CABIN COMPLEX (In Rs) Plus ASSOCIATED CIVIL WORK OF PORTA CABIN) (In Rs)					

SECTION - C NAME OF WORK: CONSTRUCTION OF FOUNDATION UPTO FFL OF 1 Nos. - CLOSED STORAGE SHEDS (60 M X 15 M) FOUNDATION

PRICE BID FOR ENABLING WORKS : FENCING OF OPEN STORAGE YARD WITH GATES, CONSTRUCTION OF CLOSED STORAGE SHED AND ITS INTERNAL ELECTRIFICATIONS ETC. ALL COMPLETE AT DAHEJ							
SECTION	SL.NO	DESCRIPTION OF WORK	UNIT	QTY	RATE IN FIGURES (In Rs)	RATE IN WORDS (In Rs)	TOTAL AMOUNT (In Rs)
SECTION C	SL.NO	DESCRIPTION OF WORK	UNIT	QTY			
SEC C	1(A)	EARTH WORK EXCAVATION FROM 0 (ZERO) TO 2 M DEPTH IN ALL KINDS OF SOIL (EXCEPT SOFT ROCK AND HARD ROCK) FOR FOUNDATIONS, RAMPS ETC., AS DIRECTED BY BHEL ENGINEER INCLUDING REMOVING THE EXCAVATED MATERIALS UP TO A DISTANCE OF 50M, DEWATERING (BOTH GROUND WATER AS WELL AS RAIN WATER) AND KEEP THE AREA DRY TILL COMPLETION OF ALL THE WORKS, LABOURS, MATERIALS AND REQUIRED T&Ps ETC. COMPLETE.	M3	142			
SEC C	1(B)	EARTH WORK EXCAVATION FROM 0 (ZERO) TO 2 M DEPTH FOR SOFT ROCK AND HARD ROCK (BY MANUALLY OR MECHANICALLY BUT WITHOUT BLASTING) FOR FOUNDATIONS, RAMPS ETC., AS DIRECTED BY BHEL ENGINEER INCLUDING REMOVING THE EXCAVATED MATERIALS UP TO A DISTANCE OF 50M, DEWATERING (BOTH GROUND WATER AS WELL AS RAIN WATER) AND KEEP THE AREA DRY TILL COMPLETION OF ALL THE WORKS, LABOURS, MATERIALS AND REQUIRED T&Ps ETC. COMPLETE.	M3	18			
SEC C	1(C)	EARTH WORK EXCAVATION FROM 2.0M TO 4.0 M DEPTH IN ALL KINDS OF SOIL (EXCEPT HARD ROCK AND SOFT ROCK) FOR FOUNDATIONS, RAMPS ETC., AS DIRECTED BY BHEL ENGINEER INCLUDING REMOVING THE EXCAVATED MATERIALS UP TO A DISTANCE OF 50M, DEWATERING (BOTH GROUND WATER AS WELL AS RAIN WATER) AND KEEP THE AREA DRY TILL COMPLETION OF ALL THE WORKS, LABOURS, MATERIALS AND REQUIRED T&Ps ETC. COMPLETE.	M3	9			
SEC C	1(D)	EXCAVATION IN ALL KINDS OF SOIL INCLUDING SOFT & HARD ROCK (BY MANUAL CHISELING OR BY MECHANICAL MEANS BUT WITHOUT BLASTING) FROM 2 TO 4M DEPTH FOR FOUNDATIONS, RAMPS ETC WHEREVER REQUIRED INCLUDING REMOVING THE EXCAVATED MATERIALS UP TO A DISTANCE OF 50M, DEWATERING (BOTH GROUND WATER AS WELL AS RAIN WATER) AND KEEP THE AREA DRY TILL COMPLETION OF ALL THE WORKS, LABOURS, MATERIALS AND REQUIRED T&Ps ETC. COMPLETE.	M3	9			
SEC C	1(E)	SUB GRADE PREPARATION: CUTTING LEVELLING, FILLING USING EXCAVATED EART, WATERING AND CONSOLIDATION FOR PLINTH PROTECTION AREA BEFORE LAYING THE PCC WITH ALL T&P, LABOURS, MATERIALS ETC. COMPLETE.	M2	1134			
SEC C	2	DISPOSAL OF EXCAVATED EARTH/ROCK (NOT SUITABLE FOR BACK FILLING) BEYOND INITIAL LEAD OF 50M AND UPTO A MAXIMUM LEAD OF 2 KM OR PART THEREOF INCLUDING LOADING, UNLOADING , TRANSPORTING AND SPREADING AS PER DIRECTION OF BHEL ENGINEER .	M3	76			
SEC C	3	BACKFILLING OF FOUNDATION ,FLOORS AND PLINTH IN LAYERS NOT EXCEEDING I50MM THICK. INCLUDING WATERING AND CONSOLIDATING ETC. COMPLETE AS PER STANDARD SPECIFICATION AND INSTRUCTED BY BHEL ENGINEER.					
SEC C	A	WITH GOOD EXCAVATED SOIL AVAILABLE FROM THE EARTH WORK.	M3	309			

PRICE BID FOR ENABLING WORKS : FENCING OF OPEN STORAGE YARD WITH GATES, CONSTRUCTION OF CLOSED STORAGE SHED AND ITS INTERNAL ELECTRIFICATIONS ETC. ALL COMPLETE AT DAHEJ							
SECTION	SL.NO	DESCRIPTION OF WORK	UNIT	QTY	RATE IN FIGURES (In Rs)	RATE IN WORDS (In Rs)	TOTAL AMOUNT (In Rs)
SEC C	B	WITH GRANULAR MURUM IN LAYERS (THICKNESS OF EACH LAYER SHOULD NOT EXCEED 150MM) BELOW FOUNDATIONS AND RAMP AS PER STANDARD SPECIFICATION, RELEVANT DRAWINGS AND INSTRUCTED BY BHEL ENGINEER INCLUDING ROYALTY. CONTRACTOR HAS TO SUBMIT ROYALTY CERTIFICATE FROM CONCERNED STATE GOVT. MINING DEPARTMENT	M3	21			
SEC C	C	WITH GOOD EARTH BROUGHT FROM OUTSIDE FROM CONTRACTOR'S OWN SOURCE INCLUDING ROYALTY ETC.	M3	100			
SEC C	D	PROVIDING STONE SOLING OF REUIRED THICKNESS AS PER DRAWING BELOW FLOORING, RAMP, COLUMN FOUNDATIONS OF STORAGE SHED ETC. BY USING 80 MM SIZE HARD BROKEN BLACK GRANITE/QUARTZITE/GNEISS/TRAP STONE METAL INCLUDING GRANULAR MURRUM PACKING, WATERING & COMPACTION ETC COMPLETE.AS PER STANDARD SPECIFICATION AND INSTRUCTED BY BHEL ENGINEER	M3	242			
SEC C	4	PROVIDING AND LAYING OF PLAIN CEMENT CONCRETE OF MIX 1:4:8 USING OPC GRADE 43/53, 20 MM DOWN SIZE HARD BROKEN GRANITE STONE JELLY FOR FOUNDATION, FLOORING, COLUMN ETC. INCLUDING SHUTTERING, FINISHING, CURING, CONSOLIDATION ETC. COMPLETE AS PER STANDARD SPECIFICATIONS AND AS DIRECTED BY BHEL ENGINEER.	M3	12			
SEC C	5	PROVIDING AND LAYING OF 100 MM THICK PLAIN CEMENT CONCRETE OF MIX 1:3:6 USING OPC GRADE 43/53, 20 MM DOWN SIZE HARD BROKEN GRANITE STONE JELLY WITH TROWEL FINISH FOR PLINTH PROTECTION WITH TROWEL FINISH INCLUDING SHUTTERING, FINISHING, CURING, CONSOLIDATION ETC. COMPLETE AS PER STANDARD SPECIFICATIONS AND AS DIRECTED BY BHEL ENGINEER.	M3	12			
SEC C	6	PROVIDING AND LAYING OF RCC/CC MIX 1:2:4 USING OPC GRADE 43/53, 20MM DOWN SIZE HARD BROKEN GRANITE STONE AGGREGATE INCLUDING MECHANICAL MIXING, VIBRATION, CURING, FORM WORK & CENTERING AS PER DRAWING AND SPECIFICATION AND DIRECTED BY BHEL ENGINEER BUT EXCLUDING COST OF REINFORCEMENTS.	M3	96			
Sec. C	4(D)	PROVIDING AND LAYING OF RCC MIX 1:1.5:3 USING OPC GRADE 43/53 , 20MM DOWN SIZE HARD BROKEN GRANITE STONE 20MM DOWN SIZE HARD BROKEN GRANITE STONE JELLY WITH TROWEL FINISH FOR FOUNDATION ,RAFT COLOUM,PLINTH BEAM AND WHEREVER REQUIRED INCLUDING MECHANICAL MIXING, VIBRATION, CURING, FORM WORK & CENTERING AS PER DRAWING AND SPECIFICATION AND DIRECTED BY BHEL ENGINEER BUT EXCLUDING COST OF REINFORCEMENTS.	M3	49			
SEC C	7	PROVIDING AND LAYING DPC (DAMP PROOF COURSE) 50MM THICK IN 1:2:4 CEMENT CONCRETE LAYER USING OPC GRADE 43/53AND WITH 6MM DOWN AGGREGATE, INCLUDING FORMWRK, BITUMEN FELT USING CEMENT WITH WATER PROOFING COMPOUND ETC. COMPLETE	M2	36			

PRICE BID FOR ENABLING WORKS : FENCING OF OPEN STORAGE YARD WITH GATES, CONSTRUCTION OF CLOSED STORAGE SHED AND ITS INTERNAL ELECTRIFICATIONS ETC. ALL COMPLETE AT DAHEJ							
SECTION	SL.NO	DESCRIPTION OF WORK	UNIT	QTY	RATE IN FIGURES (In Rs)	RATE IN WORDS (In Rs)	TOTAL AMOUNT (In Rs)
SEC C	8	PROVIDING , CUTTING, BENDING AND FIXING IN POSITION REINFORCEMENT OF VARIOUS DIA. USING HIGH TENSILE TOR STEEL (Fe -415/500) FOR FOUNDATIONS, COLUMNS, BEAMS, FLOORS, SUNSHED, SLAB ETC. AS PER DRAWING AND SPECIFICATION AND AS DIRECTED BY BHEL ENGINEER INCLUDING COST OF ALL MATERIALS, LEADS, LIFT, LABOURS, MS BINDING WIRE 18/20 GAUGE, TACK WELDING AND SUPPORTING AS REQUIRED COMPLETE.	MT	3			
SEC C	9(B)	PROVIDING BRICK WORK IN CM 1:6 (1 CEMENT & 6 COARSE SAND) USING OPC GRADE 43/53 AND FLY ASH LIME BRICKS (MIN STRENGTH 35 KG/CM ²) AS PER DRAWING AND SPECIFICATION FOR FOUNDATION, WALL, SEPTIC TANK ETC. INCLUDING COST OF ALL MATERIALS, LABOUR, SCAFFOLDING, CURING , AT ALL ELEVATIONS AND LEVELS , RAKING OUT JOINTS ETC. COMPLETE AND AS DIRECTED BY ENGINEER . EXCLUDING PLASTERING & PAINTING.	M3	24			
SEC C	14	PROVIDING AND FIXING OF IPS FLOORING 40MM THICK USING OPC GRADE 43/53 WITH CEMENT CONCRETE 1:2:4 (USING 12 MM DOWN AGGREGATES) AS PER STANDARD PRACTICE IN PANELS OF SIZE NOT EXCEEDING 2.0 x 2.0 SQ.M BY PROVIDING, FIXING GLASS STRIPS.INCLUDING CURING & CLEANING.	M2	945			
SEC C	15	PROVIDING 2MM THICK NEAT CEMENT FINISH USING OPC GRADE 43/53 OVER CONCRETE BASE FOR FLOORING, PAVING ,PLASTERED SURFACE ETC.INCLUDING CURING & CLEANING AND SCAFFOLDING COMPLETE.	M2	945			
SEC C	16	PROVIDING PLASTERING WITH CEMENT MORTAR -1:6 (1 CEMENT & 6 COARSE SAND) USING OPC GRADE 43/53 OVER BOTH INTERNAL AND EXTERNAL FACES OF BRICKWORK AND CONCRETE SURFACES, PARTITION WALLS ETC. AT ALL LEVELS INCLUDING PREPARING THE SURFACE, RAKING JOINTS, SCAFFOLDING, CURING, COST OF ALL MATERIALS, LABOUR ETC. COMPLETE.					
SEC C		(i) EXTERNAL PLASTERING - 18MM THICK	M2	90			
SEC C		(ii) INTERNAL PLASTERING -12MM THICK	M2	47			
SEC C	17(A)	PROVIDING & APPLYING COLOUR WASH -THREE COATS ON NEWLY PLASTERED EXTERNAL SURFACE OF SHED BY USING BEST SHALL LIME TO GIVE AN EVEN SHADE INCLUDING PREPARING THE SURFACE LIKE CLEANING AND BRUSHING & BROOMING OF WALLS AND IN ACCORDANCE WITH STANDARD SPECIFICATION. RATE INCLUDE COST OF ALL MATERIALS , COLOURING AGENT, BASE COAT OF WHITE WASH,APPROVED ADHESIVE, SCAFFOLDING AT ALL LEVEL, BRUSH ETC. COMPLETE.	M2	90			
SEC C	17(B)	PROVIDING & APPLYING WHITE WASH - THREE COATS ON NEWLY PLASTERED INTERNAL SURFACE OF SHED BY USING BEST SHALL LIME TO GIVE AN EVEN SHADE INCLUDING PREPARING THE SURFACE LIKE CLEANING AND BRUSHING & BROOMING OF WALLS AND IN ACCORDANCE WITH STANDARD SPECIFICATION. RATE INCLUDE COST OF ALL MATERIALS , COLOURING AGENT, APPROVED ADHESIVE, SCAFFOLDING AT ALL LEVEL, BRUSH ETC. COMPLETE.	M2	47			

PRICE BID FOR ENABLING WORKS : FENCING OF OPEN STORAGE YARD WITH GATES, CONSTRUCTION OF CLOSED STORAGE SHED AND ITS INTERNAL ELECTRIFICATIONS ETC. ALL COMPLETE AT DAHEJ							
SECTION	SL.NO	DESCRIPTION OF WORK	UNIT	QTY	RATE IN FIGURES (In Rs)	RATE IN WORDS (In Rs)	TOTAL AMOUNT (In Rs)
Sec. C	12	SUPPLYING & FIXING IN POSITION MS FOUNDATION BOLTS WITH HEXAGONAL NUTS (3 NOS. NUTS WITH EACH BOLT) IN RCC COLUMNS OF PEB SHED FOUNDATION AS PER DRAWINGS & DIRECTION OF BHEL ENGINEER	MT	1			
SEC C	18	MANUFACTURING, SUPPLYING AND FIXING OF 20 GAUGE MS ROLLING SHUTTERS OF SIZE 5M X 5 M AS PER I.S. SPECIFICATIONS, COMPLETE, MECHANICALLY OPERATED FROM IN AND OUTSIDE BOTH AS INSTRUCTED BY BHEL ENGINEER INCLUDING TWO COATS OF SYNTHETIC ENAMEL PAINT OF APPROVED COLOUR AND QUALITY OVER ONE COAT OF RED OXIDE PRIMER LOCKING ARRANGEMENT. RATE SHALL BE INCLUSIVE OF ALL THE ABOVE COMPLETE.	M2	25			
SEC C		TOTAL VALUE OF SECTION-C IN Rs.					
SECTION D NAME OF THE WORK : INTERNAL ELECTRIFICATION WORK OF 1 NOS. CLOSED SHEDS (60M X 15M)							
SEC.	SL.NO	DESCRIPTION OF WORK	UNIT	QTY			
Sec. D	1	SUPPLYING & INSTALLING POWER DISTRIBUTION BOARD COMPLETE WITH: COMMON BOARD FOR ALL SHEDS. 1) INCOMING MCB TPH 100 AMPS. - 1 NO. 2) OUTGOING MCB TPH 32 AMPS. -3NOS. 3) RCCB DP 25/20 AMPS. - 2NOS. 4) OUTGOING MCB SP 6 AMPS - 6NOS. All RCCBs, MCBs SHALL BE MDS/INDO KOPP MAKE. DISTRIBUTION BOARDS SHALL BE SIEMENS / MDS / INDO KOPP MAKE WITH INTERNAL BUSBARS, INTERNAL WIRING, 2 NOS. EARTHING TERMINALS, EARTH CONNECTIONS, INCLUDING GLANDS, LUGS.	Set	1			
Sec. D	2	SUPPLYING & FIXING WALL MOUNTING TYPE LIGHTING PANELS, EACH WITH : (1) INCOMING MCB TPN -32 AMPS - 1NO. (2) RCCB DP 32 AMPS - 2NOS (3) MCB SP 6AMPS - 30 NOS.. All RCCBs, MCBs SHALL BE MDS/INDO KOPP MAKE. LIGHTING PANEL SHALL BE SIEMENS/MDS/INDO KOPP MAKE WITH INTERNAL BUSBARS, 2 NOS. EARTHING TERMINALS, EARTH CONNECTIONS, INCLUDING GLANDS, LUGS & WIRING FROM MAIN DB	Set	1			
Sec. D	3	PROVIDING AND INSTALLING WIRING USING 2.5 SQ.MM COPPER CONDUCTOR THROUGH PVC CONDUIT OF REQUIRED SIZE WITH ACCESSORIES AND FIXTURES .WIRING SHALL BE CONCEALED TYPE FOR COMPUTER ROOM, OFFICE SHED & FOR REST OF SHEDS OPEN AND WHRERVER REQUIRED IN PVC CONDUIT OF REQUIRED SIZE.	PER POINT	64			
Sec. D	4	PROVIDING AND INSTALLING WIRING FOR USING 4.0 SQ.MMCOPPER CONDUCTOR THROUGH PVC CONDUIT OF REQUIRED SIZE WITH ACCESSORIES AND FIXTURES .WIRING SHALL BE CONCEALED TYPE FOR COMPUTER ROMM, OFFICE SHED & FOR REST OF SHEDS OPEN AND WHRERVER REQUIRED IN PVC CONDUIT OF REQUIRED SIZE.	PER POINT	3			
Sec. D	5	PROVIDING AND INSTALLING WIRING FOR MAINS USING 6.00 SQ.MM COPPER CONDUCTOR OF ISI MAKE. USING CONCEALED TYPE WIRING/PVC CONDUIT OF REQUIRED SIZE.	PER POINT	3			

PRICE BID FOR ENABLING WORKS : FENCING OF OPEN STORAGE YARD WITH GATES, CONSTRUCTION OF CLOSED STORAGE SHED AND ITS INTERNAL ELECTRIFICATIONS ETC. ALL COMPLETE AT DAHEJ							
SECTION	SL.NO	DESCRIPTION OF WORK	UNIT	QTY	RATE IN FIGURES (In Rs)	RATE IN WORDS (In Rs)	TOTAL AMOUNT (In Rs)
Sec. D	6	PROVIDING AND INSTALLING WIRING FOR MAINS USING 16.00 SQ.MM COPPER CONDUCTOR OR ISI MAKE USING CONCEALED TYPE WIRING/PVC CONDUIT OF REQUIRED SIZE.	PER POINT	3			
Sec. D	7	PROVIDING AND INSTALLATION OF PLUG POINT OF 5A SOCKET (ANCHOR OR EQUIV.) OUTLET INCLUDING WIRING TERMINATION. THIS INCLUDES TUBE LIGHT FITTINGS ETC. COMPLETE.	NO	3			
Sec. D	8	PROVIDING AND INSTALLATION OF PLUG POINT OF 15A SOCKET (ANCHOR OR EQUIV.) OUTLET INCLUDING WIRING TERMINATION. THIS INCLUDES TUBE LIGHT FITTINGS V	NO	3			
Sec. D	9	PROVIDING AND FIXING ORDINARY TUBELIGHT WITH FRAME OF STANDARD MANUFACTURER LIKE PHILIPS/BAJAJ OR EQUIVALENT AS APPROVED BY BHEL. THIS INCLUDES TUBE LIGHT FITTINGS ETC. COMPLETE.	NO.	40			
Sec. D	10	PROVIDING AND FIXING CEILING FAN 48" DIAMETER OF APPROVED COMPANY SUCH AS CROMTAN GREEVES OR ANY OTHER STANDARD MANUFACTURER AS DIRECTED BY BHEL. THIS INCLUDES TUBE LIGHT FITTINGS ETC. COMPLETE.	NO	6			
Sec. D	11	PROVIDING AND FIXING CALLING BELLS (WITH INDICATOR LIGHT)	NO	1			
Sec. D	12	PROVIDING EARTHING PITS WITH 2 " DIA , 2 M LONG GI PIPES WITH FLANGE & GI WIRES WITH CHARCOAL, SALT AND AS PER THE STANDARD PRACTICE FOR ELECTRICAL CONNECTION.RATE SHALL BE INCLUSIVE OF ALL MATERIALS, LABOURS, ETC COMPLETE.	NO	1			
Sec. D	13	PROVIDING & FIXING ALUMINIUM DISPERSIVE LUMINAIRE ENAMELED GREEN AND WHITE WITH CAST ALUMINIUM FLANGE AND NIPPLE SUITABLE FOR USE WITH GLS LAMP, DOME 12" DIAMETER, WITH HANGING BRACKET AND 200W GLS LAMP OF CROMPTON OR EQUIVALENT BAJAJ/PHILIPS MAKE, COMPLETE.	Nos.	18			
Sec. D	14	WIRING WITH 2.5 SQ MM ISI MARK COPPER WIRE FOR ABOVE IN PVC CONDUIT ALONG WITH GI EARTH WIRE INCLUSIVE OF ALL MATERIAL, LABOUR ETC. COMPLETE	Per Point	3			
Sec. D	15	SUPPLY OF CABLES 2 CORE X 10 SQMM ALUMINIUM ARMoured PVC INSULATED CABLE CONFIRMING TO IS 1554 (PART -I)	RM	50			
Sec. D	16	INSTALLATION OF CABLES 2 CORE X 10 SQMM ALUMINIUM ARMoured PVC INSULATED CABLE CONFIRMING TO IS 1554 (PART -I) INCLUDING LAYING OF CABLE BELOW GROUND , EXCAVATION OF TRENCH OF 600 MM DEPTH IN ALL KIND OF SOIL, TERMINATION OF CABLES CORES WITH CRIMP TYPE LUGGS, PROVIDING SAND LAYER BELOW/ ABOVE THE CABLE, BRICK LAYING BOTH SIDE /ABOVE THE ABOVE THE CABLE AND BACK FILLING ETC COMPLETE. CABLES ARE TO BE LAID FROM 415 VOLT AC POWER FEEDER PILLAR BOARD BOARD TO LIGHTING POLES & POLE TO POLE	RM	50			
Sec. D	17	SUPPLY OF CABLES 3 -1/2 COREX 35 SQMM ALUMINIUM ARMoured PVC INSULATED CABLE (THREE AND HALF CORE) CONFIRMING TO IS 1554 (PART -I)	RM	30			

PRICE BID FOR ENABLING WORKS : FENCING OF OPEN STORAGE YARD WITH GATES, CONSTRUCTION OF CLOSED STORAGE SHED AND ITS INTERNAL ELECTRIFICATIONS ETC. ALL COMPLETE AT DAHEJ							
SECTION	SL.NO	DESCRIPTION OF WORK	UNIT	QTY	RATE IN FIGURES (In Rs)	RATE IN WORDS (In Rs)	TOTAL AMOUNT (In Rs)
Sec. D	18	INSTALLATION OF CABLES 3 -1/2 COREX 35 SQMM ALUMINIUM ARMoured PVC INSULATED CABLE CONFIRMING TO IS 1554 (PART -I) INCLUDING LAYING OF CABLE BELOW GROUND , EXCAVATION OF TRENCH OF 600 MM DEPTH IN ALL KIND OF SOIL, TERMINATION OF CABLES CORES WITH CRIMP TYPE LUGGS, PROVIDING SAND LAYER BELOW/ ABOVE THE CABLE, BRICK LAYING BOTH SIDE /ABOVE THE ABOVE THE CABLE AND BACK FILLING ETC. CABLES ARE TO BE LAID FROM TRANSFORMER SUB STATION TO 415 VOLT AC DISTRIBUTION BOARD	RM	30			
Sec. D	19	SUPPLY OF CABLES 3 -1/2 CORE X 95 SQMM ALUMINIUM ARMoured PVC INSULATED CABLE (THREE AND HALF CORE) CONFIRMING TO IS 1554 (PART -I)	RM	20			
Sec. D	20	INSTALLATION OF CABLES 3 -1/2 CORE X 95 SQMM ALUMINIUM ARMoured PVC INSULATED CABLE CONFIRMING TO IS 1554 (PART -I) INCLUDING LAYING OF CABLE BELOW GROUND, EXCAVATION OF TRENCH OF 600 MM DEPTH IN ALL KIND OF SOIL, TERMINATION OF CABLES CORES WITH CRIMP TYPE LUGGS, PROVIDING SAND LAYER BELOW/ ABOVE THE CABLE, BRICK LAYING BOTH SIDE /ABOVE THE ABOVE THE CABLE AND BACK FILLING ETC COMPLETE. CABLES ARE TO BE LAID FROM 415 VOLT AC DISTRIBUTION BOARD TO FEEDER PILLAR BOARD , FEEDER PILLAR BOARD TO LIGHTING MAST / TOWER.	RM	20			
Sec. D	21	SUPPLY OF CABLES 3 -1/2 COREX 185 SQMM ALUMINIUM ARMoured PVC INSULATED CABLE (THREE AND HALF CORE) CONFIRMING TO IS 1554 (PART -I)	RM	25			
Sec. D	22	INSTALLATION OF CABLES 3 -1/2 COREX 185 SQMM ALUMINIUM ARMoured PVC INSULATED CABLE CONFIRMING TO IS 1554 (PART -I) INCLUDING LAYING OF CABLE BELOW GROUND , EXCAVATION OF TRENCH OF 600 MM DEPTH IN ALL KIND OF SOIL, TERMINATION OF CABLES CORES WITH CRIMP TYPE LUGGS, PROVIDING SAND LAYER BELOW/ ABOVE THE CABLE, BRICK LAYING BOTH SIDE /ABOVE THE ABOVE THE CABLE AND BACK FILLING ETC. CABLES ARE TO BE LAID FROM TRANSFORMER SUB STATION TO 415 VOLT AC DISTRIBUTION BOARD.	RM	25			
Sec. D		TOTAL VALUE OF SECTION-D IN Rs.					

TOTAL SUMMARY OF PRICE BID- 1322

SECTION	PARTICULARS	TOTAL AMOUNTS (In Rs)
SECTION - A	Total of Section A - Fencing OF OPEN STORAGE YARD(10000 SQM) With Gate	
SECTION-B	Total of Section B- Associated civil work of Porta cabin plus ELECTRIFICATION OF PORTA CABIN COMPLEX	
SECTION -C	Total of Section C - CONSTRUCTION OF FOUNDATION OF ONE CLOSED SHED	

PRICE BID FOR ENABLING WORKS : FENCING OF OPEN STORAGE YARD WITH GATES, CONSTRUCTION OF CLOSED STORAGE SHED AND ITS INTERNAL ELECTRIFICATIONS ETC. ALL COMPLETE AT DAHEJ							
SECTION	SL.NO	DESCRIPTION OF WORK	UNIT	QTY	RATE IN FIGURES (In Rs)	RATE IN WORDS (In Rs)	TOTAL AMOUNT (In Rs)
SECTION-D		Total of Section D - INTERNAL AND EXTERNAL ELECTRIFICATION FOR THE ABOVE					
		GRAND TOTAL OF (ALL SECTIONS A TO D) IN RS.					
(GRAND TOTAL IN WORDS Rs.ONLY)							